



SIEMENS LOW VOLTAGE UN-ASSEMBLED MOBILE HOME LOAD CENTER PANEL. BOX FACTORY INSTALLED MAIN BREAKER 12 (1 INCH) SPACES INTERIOR ALLOWING 24 MAX CIRCUITS. 1-PHASE 3-WIRE SYSTEM RATED 120/240V (100A). SPECIAL FEATURES: FACTORY INSTALLED GROUND BAR.

last modified:

10/21/2022 

