

# GE LAMPS CATALOG

LED & TRADITIONAL

2026

Current

# **Table** of Contents


**INTRO: WE ARE ..... 4**
**SELECTABLE LED LAMPS ..... 6**
**LED LAMPS ..... 8**

LED Lamps - Tubes ..... 9
- **Type A (Ballast Compatible) ..... 12**
- **Type A+B (Dual Mode) ..... 17**
- **Type B (Ballast Bypass) ..... 18**
- **Type C (Remote Driver) ..... 34**

LED Lamps - HID ..... 38
- **LED HID for Hazardous Locations ..... 54**

LED Lamps - Plug-in ..... 58
- **Type A (Ballast Compatible) ..... 58**
- **Type B (Ballast Bypass) ..... 62**

LED Lamps - Directional ..... 70
- **PARs ..... 70**
- **MR16s ..... 78**
- **RS Cans ..... 80**
- **Reflectors ..... 82**

LED Lamps - General Purpose ..... 84
- **A-line ..... 84**
- **Decorative ..... 90**

# TRADITIONAL LAMPS & BALLASTS..... 94


Traditional Lamps..... 95
- Linear Fluorescent Lamps ..... 96
- High Intensity Discharge Lamps ..... 102
- Compact Fluorescent Lamps..... 112
- Halogen Lamps..... 116
- Incandescent Lamps ..... 119

Ballasts..... 123
- Linear Fluorescent Ballasts..... 124
- Compact Fluorescent Ballasts ..... 146
- Electromagnetic HID Ballasts ..... 148

**APPENDIX..... 161**
**GLOSSARY OF TERMS .....162**
**COLOR SAMPLES .....165**


GE lamps provide unmatched
**peace of mind.**



# We are:


## COMPLETE

Current's comprehensive offering of GE lamps includes high performance LED lighting solutions in addition to popular Traditional products. GE lamps cover a wide range of Linear Fluorescent, High Intensity Discharge, Compact Fluorescent, Halogen, Incandescent and Ballast applications.



## INNOVATIVE

Current's exceptional engineering professionals use deep knowledge of Traditional lamp applications to create industry-leading LED lamps that provide the right amount of light while saving energy and lasting longer. Use them to transform the look and efficiency of your facilities.



# DEPENDABLE

GE lamps have provided the exceptional light quality that you know and love for years. Current's engineers continue to develop reliable GE LED Lamps that fit Traditional applications and meet industry standards for equivalency claims.



# TRUSTED

A reputation for quality and reliability is our legacy. Current continues the proud tradition today, creating GE LED Lamps that last up to 70,000 hours and delivering superior solutions for even the most challenging replacement lamp applications.



# **Selectable** LED Lamps




## Lumen**Choice**®

Optimize light levels and power consumption instantly, maximizing energy savings immediately


Make lumen/wattage selections easily at any time with integrated switch, no tools required

# Lumen**Choice**® + Spectra**Choice**™

## Spectra**Choice**™

Match the color of lighting across a facility or choose to change the aesthetic of a space

Make color temperature selections easily at any time with integrated switch, no tools required




pg. 20
LED Tubes

### Reduce Inventory

Reduce SKU count and inventory dollars

### Simplify Projects

Simplify BOMs, project management, MRO

Maintain utility rebates

### Optimize Solutions

Create flexibility for

installers to react on-site

Take **control** of your lighting & inventory with our full line of Selectable **LED Lamps**



pg. 42

LED HID



pg. 60

LED Plug-In



pg. 72

LED PAR Lamps



pg. 80

LED RS Cans



pg. 82

LED Reflectors




pg. 85

LED A-Line


# **LED** Lamps




## Lamp **Drawings** (not drawn to scale)




**T5 (5/8" diameter) Miniature Bi-Pin Base (G5)**




**T8 (1" diameter) Medium Bi-Pin Base (G13)**




**T8 (1" diameter) Single Pin Base (Fa8)**



**T8 (1" diameter) Recessed Double Contact Base (R17d)**



**T8 (1" diameter) U6 Medium Bi-Pin Base (2G13)**




**T8 (1" diameter) U1-5/8 Medium Bi-Pin Base (2G13)**


## Base **Identification** (not drawn to scale)




**Min BiPin G5**



**Med BiPin G13**



**Single Pin Fa8**



**Recessed Double Contact R17D**

# **LED Lamps** - Tubes

**LED Tubes,** sometimes referred to as "TLEDs," are meant to use linear fluorescent sockets and fixtures. LED Tubes have the same length and pins as the linear fluorescent lamps they are intended to replace. The details of how the fixture is wired and the auxiliary equipment used may vary, depending on the LED Tube solution.

The lighting industry refers to three basic Types of LED Tubes:

- **Type A LED Tubes** are intended to be used as direct replacements for linear fluorescent lamps, with no modification to the fixture. Type A LED Tubes operate from fluorescent ballasts.
- **Type B LED Tubes** operate from mains voltage. The ballast is bypassed and the fixture is re-wired according to the installation instructions that come with the lamp. Wiring may vary across Type B LED Tubes from different manufacturers. A retrofit fixture label indicating the LED Tube used and that the fixture has been re-wired is provided to be applied to the fixture.
- **Type C LED Tubes** operate from dedicated remote (external) LED drivers. Instead of a ballast, a remote driver is used to provide the proper voltage and current for the Type C LED Tubes. A retrofit fixture label indicating the LED Tube and Driver used is provided to be applied to the fixture. Type C LED Tube and Driver solutions vary across the industry – they are not yet standardized like linear fluorescent lamps and ballasts.

There are also "hybrid" lamps that can cover multiple Types of LED Tubes, depending on how they are implemented.

Current offers a wide range of GE LED Tubes to replace linear fluorescent lamps, including all of the Types above. Each Type of LED Tube offers different advantages, so the right solution may vary by application.

## Which LED Tube is right for you?

A basic comparison of the Types of LED Tubes is provided below. For more detailed information, please contact your Current sales representative.

### Ballast Compatible (UL Type A)


**Easy Plug & Play**



- Uses fluorescent ballast
- No re-wiring required
- Low installation cost
- Direct replacement (lamp)
- Dimming limited by ballast
- Check compatibility

### Ballast Bypass (UL Type B)

**Simple Long-Term Solution**



- Uses no ballast / driver
- Re-wire to bypass ballast
- Low future maintenance
- Retrofit Kit (lamp, label)
- Dimming impractical
- Consider misapplication fuse

### External LED Driver (UL Type C)







**Robust & Flexible System**



- Uses external LED driver
- Replace ballast with driver
- Low voltage output
- Retrofit Kit (lamp, label, driver)
- Dimming driver (0-10V)
- Field-tunable driver settings

## LED Tube Wiring Basics:

The wiring diagrams below are provided as general guidance for GE LED Tubes. Other manufacturers' may vary. Refer to installation guides provided with GE LED Tubes for more detailed directions. If sockets are in good condition, no socket replacement should be necessary for GE LED Tubes. Add a jumper to non-shunted sockets, or tie both wires from a non-shunted socket to the incoming power as shown.

| | Ballast Compatible (UL Type A) | Ballast Bypass (UL Type B) | External LED Driver (UL Type C) |
|---|---|---|---|
| | **Follow Ballast Wiring Diagram**<br>High Voltage Ballast Output to Sockets | **Follow Lamp Wiring Diagram**<br>Mains Voltage AC to Sockets | **Follow Driver Wiring Diagram**<br>Low Voltage DC Driver Output to Sockets |
| **Shunted Sockets** (Used with Instant Start Ballasts) |  |  |  |
| **Non-Shunted Sockets** (Used with Programmed Start Ballasts) |  |  |  |

## LED Tube Construction, Coating, & covRguard®:

GE LED Tubes are primarily constructed of glass tubes with an internal coating for diffusion. This is similar to linear fluorescent construction that has been used for decades. Glass is a stable material and works well for most applications. The coating inside the glass provides good diffusion, spreading out the light and eliminating hot spots and pixilation from the individual LEDs.


GE LED Tubes are also offered with PET coating. This white coating is heat-shrunk onto a clear glass tube. Diffusion is supplied by the PET coating, which also provides some shatter resistance. These lamps are NSF Splash Zone rated.

GE LED Tubes are also available with covRguard®. Similar to covRguard® on linear fluorescent lamps, a polycarbonate sleeve is applied over the glass tube and affixed to the lamp end caps. This construction provides excellent shatter protection. These lamps are NSF Food Zone (Non-contact) rated.



## LED Tubes - Type A

GE Type A LED Tubes offer a fast and easy upgrade to LED. No modification to the fixture is necessary. Simply replace the linear fluorescent lamp with the Type A LED Tube. The ballast remains in the circuit, powering the lamps. Confirm ballast compatibility at www.LED.com/LEDTUBES-ballast-compatibility.



# **LED Lamps** - Tubes - Type A

## Catalog Logic:

**Bulb Shape:** Bulb shape followed by its size (the maximum diameter of the bulb expressed in eighths of an inch).

**Base Type:** ANSI Base

**Lamp Watts:** Typical Lamp Watts on Normal Ballast Factor (does not include ballast consumption)

**Order Code:** Use the order code when ordering to ensure that you receive the exact product you require

**Description:** Lamp Model Description

**Carton Quantity:** Number of lamps packed in a carton

**MOL (in):** Maximun Overall Length in inches

**System Watts:** Total input watts, including ballast and lamp consumption typical of each Ballast Factor

**Lumens (initial):** Typical lamp lumens when operating on each Ballast Factor

**Color Temperature (K):** A measure of the visual "warmth" or "coolness" of the light from the lamp. The higher the value, the whiter or "cooler" the light appears.

**Color Rendering Index (CRI or R):** An indication of the ability of the lamp to render object colors in a normal natural way. The higher the number (0-100), the better the color appearance.

**Rated Life L70:** Hours of operation the lamp will provide before reaching 70% of its original lumen output

**DLC:** Indicates whether product is listed on the DesignLights Consortium® Qualified Products List

**Location Rating:** Location Rating as defined for LED Lamps by UL 1993

**Additional Information:** Typical application and/ or other important information.

| | | | | | | | Low Ballast Factor | | Normal Ballast Factor | | High Ballast Factor | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Bulb Shape** | **Base Type** | **Lamp Watts[5]** | **Order Code** | **Description** | **Carton Qty[2]** | **MOL (in)** | System Watts | Lumens (Initial) | **System Watts** | **Lumens (Initial)** | System Watts | Lumens (Initial) | **Color Temp (Initial)** | **CRI** | **Rated Life L70 (Hrs)[1]** | **DLC[4]** | **Location Rating[3]** | **Additional Information** |
| **Integrated 4ft Glass Tubes (operates on Instant Start or Program Start Ballast)** | | | | | | | | | | | | | | | | | | |
| **T8** | **G13** | **18** | **35767** | **LED18ET8/G/4/830** | **20** | **48** | 17 | 2100 | **20** | **2500** | 26 | 3250 | **3000K** | **80** | **70,000** | **Yes** | **Damp** | **Instant or PRS Ballast** |

**LED18ET8/G/4/830**

- Wattage
- **E** = Type A ("**E**" = Electronic ballast)
- Bulb Shape
- "G" indicates Glass tube
- Length in feet
- CRI (8 = 80)
- CCT (30 = 3000K)

## Integrated Glass Tubes - Type A

| Bulb Shape | Base Type | Lamp Watts[5] | Order Code | Description | Carton Qty[2] | MOL (in) | Low Ballast Factor System Watts | Low Ballast Factor Lumens (Initial) | Normal Ballast Factor System Watts | Normal Ballast Factor Lumens (Initial) | High Ballast Factor System Watts | High Ballast Factor Lumens (Initial) | Color Temp (Initial) | CRI | Rated Life L70 (Hrs)[1] | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Integrated 4ft Glass Tubes (operates on Instant Start or Program Start Ballast)** | | | | | | | | | | | | | | | | | | |
| T8 | G13 | 18 | 35767 | LED18ET8/G/4/830 | 20 | 48 | 17 | 2100 | 20 | 2500 | 26 | 3250 | 3000K | 80 | 70,000 | PXTA9H72 | Damp | |
| | G13 | 18 | 35768 | LED18ET8/G/4/835 | 20 | 48 | 17 | 2100 | 20 | 2500 | 26 | 3250 | 3500K | 80 | 70,000 | P3FTDF97 | Damp | |
| | G13 | 18 | 35769 | LED18ET8/G/4/840 | 20 | 48 | 17 | 2150 | 20 | 2600 | 26 | 3400 | 4000K | 80 | 70,000 | P9HNH1U8 | Damp | |
| | G13 | 18 | 35772 | LED18ET8/G/4/850 | 20 | 48 | 17 | 2150 | 20 | 2600 | 26 | 3400 | 5000K | 80 | 70,000 | PMHB5Y1H | Damp | |
| | G13 | 18 | 35773 | LED18ET8/G/4/865 | 20 | 48 | 17 | 2150 | 20 | 2600 | 26 | 3400 | 6500K | 80 | 70,000 | - | Damp | |
| | G13 | 15 | 35790 | LED15ET8/G/4/830 | 20 | 48 | 15 | 1850 | 17 | 2150 | 23 | 2900 | 3000K | 80 | 70,000 | PNH7QX7P | Damp | |
| | G13 | 15 | 35791 | LED15ET8/G/4/835 | 20 | 48 | 15 | 1850 | 17 | 2200 | 23 | 2950 | 3500K | 80 | 70,000 | PC3FZA9X | Damp | |
| | G13 | 15 | 35793 | LED15ET8/G/4/840 | 20 | 48 | 15 | 1950 | 17 | 2300 | 23 | 3100 | 4000K | 80 | 70,000 | PXTTMVUC | Damp | |
| | G13 | 15 | 35797 | LED15ET8/G/4/850 | 20 | 48 | 15 | 1950 | 17 | 2300 | 23 | 3100 | 5000K | 80 | 70,000 | PDHK69J3 | Damp | |
| | G13 | 15 | 35798 | LED15ET8/G/4/865 | 20 | 48 | 15 | 1950 | 17 | 2300 | 23 | 3100 | 6500K | 80 | 70,000 | - | Damp | |
| | G13 | 10 | 34277 | LED10ET8/G/4/830 | 20 | 48 | 11.5 | 1350 | 13 | 1600 | 17.5 | 2100 | 3000K | 80 | 70,000 | - | Damp | |
| | G13 | 10 | 34279 | LED10ET8/G/4/835 | 20 | 48 | 11.5 | 1400 | 13 | 1600 | 17.5 | 2150 | 3500K | 80 | 70,000 | PRHQNZN1 | Damp | |
| | G13 | 10 | 34280 | LED10ET8/G/4/840 | 20 | 48 | 11.5 | 1450 | 13 | 1700 | 17.5 | 2300 | 4000K | 80 | 70,000 | P7YZ0A29 | Damp | |
| | G13 | 10 | 34282 | LED10ET8/G/4/850 | 20 | 48 | 11.5 | 1450 | 13 | 1700 | 17.5 | 2300 | 5000K | 80 | 70,000 | PSVXE1E0 | Damp | |
| **Integrated 4ft Value Glass Tubes (operates on Instant Start or Program Start Ballast)** | | | | | | | | | | | | | | | | | | |
| T8 | G13 | 14 | 34283 | LED14ET8/G/4/830 | 20 | 48 | 15 | 1700 | 17 | 2050 | 23 | 2700 | 3000K | 80 | 50,000 | P8P45K7K | Damp | |
| | G13 | 14 | 34289 | LED14ET8/G/4/835 | 20 | 48 | 15 | 1700 | 17 | 2050 | 23 | 2700 | 3500K | 80 | 50,000 | PKO4WU91 | Damp | |
| | G13 | 14 | 34291 | LED14ET8/G/4/840 | 20 | 48 | 15 | 1750 | 17 | 2100 | 23 | 2750 | 4000K | 80 | 50,000 | PLVH468G | Damp | |
| | G13 | 14 | 34300 | LED14ET8/G/4/850 | 20 | 48 | 15 | 1750 | 17 | 2100 | 23 | 2750 | 5000K | 80 | 50,000 | P1XYY7L6 | Damp | |
| | G13 | 11 | 93107390 | LED11ET8/G/4/830 | 20 | 48 | 12.5 | 1450 | 14 | 1700 | 19 | 2300 | 3000K | 80 | 50,000 | - | Damp | |
| | G13 | 11 | 93107391 | LED11ET8/G/4/835 | 20 | 48 | 12.5 | 1450 | 14 | 1700 | 19 | 2300 | 3500K | 80 | 50,000 | PTB81YWO | Damp | |
| | G13 | 11 | 93107392 | LED11ET8/G/4/840 | 20 | 48 | 12.5 | 1450 | 14 | 1700 | 19 | 2300 | 4000K | 80 | 50,000 | PTIWPW1J | Damp | |
| | G13 | 11 | 93107393 | LED11ET8/G/4/850 | 20 | 48 | 12.5 | 1450 | 14 | 1700 | 19 | 2300 | 5000K | 80 | 50,000 | PZ9A65MO | Damp | |
| **Integrated 3ft Glass Tubes (operates on Instant Start or Program Start Ballast)** | | | | | | | | | | | | | | | | | | |
| T8 | G13 | 10.5 | 35783 | LED11ET8/G/3/830 | 20 | 36 | 11.5 | 1350 | 13 | 1600 | 18 | 2150 | 3000K | 80 | 70,000 | PCEIN3O5 | Damp | |
| | G13 | 10.5 | 35784 | LED11ET8/G/3/835 | 20 | 36 | 11.5 | 1350 | 13 | 1600 | 18 | 2150 | 3500K | 80 | 70,000 | PL2XF8BQ | Damp | |
| | G13 | 10.5 | 35788 | LED11ET8/G/3/840 | 20 | 36 | 11.5 | 1350 | 13 | 1600 | 18 | 2150 | 4000K | 80 | 70,000 | PFERF8MX | Damp | |
| | G13 | 10.5 | 35789 | LED11ET8/G/3/850 | 20 | 36 | 11.5 | 1400 | 13 | 1650 | 18 | 2250 | 5000K | 80 | 70,000 | PQKLCP9K | Damp | |
| **Integrated 2ft Glass Tubes (operates on Instant Start or Program Start Ballast)** | | | | | | | | | | | | | | | | | | |
| T8 | G13 | 8.5 | 35775 | LED8ET8/G/2/830 | 20 | 24 | 9.5 | 1200 | 11 | 1350 | 15 | 1850 | 3000K | 80 | 70,000 | - | Damp | |
| | G13 | 8.5 | 35776 | LED8ET8/G/2/835 | 20 | 24 | 9.5 | 1200 | 11 | 1350 | 15 | 1850 | 3500K | 80 | 70,000 | PJDHZYEY | Damp | |
| | G13 | 8.5 | 35778 | LED8ET8/G/2/840 | 20 | 24 | 9.5 | 1200 | 11 | 1350 | 15 | 1850 | 4000K | 80 | 70,000 | P557S4DE | Damp | |
| | G13 | 8.5 | 35779 | LED8ET8/G/2/850 | 20 | 24 | 9.5 | 1200 | 11 | 1400 | 15 | 1950 | 5000K | 80 | 70,000 | PU5UYRCN | Damp | |

## Metric Integrated Glass Tubes - Type A

| Bulb Shape | Base Type | Lamp Watts[5] | Order Code | Description | Carton Qty[2] | MOL (in) | Low Ballast Factor System Watts | Low Ballast Factor Lumens (Initial) | Normal Ballast Factor System Watts | Normal Ballast Factor Lumens (Initial) | High Ballast Factor System Watts | High Ballast Factor Lumens (Initial) | Color Temp (Initial) | CRI | Rated Life L70 (Hrs)[1] | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Metric Integrated Glass Tubes (operates on Instant Start or Program Start Ballast)** | | | | | | | | | | | | | | | | | | |
| T8 | G13 | 14 | 93312131 | LED14ET8/G/835/METRIC | 20 | 45.67 | 15 | 1700 | 17 | 2050 | 23 | 2700 | 3500K | 80 | 50,000 | - | Damp | |
| | G13 | 14 | 93312133 | LED14ET8/G/840/METRIC | 20 | 45.67 | 15 | 1750 | 17 | 2100 | 23 | 2750 | 4000K | 80 | 50,000 | - | Damp | |

## Integrated Plastic Tubes - Type A

| Bulb Shape | Base Type | Lamp Watts[5] | Order Code | Description | Carton Qty[2] | MOL (in) | Low Ballast Factor System Watts | Low Ballast Factor Lumens (Initial) | Normal Ballast Factor System Watts | Normal Ballast Factor Lumens (Initial) | High Ballast Factor System Watts | High Ballast Factor Lumens (Initial) | Color Temp (Initial) | CRI | Rated Life L70 (Hrs)[1] | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Integrated U6 Plastic Tubes (operates on Instant Start or Program Start Ballast)** | | | | | | | | | | | | | | | | | | |
| T8-U6 | 2G13 | 13 | 43120 | LED13ET8/U6/830 | 12 | 22.5 | 13 | 1500 | 15 | 1800 | 20.5 | 2400 | 3000K | 80 | 50,000 | P4CDITRI | Damp | |
| | 2G13 | 13 | 43125 | LED13ET8/U6/835 | 12 | 22.5 | 13 | 1550 | 15 | 1850 | 20.5 | 2450 | 3500K | 80 | 50,000 | PFX71YXR | Damp | |
| | 2G13 | 13 | 43129 | LED13ET8/U6/840 | 12 | 22.5 | 13 | 1600 | 15 | 1900 | 20.5 | 2500 | 4000K | 80 | 50,000 | PTEX0PXE | Damp | |
| | 2G13 | 13 | 43130 | LED13ET8/U6/850 | 12 | 22.5 | 13 | 1600 | 15 | 1900 | 20.5 | 2500 | 5000K | 80 | 50,000 | PSF41B80 | Damp | |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[4] Not all product variations on this page are DLC qualified. Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
[5] Bare lamp wattage operated on Normal Ballast Factor. Measured performance on Low (0.78), Normal (0.88) and High (1.18) Ballast Factors is provided for reference. Performance may vary depending on ballast model and age. Check ballast compatibility at www.LED.com/LEDTUBES-ballast-compatibility.
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## Integrated covRguard® Plastic Sleeved Glass Tubes - Type A

| Bulb Shape | Base Type | Lamp Watts[5] | Order Code | Description | Carton Qty[2] | MOL (in) | Low Ballast Factor System Watts | Low Ballast Factor Lumens (Initial) | Normal Ballast Factor System Watts | Normal Ballast Factor Lumens (Initial) | High Ballast Factor System Watts | High Ballast Factor Lumens (Initial) | Color Temp (Initial) | CRI | Rated Life L70 (Hrs)[1] | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Integrated 4ft covRguard® Plastic Sleeved Glass Tubes (operates on Instant Start or Program Start Ballast)** | | | | | | | | | | | | | | | | | | |
| T8 | G13 | 18 | 93135924 | LED18ET8/G/4/830CVG | 20 | 48 | 17 | 2050 | 20 | 2450 | 26 | 3200 | 3000K | 80 | 70,000 | PWZVF5VO | Damp | NSF Food Zone |
| | G13 | 18 | 93135946 | LED18ET8/G/4/835CVG | 20 | 48 | 17 | 2100 | 20 | 2500 | 26 | 3250 | 3500K | 80 | 70,000 | PF5EUKL2 | Damp | NSF Food Zone |
| | G13 | 18 | 93135947 | LED18ET8/G/4/840CVG | 20 | 48 | 17 | 2100 | 20 | 2500 | 26 | 3250 | 4000K | 80 | 70,000 | PSKVG35W | Damp | NSF Food Zone |
| | G13 | 18 | 93135948 | LED18ET8/G/4/850CVG | 20 | 48 | 17 | 2150 | 20 | 2600 | 26 | 3400 | 5000K | 80 | 70,000 | P65JROO4 | Damp | NSF Food Zone |
| | G13 | 15 | 93135823 | LED15ET8/G/4/835CVG | 20 | 48 | 15 | 1850 | 17 | 2200 | 23 | 2950 | 3500K | 80 | 70,000 | PYIS7JSD | Damp | NSF Food Zone |
| | G13 | 15 | 93135824 | LED15ET8/G/4/840CVG | 20 | 48 | 15 | 1850 | 17 | 2200 | 23 | 2950 | 4000K | 80 | 70,000 | PPXC7238 | Damp | NSF Food Zone |
| | G13 | 15 | 93135846 | LED15ET8/G/4/850CVG | 20 | 48 | 15 | 1900 | 17 | 2250 | 23 | 3000 | 5000K | 80 | 70,000 | PU8LNXAM | Damp | NSF Food Zone |
| | G13 | 10 | 93135714 | LED10ET8/G/4/835CVG | 20 | 48 | 11.5 | 1400 | 13 | 1600 | 17.5 | 2150 | 3500K | 80 | 70,000 | PUCLMBOV | Damp | NSF Food Zone |
| | G13 | 10 | 93135715 | LED10ET8/G/4/840CVG | 20 | 48 | 11.5 | 1400 | 13 | 1600 | 17.5 | 2150 | 4000K | 80 | 70,000 | PUW18WQG | Damp | NSF Food Zone |
| | G13 | 10 | 93135716 | LED10ET8/G/4/850CVG | 20 | 48 | 11.5 | 1400 | 13 | 1650 | 17.5 | 2250 | 5000K | 80 | 70,000 | PI7FRGBP | Damp | NSF Food Zone |
| **Integrated 3ft covRguard® Plastic Sleeved Glass Tubes (operates on Instant Start or Program Start Ballast)** | | | | | | | | | | | | | | | | | | |
| T8 | G13 | 10.5 | 93135659 | LED11ET8/G/3/835CVG | 20 | 36 | 11.5 | 1350 | 13 | 1600 | 18 | 2150 | 3500K | 80 | 70,000 | PSBVQAZE | Damp | NSF Food Zone |
| | G13 | 10.5 | 93135660 | LED11ET8/G/3/840CVG | 20 | 36 | 11.5 | 1350 | 13 | 1600 | 18 | 2150 | 4000K | 80 | 70,000 | P5QTVCPX | Damp | NSF Food Zone |
| | G13 | 10.5 | 93135661 | LED11ET8/G/3/850CVG | 20 | 36 | 11.5 | 1400 | 13 | 1650 | 18 | 2250 | 5000K | 80 | 70,000 | PJ78M875 | Damp | NSF Food Zone |
| **Integrated 2ft covRguard® Plastic Sleeved Glass Tubes (operates on Instant Start or Program Start Ballast)** | | | | | | | | | | | | | | | | | | |
| T8 | G13 | 8.5 | 93135655 | LED8ET8/G/2/835CVG | 20 | 24 | 9.5 | 1200 | 11 | 1350 | 15 | 1850 | 3500K | 80 | 70,000 | PVDR8UFU | Damp | NSF Food Zone |
| | G13 | 8.5 | 93135656 | LED8ET8/G/2/840CVG | 20 | 24 | 9.5 | 1200 | 11 | 1350 | 15 | 1850 | 4000K | 80 | 70,000 | PDP040JM | Damp | NSF Food Zone |
| | G13 | 8.5 | 93135657 | LED8ET8/G/2/850CVG | 20 | 24 | 9.5 | 1200 | 11 | 1350 | 15 | 1850 | 5000K | 80 | 70,000 | P0Y2CIVW | Damp | NSF Food Zone |

## Integrated PET Plastic Coated Glass Tubes - Type A

| Bulb Shape | Base Type | Lamp Watts[5] | Order Code | Description | Carton Qty[2] | MOL (in) | Low Ballast Factor System Watts | Low Ballast Factor Lumens (Initial) | Normal Ballast Factor System Watts | Normal Ballast Factor Lumens (Initial) | High Ballast Factor System Watts | High Ballast Factor Lumens (Initial) | Color Temp (Initial) | CRI | Rated Life L70 (Hrs)[1] | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Integrated 4ft PET Plastic Coated Glass Tubes (operates on Instant Start or Program Start Ballast)** | | | | | | | | | | | | | | | | | | |
| T8 | G13 | 14 | 93107394 | LED14ET8/G4/830CT | 20 | 48 | 15 | 1700 | 17 | 2050 | 23 | 2700 | 3000K | 80 | 50,000 | - | Damp | NSF Splash Zone |
| | G13 | 14 | 93107506 | LED14ET8/G4/835CT | 20 | 48 | 15 | 1700 | 17 | 2050 | 23 | 2700 | 3500K | 80 | 50,000 | PG06MMSK | Damp | NSF Splash Zone |
| | G13 | 14 | 93107507 | LED14ET8/G4/840CT | 20 | 48 | 15 | 1750 | 17 | 2100 | 23 | 2750 | 4000K | 80 | 50,000 | PI234OJJ | Damp | NSF Splash Zone |
| | G13 | 14 | 93107510 | LED14ET8/G4/850CT | 20 | 48 | 15 | 1750 | 17 | 2100 | 23 | 2750 | 5000K | 80 | 50,000 | PJ6AUR4D | Damp | NSF Splash Zone |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[4] Not all product variations on this page are DLC qualified. Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
[5] Bare lamp wattage operated on Normal Ballast Factor. Measured performance on Low (0.78), Normal (0.88) and High (1.18) Ballast Factors is provided for reference. Performance may vary depending on ballast model and age. Check ballast compatibility at www.LED.com/LEDTUBES-ballast-compatibility.
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## Integrated Glass Tubes - Type A - T5

| Bulb Shape | Base Type | Lamp Watts[5] | Order Code | Description | Carton Qty[2] | MOL (In) | System Watts (BF=1.0) | Lumens (Initial) | Color Temp. (Initial) | CRI | Rated Life L70 (Hrs)[1] | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Integrated 4ft T5 HO Glass Tubes (operates on T5 Ballast)** | | | | | | | | | | | | | | |
| T5 | G5 | 25.5 | 19203 | LED26ET5/G/4/830 | 20 | 46 | 32 | 3650 | 3000K | 80 | 50,000 | PWNBNEB9 | Damp | Requires T5 HO Ballast |
| | G5 | 25.5 | 19221 | LED26ET5/G/4/835 | 20 | 46 | 32 | 3750 | 3500K | 80 | 50,000 | POB2VN8V | Damp | Requires T5 HO Ballast |
| | G5 | 25.5 | 19227 | LED26ET5/G/4/840 | 20 | 46 | 32 | 3800 | 4000K | 80 | 50,000 | PUS7DGWC | Damp | Requires T5 HO Ballast |
| | G5 | 25.5 | 19348 | LED26ET5/G/4/850 | 20 | 46 | 32 | 3900 | 5000K | 80 | 50,000 | P99UF0I0 | Damp | Requires T5 HO Ballast |
| | G5 | 25.5 | 19488 | LED26ET5/G/4/865 | 20 | 46 | 32 | 3800 | 6500K | 80 | 50,000 | - | Damp | Requires T5 HO Ballast |
| **Integrated 2ft T5 HO Glass Tubes (operates on T5 Ballast)** | | | | | | | | | | | | | | |
| T5 | G5 | 11 | 34413 | LED11ET5/G/2/830 | 20 | 22 | 13.5 | 1500 | 3000K | 80 | 50,000 | - | Damp | Requires T5 HO Ballast |
| | G5 | 11 | 34417 | LED11ET5/G/2/835 | 20 | 22 | 13.5 | 1550 | 3500K | 80 | 50,000 | - | Damp | Requires T5 HO Ballast |
| | G5 | 11 | 34418 | LED11ET5/G/2/840 | 20 | 22 | 13.5 | 1600 | 4000K | 80 | 50,000 | - | Damp | Requires T5 HO Ballast |
| | G5 | 11 | 34424 | LED11ET5/G/2/850 | 20 | 22 | 13.5 | 1600 | 5000K | 80 | 50,000 | - | Damp | Requires T5 HO Ballast |
| **Integrated 4ft T5 HE Glass Tubes (operates on T5 Ballast)** | | | | | | | | | | | | | | |
| T5 | G5 | 13 | 34351 | LED13ET5G4/830HE | 20 | 46 | 16 | 1900 | 3000K | 80 | 50,000 | P3D2AHME | Damp | Requires T5 HE Ballast |
| | G5 | 13 | 34354 | LED13ET5G4/835HE | 20 | 46 | 16 | 1950 | 3500K | 80 | 50,000 | P9QL3V95 | Damp | Requires T5 HE Ballast |
| | G5 | 13 | 34355 | LED13ET5G4/840HE | 20 | 46 | 16 | 2000 | 4000K | 80 | 50,000 | PIN820KS | Damp | Requires T5 HE Ballast |
| | G5 | 13 | 34367 | LED13ET5G4/850HE | 20 | 46 | 16 | 2000 | 5000K | 80 | 50,000 | PXRH4DM6 | Damp | Requires T5 HE Ballast |
| **Integrated 3ft T5 HE Glass Tubes (operates on T5 Ballast)** | | | | | | | | | | | | | | |
| T5 | G5 | 10 | 34371 | LED10ET5G3/830HE | 20 | 34 | 13 | 1500 | 3000K | 80 | 50,000 | - | Damp | Requires T5 HE Ballast |
| | G5 | 10 | 34376 | LED10ET5G3/835HE | 20 | 34 | 13 | 1550 | 3500K | 80 | 50,000 | - | Damp | Requires T5 HE Ballast |
| | G5 | 10 | 34401 | LED10ET5G3/840HE | 20 | 34 | 13 | 1600 | 4000K | 80 | 50,000 | - | Damp | Requires T5 HE Ballast |
| | G5 | 10 | 34402 | LED10ET5G3/850HE | 20 | 34 | 13 | 1600 | 5000K | 80 | 50,000 | - | Damp | Requires T5 HE Ballast |
| **Integrated 2ft T5 HE Glass Tubes (operates on T5 Ballast)** | | | | | | | | | | | | | | |
| T5 | G5 | 7 | 34403 | LED7ET5/G2/830HE | 20 | 22 | 10 | 1000 | 3000K | 80 | 50,000 | - | Damp | Requires T5 HE Ballast |
| | G5 | 7 | 34404 | LED7ET5/G2/835HE | 20 | 22 | 10 | 1100 | 3500K | 80 | 50,000 | - | Damp | Requires T5 HE Ballast |
| | G5 | 7 | 34411 | LED7ET5/G2/840HE | 20 | 22 | 10 | 1150 | 4000K | 80 | 50,000 | - | Damp | Requires T5 HE Ballast |
| | G5 | 7 | 34412 | LED7ET5/G2/850HE | 20 | 22 | 10 | 1150 | 5000K | 80 | 50,000 | - | Damp | Requires T5 HE Ballast |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[4] Not all product variations on this page are DLC qualified. Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
[5] Bare lamp wattage operated on T5 Ballasts. Measured performance on T5 ballasts (Ballast Factor = 1.0) is provided for reference. Performance may vary depending on ballast model and age.
Check ballast compatibility at www.LED.com/LEDTUBES-ballast-compatibility.
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## Dual Mode PET Plastic Coated Glass Tubes - Type A+B

GE Type A+B Tubes offer the flexibility to be used in either Type A (ballast driven) or Type B (ballast bypass) applications. The notes about each separate Type apply. Type A+B Tubes might be installed as Type A and then when the ballast fails or if it is found to be incompatible, switched to Type B. To use Type A+B lamps as Type B, the same re-wiring process must be done as for Type B lamps.

## Selectable SpectraChoice™ Dual Mode PET Plastic Coated Glass Tubes - Type A+B


| | | | | | | | TYPE A MODE | | | | | | TYPE B MODE | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | Low Ballast Factor | | Normal Ballast Factor | | High Ballast Factor | | | | | | | | | | |
| Bulb Shape | Base Type | Lamp Watts[5] | Order Code | Description | Carton Qty[2] | MOL (in) | System Watts | Lumens (Initial) | System Watts | Lumens (Initial) | System Watts | Lumens (Initial) | Input Voltage | Watts | Lumens (Initial) | Power Factor | CRI | Selectable Color Temp. (Initial)* | Rated Life L70 (Hrs)[1] | DLC®[4] | Location Rating[3] |
| **Dual Mode 4ft PET Plastic Coated Glass Tubes (Type A+B)** | | | | | | | | | | | | | | | | | | | | | |
| T8 | G13 | 14.5 | 93319135 | LED14ABT8/G4/8SC | 25 | 48 | 15.5 | 1850 | 18.5 | 2200 | 26 | 2950 | 120-277 | 14.5 | 2000 | >0.9 | 80 | 3000K | 50,000 | S-L5ZXZP | Damp |
| | | | | | | | 15.5 | 1900 | 18.5 | 2250 | 26 | 3000 | 120-277 | 14.5 | 2050 | >0.9 | 80 | 3500K | 50,000 | S-L5ZXZP | Damp |
| | | | | | | | 15.5 | 1900 | 18.5 | 2250 | 26 | 3000 | 120-277 | 14.5 | 2050 | >0.9 | 80 | 4000K* | 50,000 | S-L5ZXZP | Damp |
| | | | | | | | 15.5 | 1850 | 18.5 | 2200 | 26 | 2950 | 120-277 | 14.5 | 2000 | >0.9 | 80 | 5000K | 50,000 | S-L5ZXZP | Damp |
| **Dual Mode 3ft PET Plastic Coated Glass Tubes (Type A+B)** | | | | | | | | | | | | | | | | | | | | | |
| T8 | G13 | 12 | 93320992 | LED12ABT8/G3/8SC | 25 | 36 | 10 | 1100 | 11.5 | 1350 | 17.5 | 1850 | 120-277 | 12 | 1650 | >0.9 | 80 | 3000K | 50,000 | - | Damp |
| | | | | | | | 10 | 1150 | 11.5 | 1400 | 17.5 | 1900 | 120-277 | 12 | 1650 | >0.9 | 80 | 3500K | 50,000 | - | Damp |
| | | | | | | | 10 | 1200 | 11.5 | 1450 | 17.5 | 1950 | 120-277 | 12 | 1700 | >0.9 | 80 | 4000K* | 50,000 | - | Damp |
| | | | | | | | 10 | 1200 | 11.5 | 1450 | 17.5 | 1950 | 120-277 | 12 | 1700 | >0.9 | 80 | 5000K | 50,000 | - | Damp |
| **Dual Mode 2ft PET Plastic Coated Glass Tubes (Type A+B)** | | | | | | | | | | | | | | | | | | | | | |
| T8 | G13 | 8 | 93320998 | LED8ABT8/G2/8SC | 25 | 24 | 9.5 | 1050 | 11 | 1300 | 17 | 1700 | 120-277 | 8 | 1100 | >0.9 | 80 | 3000K | 50,000 | - | Damp |
| | | | | | | | 9.5 | 1100 | 11 | 1300 | 17 | 1750 | 120-277 | 8 | 1100 | >0.9 | 80 | 3500K | 50,000 | - | Damp |
| | | | | | | | 9.5 | 1150 | 11 | 1350 | 17 | 1800 | 120-277 | 8 | 1150 | >0.9 | 80 | 4000K* | 50,000 | - | Damp |
| | | | | | | | 9.5 | 1150 | 11 | 1350 | 17 | 1800 | 120-277 | 8 | 1150 | >0.9 | 80 | 5000K | 50,000 | - | Damp |

**Selectable SpectraChoice™ Dual Mode PET Plastic Coated Glass Tubes** - Dimmer Compatibility
Lamps are dimmable on 120V on the below reverse phase dimmers.


| Brand | Model Number |
|---|---|
| **Compatible Reverse Phase Dimmer List** | |
| LUTRON | DVELV-300P-** |
| LUTRON | DVELV-303P-** |
| LUTRON | MAELV-600-** |

**If lamp holders are shunted, follow instructions for double-ended wiring.**
**If lamp holders are not shunted, single-ended or double-ended wiring may be used.**


**Double-Ended Wiring with Shunted Lamp Holders**




**Double-Ended Wiring with Non-Shunted Lamp Holders**





**Single-Ended Wiring with Non-Shunted Lamp Holders**




[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[4] Not all product variations on this page are DLC qualified. Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
[5] Bare lamp wattage operated on Normal Ballast Factor. Measured performance on Low (0.78), Normal (0.88) and High (1.18) Ballast Factors is provided for reference. Performance may vary depending on ballast model and age. Check ballast compatibility at www.LED.com/LEDTUBES-ballast-compatibility.
* Default wattage and color temperature settings noted by "*" in tables above.
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## **LED Tubes** - Type B

GE Type B LED Tubes offer a simple long-term solution for linear applications. The fixture is re-wired to bypass the ballast, taking mains voltage directly to the lampholders. This eliminates the ballast as a potential failure point, eliminates the ballast energy consumption and reduces future maintenance. GE Type B LED Tubes have multiple safety features designed into the lamp. Current also offers an external misapplication fuse kit for added protection and peace of mind.



## Catalog Logic:

**Bulb Shape:** Bulb shape followed by its size (the maximum diameter of the bulb expressed in eighths of an inch)

**Base Type:** ANSI Base

**Watts:** Energy Used (as defined by FTC Lamp Label Rules)

**Order Code:** Use the order code when ordering to ensure that you receive the exact product you require

**Description:** Lamp Model Description

**Volts:** Lamp data is based on operation at rated voltage

**Carton Quantity:** Number of lamps packed in a carton

**MOL (in):** Maximum Overall Length in inches

**Lumens:** Light output (as defined by FTC Lamp Label Rules)

**Color Temperature (K):** A measure of the visual "warmth" or "coolness" of the light from the lamp. The higher the value, the whiter or "cooler" the light appears.

**Color Rendering Index (CRI or R):** An indication of the ability of the lamp to render object colors in a normal, natural way. The higher the number (0-100), the better the color appearance.

**Rated Life L70:** Hours of operation the lamp will provide before reaching 70% of its original lumen output


**Power Factor:** A measure of the phase difference between voltage and current drawn by an electrical device

**DLC:** Indicates whether product is listed on the DesignLights Consortium® Qualified Products List

**Location Rating:** Location Rating as defined for LED Lamps by UL 1993

**Additional Information:** Typical application and/or other important information

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Rated Life L70 (Hrs)[1] | Power Factor | DLC®[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Ballast Bypass - 4ft Glass Tubes** | | | | | | | | | | | | | | | |
| T8 | G13 | 14 | 39498 | LED14BDT8/G4/840 | 120-277 | 20 | 48 | 1800 | 4000K | 80 | 50,000 | >0.9 | Yes | Damp | |



Current offers unmatched flexibility in a single **Type B LED Tube**.
Select wattage and color temperature at the flick of a switch.

LumenChoice® + SpectraChoice™ Selectable LED Tubes maximize the potential to reduce inventory and streamline product lists. These lamps allow installers to react to a wide variety of needs, providing the ability to adjust both the color temperature of the light and the brightness.

But what about when it's known a site prefers 4000K? LumenChoice® Selectable LED Tubes can be used to optimize the light levels throughout a facility with just one SKU. Reducing the wattage can save more energy and improve the comfortability of overlit spaces.




## LumenChoice®

Optimize light levels and power consumption instantly, maximizing energy savings immediately


Make lumen/wattage selections easily at any time with integrated switch, no tools required

# LumenChoice® + SpectraChoice™

## SpectraChoice™

Match the color of lighting across a facility or choose to change the aesthetic of a space

Make color temperature selections easily at any time with integrated switch, no tools required



## Ballast Bypass Selectable LumenChoice® + SpectraChoice™ Glass Tubes - Double Ended - Type B

| Bulb Shape | Base Type | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Selectable Watts* | Selectable Lumens (Initial)* | Selectable Color Temp. (Initial)* | CRI | Rated Life L70 (Hrs)[1] | Power Factor | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Ballast Bypass (Type B) - 4ft Glass Tubes** | | | | | | | | | | | | | | | |
| T8 | G13 | 93301824 | LEDLCBDT8/G4/8SC | 120-277 | 20 | 48 | 8<br>12*<br>16 | 1100<br>1600*<br>2000 | 3500K<br>4000K*<br>5000K | 80 | 70,000 | >0.9 | S-3Q0BDP | Damp | |
| | G13 | 93313525 | LEDLCBDT8/G4/8SCXL/120-347 | 120-347 | 20 | 48 | 10<br>13*<br>16 | 1650<br>2050*<br>2550 | 3000K<br>3500K<br>4000K*<br>5000K | 80 | 70,000 | >0.9 | S-3PNRN2 | Damp | |
| **Ballast Bypass (Type B) - 3ft Glass Tubes** | | | | | | | | | | | | | | | |
| T8 | G13 | 93313565 | LEDLCBDT8/G3/8SC/120-347 | 120-347 | 20 | 36 | 10<br>12*<br>14 | 1400<br>1650*<br>1800 | 3000K<br>3500K<br>4000K*<br>5000K | 80 | 70,000 | >0.9 | S-6N1DV1 | Damp | |
| **Ballast Bypass (Type B) - 2ft Glass Tubes** | | | | | | | | | | | | | | | |
| T8 | G13 | 93313567 | LEDLCBDT8/G2/8SC/120-347 | 120-347 | 20 | 24 | 7<br>9*<br>11 | 950<br>1150*<br>1350 | 3000K<br>3500K<br>4000K*<br>5000K | 80 | 70,000 | >0.9 | S-HXPL6T | Damp | |

## Ballast Bypass Selectable LumenChoice® Glass Tubes - Double Ended - Type B

| Bulb Shape | Base Type | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Selectable Watts* | Selectable Lumens (Initial)* | Color Temp. (Initial) | CRI | Rated Life L70 (Hrs)[1] | Power Factor | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Ballast Bypass (Type B) - 4ft Glass Tubes** | | | | | | | | | | | | | | | |
| T8 | G13 | 93301783 | LEDLCBDT8/G4/840 | 120-277 | 20 | 48 | 8<br>12*<br>16 | 1100<br>1600*<br>2000 | 4000K | 80 | 70,000 | >0.9 | S-Z2H9M3 | Damp | |

## Ballast Bypass Selectable SpectraChoice™ Glass Tubes - Double Ended - Type B

| Bulb Shape | Base Type | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Watts | Lumens (Initial)* | Selectable Color Temp. (Initial)* | CRI | Rated Life L70 (Hrs)[1] | Power Factor | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Ballast Bypass (Type B) - 8ft Glass Tubes** | | | | | | | | | | | | | | | |
| T8 | Fa8 | 93319020 | LED42BDT8/G8/Fa8/8SC/120-347 | 120-347 | 10 | 96 | 42 | 5300<br>5500<br>5500*<br>5400 | 3500K<br>4000K<br>5000K*<br>6500K | 80 | 50,000 | >0.9 | S-FVL70T | Damp | |
| **Ballast Bypass (Type B) - 4ft Glass Tubes** | | | | | | | | | | | | | | | |
| T8 | G13 | 93313519 | LED16BDT8/G4/8SCXL/120-347 | 120-347 | 20 | 48 | 16 | 2550 | 3000K<br>3500K<br>4000K*<br>5000K | 80 | 70,000 | >0.9 | S-Y9PPM3 | Damp | |
| | G13 | 93313501 | LED13BDT8/G4/8SCXL/120-347 | 120-347 | 20 | 48 | 13 | 2050 | 3000K<br>3500K<br>4000K*<br>5000K | 80 | 70,000 | >0.9 | S-77F6BV | Damp | |
| | G13 | 93313483 | LED10BDT8/G4/8SCXL/120-347 | 120-347 | 20 | 48 | 10 | 1650 | 3000K<br>3500K<br>4000K*<br>5000K | 80 | 70,000 | >0.9 | S-MY0H3W | Damp | |
| | G13 | 93315883 | LED14BDT8/G4/8SC | 120-277 | 20 | 48 | 14 | 1850 | 3000K<br>3500K<br>4000K*<br>5000K | 80 | 50,000 | >0.9 | S-C04HBD | Damp | |
| **Ballast Bypass (Type B) - 18 in Glass Tubes** | | | | | | | | | | | | | | | |
| T8 | G13 | 93319892 | LED7BDT8/G18/8SC/120-347 | 120-347 | 20 | 18 | 7 | 900<br>1000<br>1000<br>950 | 3000K<br>3500K<br>4000K*<br>5000K | 80 | 70,000 | >0.9 | - | Damp | |

For Selectable R17d Signage and Standard Glass Tubes, refer to page 30

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity from Current = Case Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[4] Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
* Default wattage and color temperature settings noted by "*" in tables above.
Please note Current lamps are not for sale for use in Yukon Territory in Canada




## **Metric Ballast Bypass Selectable LumenChoice® + SpectraChoice™ Glass Tubes - Double Ended** - Type B

| Bulb Shape | Base Type | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Selectable Watts* | Selectable Lumens (Initial)* | Selectable Color Temp. (Initial)* | CRI | Rated Life L70 (Hrs)[1] | Power Factor | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Ballast Bypass (Type B) - 46" Metric Glass Tubes** | | | | | | | | | | | | | | | |
| T8 | G13 | 93319902 | LEDLCBDT8/G/8SC/METRIC | 120-347 | 20 | 46 | 10 | 1,500<br>1,550<br>1,600<br>1,600 | 3000K<br>3500K<br>4000K<br>5000K | 80 | 70,000 | >0.9 | - | Damp | |
| | | | | | | | 13* | 1,800<br>1,900<br>2,000*<br>2,000 | 3000K<br>3500K<br>4000K*<br>5000K | | | | | | |
| | | | | | | | 16 | 2,350<br>2,450<br>2,500<br>2,500 | 3000K<br>3500K<br>4000K<br>5000K | | | | | | |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity from Current = Case Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[4] Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
* Default wattage and color temperature settings noted by "*" in tables above.
Please note Current lamps are not for sale for use in Yukon Territory in Canada




## Ballast Bypass Selectable LumenChoice® + SpectraChoice™ T5 Glass Tubes - Double Ended - Type B

| Bulb Shape | Base Type | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Selectable Watts* | Selectable Lumens (Initial)* | Selectable Color Temp. (Initial)* | CRI | Rated Life L70 (Hrs)[1] | Power Factor | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Ballast Bypass (Type B) - 4ft Glass Tubes** | | | | | | | | | | | | | | | |
| T5 | G5 | 93319129 | LEDLCBDT5/G4/8SC/120-347 | 120-347 | 20 | 46 | 14 | 2,000<br>2,100<br>2,200<br>2,100 | 3000K<br>3500K<br>4000K<br>5000K | 80 | 50,000 | >0.9 | S-YF01DJ | Damp | |
| | | | | | | | 20 | 2,700<br>2,800<br>2,900<br>2,800 | 3000K<br>3500K<br>4000K<br>5000K | | | | | | |
| | | | | | | | 25* | 3,200<br>3,400<br>3,500*<br>3,400 | 3000K<br>3500K<br>4000K*<br>5000K | | | | | | |
| **Ballast Bypass (Type B) - 3ft Glass Tubes** | | | | | | | | | | | | | | | |
| T5 | G5 | 93319131 | LEDLCBDT5/G3/8SC/120-347 | 120-347 | 20 | 34 | 11.5 | 1,600<br>1,650<br>1,700<br>1,700 | 3000K<br>3500K<br>4000K<br>5000K | 80 | 50,000 | >0.9 | - | Damp | |
| | | | | | | | 14.5 | 2,000<br>2,050<br>2,100<br>2,100 | 3000K<br>3500K<br>4000K<br>5000K | | | | | | |
| | | | | | | | 18* | 2,400<br>2,450<br>2,500*<br>2,500 | 3000K<br>3500K<br>4000K*<br>5000K | | | | | | |
| **Ballast Bypass (Type B) - 2ft Glass Tubes** | | | | | | | | | | | | | | | |
| T5 | G5 | 93319133 | LEDLCBDT5/G2/8SC/120-347 | 120-347 | 20 | 22 | 7 | 950<br>1,000<br>1,050<br>1,050 | 3000K<br>3500K<br>4000K<br>5000K | 80 | 50,000 | >0.9 | - | Damp | |
| | | | | | | | 9 | 1,250<br>1,300<br>1,350<br>1,350 | 3000K<br>3500K<br>4000K<br>5000K | | | | | | |
| | | | | | | | 11* | 1,500<br>1,550<br>1,600*<br>1,600 | 3000K<br>3500K<br>4000K*<br>5000K | | | | | | |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity from Current = Case Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[4] Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
* Default wattage and color temperature settings noted by "*" in tables above.
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## U1/U6 Adjustable Lamp

Lamps ship 15 per carton with U 1-5/8" tube spacing to minimize carton size




SpectraChoice™

**Select** color temperature using built-in switch.

U 1-5/8" closed position


***Two Lamps in One***

Easily transform the U 1-5/8" out of the box into a U 6" lamp by pulling apart the tubes, allowing the hinged frames to fully extend and snap into place.



Hinged frames fully extend and snap into place to transform the lamp into U 6" tube spacing

Out of the box: U 1-5/8" configuration



Pull tubes apart to transform the lamp from U 1-5/8" tube spacing to the U 6" tube spacing



U 6" configuration with hinged frames fully extended



## **Ballast Bypass Selectable SpectraChoice™ T8 U1/U6 Adjustable - Double Ended** - Type B

| Bulb Shape | Base Type | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Watts | Selectable Lumens (Initial)* | Selectable Color Temp. (Initial)* | CRI | Rated Life L70 (Hrs)[1] | Power Factor | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Ballast Bypass (Type B) - U1/U6 Adjustable Glass Tubes** | | | | | | | | | | | | | | | |
| T8 | 2G13 | 93320487 | LED13BDT8/U/U6/8SC/120-347 | 120-347 | 15 | 22.6 | 13 | 1,750<br>1,800<br>1,850*<br>1,850 | 3000K<br>3500K<br>4000K*<br>5000K | 80 | 50,000 | >0.9 | S-ZFKXK8 | Damp | Ballast Bypass |
| Patent Pending | | | | | | | | | | | | | | | |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity from Current = Case Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[4] Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
* Default wattage and color temperature settings noted by "*" in tables above.
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## Ballast Bypass UXL PET Plastic Coated Glass Tubes - Double Ended - Type B

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Rated Life L70 (Hrs)[1] | Power Factor | DLC®[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Ballast Bypass - 4ft UXL PET Plastic Coated Glass Tubes** | | | | | | | | | | | | | | | |
| T8 | G13 | 13.5 | 93322529 | LED13BDT8/G/4/835UXL | 120-277 | 20 | 48 | 2500 | 3500K | 80 | 70,000 | >0.9 | S-WPX3P1 | Damp | NSF Splash Zone |
| | G13 | 13.5 | 93322535 | LED13BDT8/G/4/840UXL | 120-277 | 20 | 48 | 2600 | 4000K | 80 | 70,000 | >0.9 | S-3PBDXH | Damp | NSF Splash Zone |
| | G13 | 13.5 | 93322505 | LED13BDT8/G/4/850UXL | 120-277 | 20 | 48 | 2600 | 5000K | 80 | 70,000 | >0.9 | S-G2CYZF | Damp | NSF Splash Zone |
| | G13 | 9.3 | 93322511 | LED9BDT8/G/4/835UXL | 120-277 | 20 | 48 | 1700 | 3500K | 80 | 70,000 | >0.9 | S-S17R4Q | Damp | NSF Splash Zone |
| | G13 | 9.3 | 93322517 | LED9BDT8/G/4/840UXL | 120-277 | 20 | 48 | 1800 | 4000K | 80 | 70,000 | >0.9 | S-Q9SVFB | Damp | NSF Splash Zone |
| | G13 | 9.3 | 93322523 | LED9BDT8/G/4/850UXL | 120-277 | 20 | 48 | 1800 | 5000K | 80 | 70,000 | >0.9 | S-3H1TMK | Damp | NSF Splash Zone |

## Ballast Bypass Glass Tubes - Single Ended or Double Ended - Type B

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Rated Life L70 (Hrs)[1] | Power Factor | DLC®[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Ballast Bypass - 4ft XL Glass Tubes - Single-Ended or Double-Ended Wiring** | | | | | | | | | | | | | | | |
| T8 | G13 | 8.5 | 93323839 | LED8BT8/G4/835XL | 120-277 | 20 | 48 | 1600 | 3500K | 80 | 50,000 | >0.9 | - | Damp | |
| | G13 | 8.5 | 93321550 | LED8BT8/G4/840XL | 120-277 | 20 | 48 | 1650 | 4000K | 80 | 50,000 | >0.9 | - | Damp | |
| | G13 | 8.5 | 93323845 | LED8BT8/G4/850XL | 120-277 | 20 | 48 | 1650 | 5000K | 80 | 50,000 | >0.9 | - | Damp | |

## Ballast Bypass Glass Tubes - Double Ended - Type B

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Rated Life L70 (Hrs)[1] | Power Factor | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Ballast Bypass - 4ft XL Glass Tubes** | | | | | | | | | | | | | | | |
| T8 | G13 | 16 | 93132588 | LED16BDT8/G4/840XL | 120-277 | 20 | 48 | 2550 | 4000K | 80 | 70,000 | >0.9 | P32UZP06 | Damp | |
| | G13 | 16 | 93132589 | LED16BDT8/G4/850XL | 120-277 | 20 | 48 | 2550 | 5000K | 80 | 70,000 | >0.9 | PI7ZR2DY | Damp | |
| | G13 | 13 | 93132554 | LED13BDT8/G4/840XL | 120-277 | 20 | 48 | 2050 | 4000K | 80 | 70,000 | >0.9 | PN3DG2KK | Damp | |
| | G13 | 13 | 93132555 | LED13BDT8/G4/850XL | 120-277 | 20 | 48 | 2050 | 5000K | 80 | 70,000 | >0.9 | P33RC00B | Damp | |
| | G13 | 9.5 | 93132549 | LED9BDT8/G4/835XL | 120-277 | 20 | 48 | 1600 | 3500K | 80 | 70,000 | >0.9 | PP3H2D0T | Damp | |
| | G13 | 9.5 | 93132550 | LED9BDT8/G4/840XL | 120-277 | 20 | 48 | 1650 | 4000K | 80 | 70,000 | >0.9 | PE3WWYH0 | Damp | |
| | G13 | 9.5 | 93132551 | LED9BDT8/G4/850XL | 120-277 | 20 | 48 | 1650 | 5000K | 80 | 70,000 | >0.9 | P4X8QYGU | Damp | |
| **Ballast Bypass - 4ft Glass Tubes** | | | | | | | | | | | | | | | |
| T8 | G13 | 16 | 93123476 | LED16BDT8/G4/830 | 120-277 | 20 | 48 | 2150 | 3000K | 80 | 50,000 | >0.9 | P9U8R2XF | Damp | |
| | G13 | 16 | 93125618 | LED16BDT8/G4/835 | 120-277 | 20 | 48 | 2200 | 3500K | 80 | 50,000 | >0.9 | PW61S4V8 | Damp | |
| | G13 | 16 | 93125620 | LED16BDT8/G4/840 | 120-277 | 20 | 48 | 2250 | 4000K | 80 | 50,000 | >0.9 | PLWETXLG | Damp | |
| | G13 | 16 | 93125622 | LED16BDT8/G4/850 | 120-277 | 20 | 48 | 2250 | 5000K | 80 | 50,000 | >0.9 | P9DPDUA6 | Damp | |
| | G13 | 14 | 39493 | LED14BDT8/G4/830 | 120-277 | 20 | 48 | 1700 | 3000K | 80 | 50,000 | >0.9 | PQJU40YO | Damp | |
| | G13 | 14 | 39494 | LED14BDT8/G4/835 | 120-277 | 20 | 48 | 1750 | 3500K | 80 | 50,000 | >0.9 | PE7DNV4V | Damp | |
| | G13 | 14 | 39498 | LED14BDT8/G4/840 | 120-277 | 20 | 48 | 1800 | 4000K | 80 | 50,000 | >0.9 | PFXFRIB9 | Damp | |
| | G13 | 14 | 39519 | LED14BDT8/G4/850 | 120-277 | 20 | 48 | 1850 | 5000K | 80 | 50,000 | >0.9 | PYXSAU7Y | Damp | |
| | G13 | 11 | 93117212 | LED11BDT8/G4/830 | 120-277 | 20 | 48 | 1600 | 3000K | 80 | 50,000 | >0.9 | - | Damp | |
| | G13 | 11 | 93117213 | LED11BDT8/G4/835 | 120-277 | 20 | 48 | 1650 | 3500K | 80 | 50,000 | >0.9 | P1AW5I1B | Damp | |
| | G13 | 11 | 93117214 | LED11BDT8/G4/840 | 120-277 | 20 | 48 | 1650 | 4000K | 80 | 50,000 | >0.9 | P3Y9GW4E | Damp | |
| | G13 | 11 | 93117215 | LED11BDT8/G4/850 | 120-277 | 20 | 48 | 1700 | 5000K | 80 | 50,000 | >0.9 | P792993K | Damp | |
| **Ballast Bypass - 3ft Glass Tubes** | | | | | | | | | | | | | | | |
| T8 | G13 | 12 | 39547 | LED12BDT8/G3/835 | 120-277 | 20 | 36 | 1500 | 3500K | 80 | 50,000 | >0.9 | P1DV4D7M | Damp | |
| | G13 | 12 | 39554 | LED12BDT8/G3/840 | 120-277 | 20 | 36 | 1550 | 4000K | 80 | 50,000 | >0.9 | POEU7LZC | Damp | |
| | G13 | 12 | 39557 | LED12BDT8/G3/850 | 120-277 | 20 | 36 | 1550 | 5000K | 80 | 50,000 | >0.9 | P1WXGHZO | Damp | |
| **Ballast Bypass - 2ft Glass Tubes** | | | | | | | | | | | | | | | |
| T8 | G13 | 9 | 39560 | LED9BDT8/G2/835 | 120-277 | 20 | 24 | 1150 | 3500K | 80 | 50,000 | >0.9 | P41DJP7N | Damp | |
| | G13 | 9 | 39561 | LED9BDT8/G2/840 | 120-277 | 20 | 24 | 1200 | 4000K | 80 | 50,000 | >0.9 | P9VLH47P | Damp | |
| | G13 | 9 | 39563 | LED9BDT8/G2/850 | 120-277 | 20 | 24 | 1200 | 5000K | 80 | 50,000 | >0.9 | PQJS5X3I | Damp | |
| **Ballast Bypass - U6 Glass Tubes - 6" leg spacing** | | | | | | | | | | | | | | | |
| T8-U6 | 2G13 | 13 | 93133050 | LED13BDT8/U6/835 | 120-277 | 12 | 22.5 | 1800 | 3500K | 80 | 50,000 | >0.9 | PUWGR50L | Damp | 6" leg spacing |
| | 2G13 | 13 | 93133051 | LED13BDT8/U6/840 | 120-277 | 12 | 22.5 | 1850 | 4000K | 80 | 50,000 | >0.9 | P5NYY5PI | Damp | 6" leg spacing |
| | 2G13 | 13 | 93133052 | LED13BDT8/U6/850 | 120-277 | 12 | 22.5 | 1850 | 5000K | 80 | 50,000 | >0.9 | PWD1ZSNP | Damp | 6" leg spacing |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity from Current = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[4] Not all product variations on this page are DLC qualified. Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
* Default color temperature setting is 4000K.
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## Ballast Bypass covRguard® Plastic Sleeved Glass Tubes - Double Ended - Type B

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Rated Life L70 (Hrs)[1] | Power Factor | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Ballast Bypass - 4ft covRguard® Plastic Sleeved Glass Tubes** | | | | | | | | | | | | | | | |
| T8 | G13 | 16 | 93154588 | LED16BDT8/G4/835XL/CVG | 120-277 | 20 | 48 | 2400 | 3500K | 80 | 70,000 | >0.9 | S-HSC8PZ | Damp | NSF Food Zone |
| | G13 | 16 | 93154589 | LED16BDT8/G4/840XL/CVG | 120-277 | 20 | 48 | 2450 | 4000K | 80 | 70,000 | >0.9 | S-KDB8N5 | Damp | NSF Food Zone |
| | G13 | 16 | 93154586 | LED16BDT8/G4/850XL/CVG | 120-277 | 20 | 48 | 2450 | 5000K | 80 | 70,000 | >0.9 | S-398H0M | Damp | NSF Food Zone |
| | G13 | 13 | 93154613 | LED13BDT8/G4/835XL/CVG | 120-277 | 20 | 48 | 1900 | 3500K | 80 | 70,000 | >0.9 | S-PTI7MQ | Damp | NSF Food Zone |
| | G13 | 13 | 93154590 | LED13BDT8/G4/840XL/CVG | 120-277 | 20 | 48 | 1950 | 4000K | 80 | 70,000 | >0.9 | S-HVKBRT | Damp | NSF Food Zone |
| | G13 | 13 | 93154612 | LED13BDT8/G4/850XL/CVG | 120-277 | 20 | 48 | 1950 | 5000K | 80 | 70,000 | >0.9 | S-7VT10C | Damp | NSF Food Zone |
| | G13 | 9 | 93154615 | LED9BDT8/G4/835XL/CVG | 120-277 | 20 | 48 | 1550 | 3500K | 80 | 70,000 | >0.9 | - | Damp | NSF Food Zone |
| | G13 | 9 | 93154616 | LED9BDT8/G4/840XL/CVG | 120-277 | 20 | 48 | 1600 | 4000K | 80 | 70,000 | >0.9 | S-DEZYC0 | Damp | NSF Food Zone |

## Ballast Bypass PET Plastic Coated Glass Tubes - Double Ended - Type B

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Rated Life L70 (Hrs)[1] | Power Factor | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Ballast Bypass - 4ft PET Plastic Coated Glass Tubes** | | | | | | | | | | | | | | | |
| T8 | G13 | 14 | 93123124 | LED14BDT8/G4/835CT | 120-277 | 20 | 48 | 1750 | 3500K | 80 | 50,000 | >0.9 | PK9D9IG0 | Damp | NSF Splash Zone |
| | G13 | 14 | 93123316 | LED14BDT8/G4/840CT | 120-277 | 20 | 48 | 1750 | 4000K | 80 | 50,000 | >0.9 | P9R85C2W | Damp | NSF Splash Zone |
| | G13 | 14 | 93123317 | LED14BDT8/G4/850CT | 120-277 | 20 | 48 | 1800 | 5000K | 80 | 50,000 | >0.9 | PZL4PN19 | Damp | NSF Splash Zone |
| | G13 | 11 | 93129666 | LED11BDT8/G4/840CT | 120-277 | 20 | 48 | 1650 | 4000K | 80 | 50,000 | >0.9 | PKJQYIAK | Damp | NSF Splash Zone |
| **Ballast Bypass - 3ft LED Tube - PET Plastic Coated Glass** | | | | | | | | | | | | | | | |
| T8 | G13 | 12 | 93154450 | LED12BDT8/G3/840CT | 120-277 | 20 | 36 | 1450 | 4000K | 80 | 50,000 | >0.9 | S-UYXL72 | Damp | NSF Splash Zone |
| **Ballast Bypass - 2ft LED Tube - PET Plastic Coated Glass** | | | | | | | | | | | | | | | |
| T8 | G13 | 9 | 93154445 | LED9BDT8/G2/840CT | 120-277 | 20 | 24 | 1100 | 4000K | 80 | 50,000 | >0.9 | S-K7HOSB | Damp | NSF Splash Zone |

## 120-347V Ballast Bypass Glass Tubes - Double Ended - Type B

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Rated Life L70 (Hrs)[1] | Power Factor | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **120-347V Ballast Bypass - 8ft Glass Tubes** | | | | | | | | | | | | | | | |
| T8 | R17d | 42 | 93309189 | LED42BDT8/G8/R17d/840/120-347 | 120-347 | 20 | 96 | 5500 | 4000K | 80 | 50,000 | >0.9 | - | Damp | |
| **120-347V Ballast Bypass - 4ft Glass Tubes** | | | | | | | | | | | | | | | |
| T8 | G13 | 15 | 93150744 | LED15BDT8/G4/830/120-347 | 120-347 | 20 | 48 | 2000 | 3000K | 80 | 50,000 | >0.9 | PLEZ25LCZ18C | Damp | |
| | G13 | 15 | 93150745 | LED15BDT8/G4/835/120-347 | 120-347 | 20 | 48 | 2100 | 3500K | 80 | 50,000 | >0.9 | PL3AD91YOVYI | Damp | |
| | G13 | 15 | 93150774 | LED15BDT8/G4/840/120-347 | 120-347 | 20 | 48 | 2200 | 4000K | 80 | 50,000 | >0.9 | PLAVADEOC20D | Damp | |
| | G13 | 15 | 93150775 | LED15BDT8/G4/850/120-347 | 120-347 | 20 | 48 | 2200 | 5000K | 80 | 50,000 | >0.9 | PLMTIE87F98F | Damp | |
| | G13 | 11.5 | 93305112 | LED11BDT8/G4/830/120-347 | 120-347 | 20 | 48 | 1700 | 3000K | 80 | 50,000 | >0.9 | S-P96STW | Damp | |
| | G13 | 11.5 | 93305113 | LED11BDT8/G4/835/120-347 | 120-347 | 20 | 48 | 1750 | 3500K | 80 | 50,000 | >0.9 | S-FK874T | Damp | |
| | G13 | 11.5 | 93305115 | LED11BDT8/G4/840/120-347 | 120-347 | 20 | 48 | 1800 | 4000K | 80 | 50,000 | >0.9 | S-RBECUJ | Damp | |
| | G13 | 11.5 | 93305116 | LED11BDT8/G4/850/120-347 | 120-347 | 20 | 48 | 1800 | 5000K | 80 | 50,000 | >0.9 | S-32DTWS | Damp | |
| **120-347V Ballast Bypass - 3ft Glass Tubes** | | | | | | | | | | | | | | | |
| T8 | G13 | 12 | 93309175 | LED12BDT8/G3/830/120-347 | 120-347 | 20 | 36 | 1500 | 3000K | 80 | 50,000 | >0.9 | S-1A830D | Damp | |
| | G13 | 12 | 93309176 | LED12BDT8/G3/835/120-347 | 120-347 | 20 | 36 | 1550 | 3500K | 80 | 50,000 | >0.9 | S-XIZY0E | Damp | |
| | G13 | 12 | 93309177 | LED12BDT8/G3/840/120-347 | 120-347 | 20 | 36 | 1600 | 4000K | 80 | 50,000 | >0.9 | S-4DQ73F | Damp | |
| | G13 | 12 | 93309178 | LED12BDT8/G3/850/120-347 | 120-347 | 20 | 36 | 1600 | 5000K | 80 | 50,000 | >0.9 | S-CDWEX5 | Damp | |
| **120-347V Ballast Bypass - 2ft Glass Tubes** | | | | | | | | | | | | | | | |
| T8 | G13 | 7 | 93309179 | LED7BDT8/G2/830/120-347 | 120-347 | 20 | 24 | 900 | 3000K | 80 | 50,000 | >0.9 | S-Q73A5R | Damp | |
| | G13 | 7 | 93309180 | LED7BDT8/G2/835/120-347 | 120-347 | 20 | 24 | 925 | 3500K | 80 | 50,000 | >0.9 | S-WVHQ2L | Damp | |
| | G13 | 7 | 93309181 | LED7BDT8/G2/840/120-347 | 120-347 | 20 | 24 | 950 | 4000K | 80 | 50,000 | >0.9 | S-OL6XNA | Damp | |
| | G13 | 7 | 93309182 | LED7BDT8/G2/850/120-347 | 120-347 | 20 | 24 | 950 | 5000K | 80 | 50,000 | >0.9 | S-ZTFN9K | Damp | |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[4] Not all product variations on this page are DLC qualified. Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## Ballast Bypass Glass Tubes - Double Ended - Type B - T5

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Rated Life L70 (Hrs)[1] | Power Factor | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Ballast Bypass - 4ft T5 HO Glass Tubes** | | | | | | | | | | | | | | | |
| T5 | G5 | 25 | 93100293 | LED25BDT5/G4/835 | 120-277 | 20 | 46 | 3400 | 3500K | 80 | 50,000 | >0.9 | PNWXCFFY | Damp | |
| | G5 | 25 | 93100294 | LED25BDT5/G4/840 | 120-277 | 20 | 46 | 3500 | 4000K | 80 | 50,000 | >0.9 | P56WVBL6 | Damp | |
| | G5 | 25 | 93100295 | LED25BDT5/G4/850 | 120-277 | 20 | 46 | 3600 | 5000K | 80 | 50,000 | >0.9 | P95QEGYA | Damp | |
| **Ballast Bypass - 4ft T5 HE Glass Tubes** | | | | | | | | | | | | | | | |
| T5 | G5 | 14 | 93128486 | LED14BDT5G4840HE | 120-277 | 20 | 46 | 2150 | 4000K | 80 | 50,000 | >0.9 | P80DMFGU | Damp | |
| **Ballast Bypass - 3ft T5 HE Glass Tubes** | | | | | | | | | | | | | | | |
| T5 | G5 | 11 | 93128488 | LED11BDT5G3830HE | 120-277 | 20 | 34 | 1600 | 3000K | 80 | 50,000 | >0.9 | - | Damp | |
| | G5 | 11 | 93128492 | LED11BDT5G3850HE | 120-277 | 20 | 34 | 1700 | 5000K | 80 | 50,000 | >0.9 | - | Damp | |
| **Ballast Bypass - 2ft T5 HE Glass Tubes** | | | | | | | | | | | | | | | |
| T5 | G5 | 9 | 93128571 | LED9BDT5G2/850HE | 120-277 | 20 | 22 | 1350 | 5000K | 80 | 50,000 | >0.9 | - | Damp | |

## Ballast Bypass covRguard® Plastic Sleeved Glass Tubes - Double Ended - Type B - T5

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Rated Life L70 (Hrs)[1] | Power Factor | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Ballast Bypass - 4ft covRguard® Plastic Sleeved Glass Tubes** | | | | | | | | | | | | | | | |
| T5 | G5 | 25 | 93155904 | LED25BDT5/G4/840/CVG | 120-277 | 20 | 46 | 3400 | 4000K | 80 | 50,000 | >0.9 | S-60DSLU | Damp | NSF Food Zone |
| | G5 | 25 | 93155905 | LED25BDT5/G4/850/CVG | 120-277 | 20 | 46 | 3400 | 5000K | 80 | 50,000 | >0.9 | S-8STF01 | Damp | NSF Food Zone |

## Type B Tube Misapplication Fuse Kit

Current offers this fuse kit for use in Type B Tube applications for protection against future misapplication of linear fluorescent lamps.

| Order Code | Description | Kit Contents |
|---|---|---|
| 39017 | BT8-1AFUSEKIT | 1 Fuse (1A), 1 Fuse Holder |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[4] Not all product variations on this page are DLC qualified. Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
Please note Current lamps are not for sale for use in Yukon Territory in Canada



# Why switch to LED Tubes?

## LED Tubes are the fast and easy way to upgrade from Linear Fluorescent to LED.

**Current offers a variety of LED Tube options, so you can choose the best solution for each application.**

- No Mercury in LED
- 50% Energy Reduction
- 2x Longer Rated Life
- Quick Payback

## Fluorescent lamps will soon become unavailable for sale in a number of states with upcoming legislation. Are you ready?

In an effort to regulate consumer products that contain mercury, state governments within the USA have passed legislation that will prohibit the sale and distribution of Linear and Compact Fluorescent lamps. For more information or to see if your state is impacted, please visit www.LED.com/lamplegislation.

**LED Tube Design for Signage Applications:**
Standard GE LED Tubes are constructed of glass tubes with an internal coating, similar to linear fluorescent lamps. The coating inside the glass provides good diffusion, spreading out the light and eliminating hot spots and pixilation from the individual LEDs. However, since the LED board inside the tube is on one side, the output is directional. This can be an advantage in many applications where the lamps are in a ceiling and the light needs to point down.

Linear fluorescent lamps emit light equally all the way around the diameter of the tube. For double-sided signage applications, this uniformity is ideal. Signage ("SGN") GE LED Tubes are constructed similarly to standard tubes, but with two key differences designed to improve performance in signage applications. First, Signage GE LED Tubes incorporate a reflective strip inside the tube opposite the LED board. The strip bounces light back behind the LED board and reduces the intensity directly across from the LED board. This results in more uniform light distribution, which is preferred for double-sided signage cabinets. The second key feature of Signage LED Tubes is rotatable end caps. These allow the tube to be oriented properly regardless of the socket orientation inside the cabinet.

**SpectraChoice**™ Allows you to easily make color temperature selections at any time with integrated switch, no tools required

Signage R17d LED Tube





SpectraChoice™





Standard R17d LED Tube

## Graphical Representation of Light Distribution from HO Tubes:


**Linear Fluorescent**
Uniform distribution around the tube



**Standard LED Tube**
More light directed "down" from LEDs




**Signage LED Tube**
Reflective strip provides improved uniformity*










**Signage LED R17d HO Tube**

## Signage Ballast Bypass Selectable SpectraChoice™ Glass HO Tubes - Double Ended - Type B

| Bulb Shape | Base Type | Order Code | Description | Volts | Carton Qty[2] | Nominal Length (in) | Actual Length (in) | Watts | Selectable Lumens (Initial)* | Selectable Color Temp. (Initial)* | CRI | Rated Life L70 (Hrs)[1] | Power Factor | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Ballast Bypass (Type B) - High Output Recessed Double Contact (R17d) - Signage | | | | | | | | | | | | | | | |
| T8 | R17d | 93323121 | LED7BDT8/G18/R17d/8SC/SGN | 120-347 | 10 | 18.0 | 15.91 | 7 | 800<br>900<br>900<br>850* | 3500K<br>4000K<br>5000K<br>6500K* | 80 | 50,000 | >0.9 | Damp | Ballast Bypass |
| | R17d | 93323115 | LED9BDT8/G2/R17d/8SC/SGN | 120-347 | 10 | 24.0 | 21.91 | 9 | 1100<br>1200<br>1200<br>1150* | 3500K<br>4000K<br>5000K<br>6500K* | 80 | 50,000 | >0.9 | Damp | Ballast Bypass |
| | R17d | 93323109 | LED11BDT8/G30/R17d/8SC/SGN | 120-347 | 10 | 30.0 | 27.91 | 11.5 | 1450<br>1550<br>1550<br>1500* | 3500K<br>4000K<br>5000K<br>6500K* | 80 | 50,000 | >0.9 | Damp | Ballast Bypass |
| | R17d | 93319048 | LED14BDT8/G3/R17d/8SC/SGN | 120-347 | 10 | 36.0 | 33.91 | 14 | 1800<br>1900<br>1900<br>1850* | 3500K<br>4000K<br>5000K<br>6500K* | 80 | 50,000 | >0.9 | Damp | Ballast Bypass |
| | R17d | 93323103 | LED16BDT8/G42/R17d/8SC/SGN | 120-347 | 10 | 42.0 | 39.91 | 16 | 2100<br>2200<br>2200<br>2150* | 3500K<br>4000K<br>5000K<br>6500K* | 80 | 50,000 | >0.9 | Damp | Ballast Bypass |
| | R17d | 93319046 | LED18BDT8/G4/R17d/8SC/SGN | 120-347 | 10 | 48.0 | 45.91 | 18 | 2400<br>2500<br>2500<br>2450* | 3500K<br>4000K<br>5000K<br>6500K* | 80 | 50,000 | >0.9 | Damp | Ballast Bypass |
| | R17d | 93319044 | LED24BDT8/G5/R17d/8SC/SGN | 120-347 | 10 | 60.0 | 57.91 | 24 | 2800<br>2950<br>2950<br>2850* | 3500K<br>4000K<br>5000K<br>6500K* | 80 | 50,000 | >0.9 | Damp | Ballast Bypass |
| | R17d | 93319042 | LED26BDT8/G64/R17d/8SC/SGN | 120-347 | 10 | 64.0 | 61.91 | 26 | 3050<br>3200<br>3200<br>3100* | 3500K<br>4000K<br>5000K<br>6500K* | 80 | 50,000 | >0.9 | Damp | Ballast Bypass |
| | R17d | 93319040 | LED30BDT8/G6/R17d/8SC/SGN | 120-347 | 10 | 72.0 | 69.91 | 30 | 3500<br>3650<br>3650<br>3550* | 3500K<br>4000K<br>5000K<br>6500K* | 80 | 50,000 | >0.9 | Damp | Ballast Bypass |
| | R17d | 93319038 | LED35BDT8/G7/R17d/8SC/SGN | 120-347 | 10 | 84.0 | 81.91 | 35 | 4050<br>4250<br>4250<br>4150* | 3500K<br>4000K<br>5000K<br>6500K* | 80 | 50,000 | >0.9 | Damp | Ballast Bypass |
| | R17d | 93319036 | LED42BDT8/G8/R17d/8SC/SGN | 120-347 | 10 | 96.0 | 93.91 | 42 | 4900<br>5100<br>5100<br>5000* | 3500K<br>4000K<br>5000K<br>6500K* | 80 | 50,000 | >0.9 | Damp | Ballast Bypass |
| Patent Pending | | | | | | | | | | | | | | | |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity from Current = Case Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
* Default wattage and color temperature settings noted by "*" in tables above.
Please note Current lamps are not for sale for use in Yukon Territory in Canada



**Standard LED R17d HO Tube**


## Ballast Bypass Selectable SpectraChoice™ Glass HO Tubes - Double Ended - Type B

| Bulb Shape | Base Type | Order Code | Description | Volts | Carton Qty[2] | Nominal Length (in) | Actual Length (in) | Watts | Selectable Lumens (Initial)* | Selectable Color Temp. (Initial)* | CRI | Rated Life L70 (Hrs)[1] | Power Factor | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Ballast Bypass (Type B) - High Output Recessed Double Contact (R17d)** | | | | | | | | | | | | | | | |
| T8 | R17d | 93319034 | LED14BDT8/G3/R17d/8SC/120-347 | 120-347 | 10 | 36.0 | 33.91 | 14 | 1900<br>2000<br>2000<br>1950* | 3500K<br>4000K<br>5000K<br>6500K* | 80 | 50,000 | >0.9 | Damp | Ballast Bypass |
| | R17d | 93319032 | LED18BDT8/G4/R17d/8SC/120-347 | 120-347 | 10 | 48.0 | 45.91 | 18 | 2500<br>2600<br>2600<br>2550* | 3500K<br>4000K<br>5000K<br>6500K* | 80 | 50,000 | >0.9 | Damp | Ballast Bypass |
| | R17d | 93319030 | LED24BDT8/G5/R17d/8SC/120-347 | 120-347 | 10 | 60.0 | 57.91 | 24 | 3050<br>3200<br>3200<br>3100* | 3500K<br>4000K<br>5000K<br>6500K* | 80 | 50,000 | >0.9 | Damp | Ballast Bypass |
| | R17d | 93319028 | LED26BDT8/G64/R17d/8SC/120-347 | 120-347 | 10 | 64.0 | 61.91 | 26 | 3300<br>3450<br>3450<br>3350* | 3500K<br>4000K<br>5000K<br>6500K* | 80 | 50,000 | >0.9 | Damp | Ballast Bypass |
| | R17d | 93319026 | LED30BDT8/G6/R17d/8SC/120-347 | 120-347 | 10 | 72.0 | 69.91 | 30 | 3800<br>4000<br>4000<br>3850* | 3500K<br>4000K<br>5000K<br>6500K* | 80 | 50,000 | >0.9 | Damp | Ballast Bypass |
| | R17d | 93319024 | LED35BDT8/G7/R17d/8SC/120-347 | 120-347 | 10 | 84.0 | 81.91 | 35 | 4400<br>4600<br>4600<br>4500* | 3500K<br>4000K<br>5000K<br>6500K* | 80 | 50,000 | >0.9 | Damp | Ballast Bypass |
| | R17d | 93319022 | LED42BDT8/G8/R17d/8SC/120-347 | 120-347 | 10 | 96.0 | 93.91 | 42 | 5300<br>5500<br>5500<br>5400* | 3500K<br>4000K<br>5000K<br>6500K* | 80 | 50,000 | >0.9 | Damp | Ballast Bypass |


[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity from Current = Case Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
* Default wattage and color temperature settings noted by "*" in tables above.
Please note Current lamps are not for sale for use in Yukon Territory in Canada

### Wiring Diagrams for Double-Ended Type B LED Tubes

**Shunted Sockets**




**Unshunted Sockets**




### Type B Tube Misapplication Fuse Kit

| Order Code | Description | Kit Contents |
|---|---|---|
| 39017 | BT8-1AFUSEKIT | 1 Fuse (1A), 1 Fuse Holder |

## LED Tubes - Type C

GE Type C LED Tubes and Drivers are the preferred LED Tube choice for applications that demand dimming, controllability and flexibility.

GE Type C LED Tubes operate from the low voltage DC output of the drivers. The Class 2 output reduces risk of fire and shock compared to higher voltage alternatives. The same lamp may be used with various drivers.

In addition to the lamp-driver combination flexibility, LumenChoice® drivers are field-tunable. Installers can change the output to the lamps using built-in switches on the driver. This allows solutions to be optimized for each application, with potential for more energy savings by reducing the output in overlit spaces.

Dimming and controllability are readily implemented using the 0-10V dimming leads from the drivers. 0-10V dimming was common on dimming ballasts for linear fluorescent lamps, so implementation on existing systems is straightforward. 0-10V output allows for many drivers to be controlled by one device, a practical solution for LED Tube applications. The 0-10V dimming leads from GE Type C LED Tube drivers may also be combined with Current wireless controls. Contact your Current sales representative for more information.

Driver wiring mimics that of instant start ballasts, making for simple installation. Each channel from the driver is independent, so running fewer lamps than the maximum does not impact the other outputs. Running three lamps from a four-lamp driver still provides the same output to each lamp as when four lamps are being operated.

With LumenChoice® Type C LED Tubes and Drivers, fewer SKUs can be used to address the needs of an entire facility. The performance tables in this section show the light output from lamps at each driver wattage setting.

### Catalog Logic:

**Bulb Shape:**
Bulb shape followed by its size (the maximum diameter of the bulb expressed in eighths of an inch).

**Base Type:**
ANSI Base

**Order Code:**
Use the order code when ordering to ensure that you receive the exact product you require

**Description:**
Lamp Model Description

**Carton Quantity:**
Number of lamps packed in a carton

**MOL (in):**
Maximum Overall Length in inches

**Color Temperature (K):**
A measure of the visual "warmth" or "coolness" of the light from the lamp. The higher the value, the whiter or "cooler" the light appears.

**Color Rendering Index (CRI or R):**
An indication of the ability of the lamp to render object colors in a normal natural way. The higher the number (0-100), the better the color appearance.

**Rated Life L70:**
Hours of operation the lamp will provide before reaching 70% of its original lumen output

**DLC:**
Indicates whether product is listed on the DesignLights Consortium® Qualified Products List

**Location Rating:**
Location Rating as defined for LED Lamps by UL 1993

**Initial Lumens at Selectable Settings:**
Lamp lumens at various wattages


| Bulb Shape | Base Type | Order Code | Description | Carton Qty[2] | MOL (in) | Color Temp. (Initial) | CRI | Rated Life L70 (Hrs)[1] | DLC®[4] | Location Rating[3] | Initial Lumens: 6W | 9W | 12W | 15W | 18W |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **LumenChoice® 4 ft T8 Glass Tubes - Fixed CCT** | | | | | | | | | | | | | | | |
| T8 | G13 | 34211 | LEDT8/LC/G/4/830 | 20 | 48 | 3000K | 80 | 70,000 | Yes | Damp | 750 | 1150 | 1550 | 1900 | 2250 |

**LEDT8/LC/G/4/830**

- Bulb Shape
- LC = LumenChoice; output determined by external driver setting
- "G" indicates Glass tube
- Length in feet
- CRI (8 = 80)
- CCT (30 = 3000K)

## Programming LumenChoice™ Drivers

Before installation, LumenChoice™ Drivers must be set to the desired output. Lumen levels corresponding to the driver settings below are noted in the specification tables. Adjust the switches on the side of the driver to achieve the desired performance according to the table below.




| DRIVER DESCRIPTIONS | DRIVER PRODUCT CODES |
|---|---|
| LED/6-18/DR/D2L<br>LED/6-18/DR/D4L | 93313132<br>93313181 |

| SYSTEM WATTS PER LAMP | SWITCH CODE | | | | |
|---|---|---|---|---|---|
| | 1 | 2 | 3 | 4 | 5 |
| 18 | OFF | OFF | OFF | OFF | OFF |
| 15 | **ON** | OFF | OFF | OFF | OFF |
| 12 | OFF | **ON** | OFF | OFF | OFF |
| 9 | OFF | OFF | **ON** | OFF | OFF |
| 6 | OFF | OFF | OFF | **ON** | OFF |

## **Remote Drivers** for Type C LED Tubes

| Input Watts (Max.) | Order Code | Description | Input Voltage | Carton Qty[2] | Length (in) | Width (in) | Height (in) | Freq. (Hz) | Power Factor | Output Voltage | Max. Output Current (A) | Min. Temp.[1] | Max Temp. | 0-10V Dimmable | Default Wattage per Tube Setting | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **LumenChoice® Remote Drivers - Selectable Output for Type C LED Tubes (6-18W Range)** | | | | | | | | | | | | | | | | |
| 36 | 93313132 | LED/6-18/DR/D2L | 120-347 VAC | 10 | 9.5 | 1.3 | 1.2 | 60 | >0.9 | 26-34 VDC | 0.53x2 | -4° F | 104° F | Yes | 12W | Max. 2 Tubes: Class 2 Output |
| 72 | 93313181 | LED/6-18/DR/D4L | 120-347 VAC | 10 | 9.5 | 1.7 | 1.2 | 60 | >0.9 | 26-34 VDC | 0.53x4 | -4° F | 104° F | Yes | 12W | Max. 4 Tubes: Class 2 Output |
| **LumenChoice® Remote Drivers - Selectable Output for Type C LED Tubes (8-16.5W Range)** | | | | | | | | | | | | | | | | |
| 66 | 21379 | LED/DR/D4L/LW | 120-277 VAC | 10 | 9.5 | 1.7 | 1.2 | 60 | >0.9 | 26-34 VDC | 0.48x4 | -4° F | 104° F | Yes | 12W | Max. 4 Tubes; Class 2 Output |

## LumenChoice® + SpectraChoice™ T8 Type C LED Tube and Driver System

| Bulb Shape | Base Type | Order Code | Description | Carton Qty[2] | MOL (in) | Selectable Color Temp. (Initial) | CRI | Rated Life L70 (Hrs)[1] | DLC®[4] | Location Rating[3] | Initial Lumens at Driver Settings: 6W | 9W | 12W | 15W | 18W |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **LumenChoice® + SpectraChoice™ 4 ft T8 Glass Tube - Selectable CCT** | | | | | | | | | | | | | | | |
| T8 | G13 | 93322420 | LEDT8/LC/G/4/8SC | 20 | 48 | 3500K 4000K 5000K | 80 | 70,000 | - | Damp | 1050 | 1500 | 1950 | 2300 | 2700 |
| **LumenChoice® + SpectraChoice™ 3 ft T8 Glass Tube - Selectable CCT** | | | | | | | | | | | | | | | |
| T8 | G13 | 93322422 | LEDT8/LC/G/3/8SC | 20 | 36 | 3500K 4000K 5000K | 80 | 70,000 | - | Damp | 1050 | 1500 | 1900 | 2250 | 2600 |
| **LumenChoice® + SpectraChoice™ 2 ft T8 Glass Tube - Selectable CCT** | | | | | | | | | | | | | | | |
| T8 | G13 | 93322418 | LEDT8/LC/G/2/8SC | 20 | 24 | 3500K 4000K 5000K | 80 | 70,000 | - | Damp | 1000 | 1450 | 1850 | | |

## LumenChoice® T8 Type C LED Tube and Driver System

| Bulb Shape | Base Type | Order Code | Description | Carton Qty[2] | MOL (in) | Color Temp. (Initial) | CRI | Rated Life L70 (Hrs)[1] | DLC®[4] | Location Rating[3] | Initial Lumens: 6W | 9W | 12W | 15W | 18W |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **LumenChoice® 4 ft T8 Glass Tubes - Fixed CCT** | | | | | | | | | | | | | | | |
| T8 | G13 | 34211 | LEDT8/LC/G/4/830 | 20 | 48 | 3000K | 80 | 70,000 | P0I38IQ3/ PAY71VOU | Damp | 750 | 1150 | 1550 | 1900 | 2250 |
| | G13 | 93314798 | LEDT8/LC/G/4/835XL | 20 | 48 | 3500K | 80 | 70,000 | S-9YTMRV/ S-4ZZZSL | Damp | 1000 | 1450 | 1850 | 2250 | 2600 |
| | G13 | 93314800 | LEDT8/LC/G/4/840XL | 20 | 48 | 4000K | 80 | 70,000 | S-GQG393/ S-HJPP10 | Damp | 1050 | 1500 | 1900 | 2300 | 2650 |
| | G13 | 93314802 | LEDT8/LC/G/4/850XL | 20 | 48 | 5000K | 80 | 70,000 | S-VJSSD3/ S-QW2PTZ | Damp | 1050 | 1500 | 1900 | 2300 | 2650 |
| **LumenChoice® 3 ft T8 Glass Tubes - Fixed CCT** | | | | | | | | | | | | | | | |
| T8 | G13 | 36394 | LEDT8/LC/G/3/830 | 20 | 36 | 3000K | 80 | 70,000 | - | Damp | 800 | 1150 | 1550 | 1900 | |
| **LumenChoice® 2 ft T8 Glass Tubes - Fixed CCT** | | | | | | | | | | | | | | | |
| T8 | G13 | 36406 | LEDT8/LC/G/2/830 | 20 | 24 | 3000K | 80 | 70,000 | - | Damp | 750 | 1100 | 1450 | | |
| **LumenChoice® U1 T8 T8 Glass Tubes - 1-5/8" leg spacing - Fixed CCT** | | | | | | | | | | | | | | | |
| T8-U1 | 2G13 | 28084 | LED14T8/U/835 | 15 | 22.5 | 3500K | 80 | 50,000 | - | Damp | 750 | 1100 | 1550 | | |
| | 2G13 | 28164 | LED14T8/U/840 | 15 | 22.5 | 4000K | 80 | 50,000 | - | Damp | 750 | 1100 | 1550 | | |
| **LumenChoice® U6 T8 Glass Tubes - 6" leg spacing - Fixed CCT** | | | | | | | | | | | | | | | |
| T8-U6 | 2G13 | 43131 | LED15T8/G/U6/830 | 12 | 22.5 | 3000K | 80 | 50,000 | - | Damp | 700 | 1050 | 1450 | 1700 | |
| | 2G13 | 43135 | LED15T8/G/U6/835 | 12 | 22.5 | 3500K | 80 | 50,000 | - | Damp | 750 | 1100 | 1550 | 1800 | |
| | 2G13 | 43143 | LED15T8/G/U6/840 | 12 | 22.5 | 4000K | 80 | 50,000 | - | Damp | 750 | 1100 | 1550 | 1800 | |
| | 2G13 | 43145 | LED15T8/G/U6/850 | 12 | 22.5 | 5000K | 80 | 50,000 | - | Damp | 750 | 1100 | 1550 | 1800 | |

## **Remote Drivers** for Type C LED Tubes

| Input Watts (Max.) | Order Code | Description | Input Voltage | Carton Qty[2] | Length (in) | Width (in) | Height (in) | Freq. (Hz) | Power Factor | Output Voltage | Max. Output Current (A) | Min. Temp.[1] | Max Temp. | 0-10V Dimmable | Wattage per Tube | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Fixed Wattage Remote Drivers for Type C LED Tubes** | | | | | | | | | | | | | | | | |
| 72 | 63126 | LED36T8/DR/D2L | 120-277 VAC | 10 | 9.5 | 1.7 | 1.2 | 60 | >0.9 | 26-34 VDC | 1.06x2 | -4° F | 104° F | Yes | 36W | Max. 2 Tubes: Class 2 Output |

## **8ft T8 Type C LED Tube and Driver System** - T8 on 36W Driver

| Bulb Shape | Base Type | Order Code | Description | Carton Qty[2] | MOL (in) | Color Temp. (Initial) | CRI | Rated Life L70 (Hrs)[1] | DLC®[4] | Location Rating[3] | Input Watts per Lamp | Lumens (Initial) | 2-Lamp 36W Driver |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **8 ft T8 Glass Tubes - Fixed CCT** | | | | | | | | | | | | | |
| T8 | Fa8 | 62327 | LED36T8/G/8/835 | 20 | 96 | 3500K | 80 | 50,000 | PZEBFURM | Damp | 36 | 4400 | 63126 LED36T8/DR/D2L |
| | Fa8 | 62329 | LED36T8/G/8/840 | 20 | 96 | 4000K | 80 | 50,000 | P2MIT03H | Damp | 36 | 4400 | 63126 LED36T8/DR/D2L |
| | Fa8 | 62349 | LED36T8/G/8/850 | 20 | 96 | 4000K | 80 | 50,000 | P1U8ZD2E | Damp | 36 | 4400 | 63126 LED36T8/DR/D2L |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[4] Not all product variations on this page are DLC qualified. Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## Remote Drivers for Type C LED Tubes

| Input Watts (Max.) | Order Code | Description | Input Voltage | Carton Qty[2] | Length (in) | Width (in) | Height (in) | Freq. (Hz) | Power Factor | Output Voltage | Max. Output Current (A) | Min. Temp.[1] | Max Temp. | 0-10V Dimmable | Default Wattage per Tube Setting | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **LumenChoice® Remote Drivers - Selectable Output for Type C LED Tubes (6-18W Range)** | | | | | | | | | | | | | | | | |
| 36 | 93313132 | LED/6-18/DR/D2L | 120-347 VAC | 10 | 9.5 | 1.3 | 1.2 | 60 | >0.9 | 26-34 VDC | 0.53x2 | -4° F | 104° F | Yes | 12W | Max. 2 Tubes: Class 2 Output |
| 72 | 93313181 | LED/6-18/DR/D4L | 120-347 VAC | 10 | 9.5 | 1.7 | 1.2 | 60 | >0.9 | 26-34 VDC | 0.53x4 | -4° F | 104° F | Yes | 12W | Max. 4 Tubes: Class 2 Output |
| **LumenChoice® Remote Drivers - Selectable Output for Type C LED Tubes (8-16.5W Range)** | | | | | | | | | | | | | | | | |
| 66 | 21379 | LED/DR/D4L/LW | 120-277 VAC | 10 | 9.5 | 1.7 | 1.2 | 60 | >0.9 | 26-34 VDC | 0.48x4 | -4° F | 104° F | Yes | 12W | Max. 4 Tubes; Class 2 Output |

## LumenChoice® + SpectraChoice™ T5 Type C LED Tube and Driver System

| Bulb Shape | Base Type | Order Code | Description | Carton Qty[2] | MOL (in) | Selectable Color Temp. (Initial) | CRI | Rated Life L70 (Hrs)[1] | DLC®[4] | Location Rating[3] | Initial Lumens at Driver Settings: 6W | 9W | 12W | 15W | 18W |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **LumenChoice® + SpectraChoice™ 4 ft T5 Glass Tube - Selectable CCT** | | | | | | | | | | | | | | | |
| T5 | G5 | 93323642 | LEDT5/LC/G/4/8SC | 20 | 46 | 3500K 4000K 5000K | 80 | 70,000 | - | Damp | 1150 | 1650 | 2100 | 2500 | 2950 |
| **LumenChoice® + SpectraChoice™ 3 ft T5 Glass Tube - Selectable CCT** | | | | | | | | | | | | | | | |
| T5 | G5 | 93323644 | LEDT5/LC/G/3/8SC | 20 | 34 | 3500K 4000K 5000K | 80 | 70,000 | - | Damp | 950 | 1350 | 1700 | 2050 | 2350 |
| **LumenChoice® + SpectraChoice™ 2 ft T5 Glass Tube - Selectable CCT** | | | | | | | | | | | | | | | |
| T5 | G5 | 93323646 | LEDT5/LC/G/2/8SC | 20 | 22 | 3500K 4000K 5000K | 80 | 70,000 | - | Damp | 850 | 1250 | 1600 | 1850 | 2150 |

## LumenChoice® T5 Type C LED Tube and Driver System

| Bulb Shape | Base Type | Order Code | Description | Carton Qty[2] | MOL (in) | Color Temp. (Initial) | CRI | Rated Life L70 (Hrs)[1] | DLC®[4] | Location Rating[3] | Initial Lumens at Low Wattage Settings: 6W | 9W | 12W | 15W | 18W |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **LumenChoice® 4 ft T5 XL Glass Tubes - Fixed CCT** | | | | | | | | | | | | | | | |
| T5 | G5 | 93314792 | LEDT5/LC/G/4/835XL | 20 | 46 | 3500K | 80 | 70,000 | S-5LR7MR/ S-7DMN55 | Damp | 1150 | 1700 | 2150 | 2650 | 3050 |
| | G5 | 93314794 | LEDT5/LC/G/4/840XL | 20 | 46 | 4000K | 80 | 70,000 | S-XB09Y4/ S-MY2H69 | Damp | 1200 | 1750 | 2200 | 2700 | 3100 |
| | G5 | 93314796 | LEDT5/LC/G/4/850XL | 20 | 46 | 5000K | 80 | 70,000 | S-FGTDPB/ S-R7439N | Damp | 1200 | 1750 | 2200 | 2700 | 3100 |
| **LumenChoice® 3 ft T5 HE Glass Tubes - Fixed CCT** | | | | | | | | | | | | | | | |
| T5 | G5 | 39002 | LEDT5LC/G3/840HE | 20 | 34 | 4000K | 80 | 70,000 | - | Damp | 900 | 1300 | 1650 | 2000 | 2300 |
| | G5 | 39003 | LEDT5LC/G3/850HE | 20 | 34 | 5000K | 80 | 70,000 | - | Damp | 900 | 1300 | 1650 | 2000 | 2300 |
| **LumenChoice® 2 ft T5 Glass Tubes - Fixed CCT** | | | | | | | | | | | | | | | |
| T5 | G5 | 38968 | LEDT5/LC/G/2/830 | 20 | 22 | 3000K | 80 | 70,000 | - | Damp | 800 | 1200 | 1550 | 1800 | 2150 |
| | G5 | 38983 | LEDT5/LC/G/2/840 | 20 | 22 | 4000K | 80 | 70,000 | - | Damp | 850 | 1250 | 1650 | 1900 | 2200 |
| | G5 | 38992 | LEDT5/LC/G/2/850 | 20 | 22 | 5000K | 80 | 70,000 | - | Damp | 850 | 1250 | 1650 | 1900 | 2200 |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[4] Not all product variations on this page are DLC qualified. Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
Please note Current lamps are not for sale for use in Yukon Territory in Canada


# LED Lamps - HID




# LED Lamps - HID

GE LED lamps for HID replacement utilize a proprietary design with active cooling, which allows for high output from a compact size. The length and diameter match HID ANSI profiles. These lamps feature omnidirectional light output, with similar distribution to traditional HID lamps. This enables GE LED lamps to fit in a variety of fixtures while providing equivalent light levels to HID. All of the GE LED lamps in this category are Type B, which means the fixture is re-wired to bypass the ballast.


## Lamp **Drawings** (not drawn to scale)




ED17




ED23.5




ED37



ED18



ED28



BT56

## Base **Identification** (not drawn to scale)



Med Screw
E26

Mog Screw
E39

EX39

## LED Lamps – HID Portfolio Snapshot



| Profile | | ED17 | ED23.5 | ED28 | ED18 | | ED37 | BT56 |
|---|---|---|---|---|---|---|---|---|
| Base | | E26/EX39 Adapter | E26/EX39 Adapter EX39 | EX39 | EX39 | | EX39 | EX39 |
| Active Cooling LED HID Lamps | Voltage | 120-277 120-347 | 120-277 277-480 | 120-277 277-480 | 277-480 | 120-277 277-480 | 208-277 277-480 | 208-277 277-480 |
| | Wattage | 21W - 45W | 50W - 80W | 73W - 125W (UXL) 90W - 150W | 120W | 180W | 210W - 330W (UXL) 200W - 450W | 520W |
| | Lumens | 3,400 - 7,000 | 7,500 - 12,500 | 14,000 - 23,500 | 20,000 | 30,000 | 35,000 - 68,000 | 106,000 |
| | NEMA MH Equivalent | 70W - 175W | 150W - 250W | 250W - 400W | 360W | 400W | 400W - 1000W | 1500W |
| | NEMA HPS Equivalent | 50W - 100W | 100W - 150W | 200W - 310W | 250W | 400W | 400W - 750W | 1000W |
| | Hazardous Location | 21W, 35W, 45W | 80W | 150W | | | | |
| Passive Cooling LED HID Lamps | Voltage | 120-347 | 120-277 | 120-277 | | | | |
| | Wattage | 13W - 25W | 32W - 46W | 46W - 70W | | | | |
| | Lumens | 2,300 - 4,000 | 5,000 - 7,500 | 8,400 - 12,000 | | | | |
| | NEMA MH Equivalent | 50W - 70W | 150W - 175W | 150W - 250W | | | | |
| | NEMA HPS Equivalent | 35W - 70W | 70W - 100W | 100W - 150W | | | | |

*Refer to subsequent pages for full product specifications including selectable options

## Catalog Logic:

**Bulb Shape:** Bulb shape (corresponds to Traditional HID shape).

**Watts:** Energy Used (as defined by FTC Lamp Label Rules)

**Base Type:** ANSI Base

**Order Code:** Use the order code when ordering to ensure that you receive the exact product you require

**Description:** Lamp Model Description

**Volts:** Lamp data is based on operation at rated voltage

**Carton Quantity:** Number of lamps packed in a carton

**MOL (in):** Maximum Overall Length in inches

**MOD (in):** Maximum Overall Diameter in inches

**Lumens:** Light output (as defined by FTC Lamp Label Rules)

**Color Temperature (K):** A measure of the visual "warmth" or "coolness" of the light from the lamp. The higher the value, the whiter or "cooler" the light appears.

**Color Rendering Index (CRI or R):** An indication of the ability of the lamp to render object colors in a normal natural way. The higher the number (0-100), the better the color appearance.

**Wattage Replacement:** Wattage of Traditional Lamp the LED Lamp is meant to replace

**Rated Life L70:** Hours of operation the lamp will provide before reaching 70% of its original lumen output

**Dimmable:** Indicates whether a lamp is dimmable or not

**DLC:** Indicates whether product is listed on the DesignLights Consortium Qualified Products List

**Location Rating:** Location Rating as defined for LED Lamps by UL 1993

| Bulb Shape | Base Type* | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | MOD (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | Dimmable | DLC*[3,4] | Location Rating[5,6] |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LED Replacement Lamps for HID - Ballast Bypass (Type B) - Hazardous Locations | | | | | | | | | | | | | | | | |
| ED17 | E26/EX39 | 21 | 93134832 | LED21ED17/730/HAZ | 120-277 | 3 | 5.4 | 2.6 | 3,000 | 3000K | >70 | 50W HPS / 70W MH | 50,000 | - | - | Damp |

**LED21ED17/730/HAZ**

- LED21 — Wattage
- ED17 — Bulb Shape
- 7 — CRI (7 = 70)
- 30 — CCT (30 = 3000K)
- HAZ — Hazardous Locations

## NEMA LED HID Wattage Equivalency

The National Electrical Manufacturers Association (NEMA) has published NEMA LS 20037-2024 (formerly NEMA LL 10-2020) Replacing HID Lamps with LED Lamps: Light Output Equivalency Claims. Current uses this Standard for LED products replacing HID lamps, meeting or exceeding the minimum LED light output for equivalency claims. The LED wattage equivalency varies based on the type of HID lamp being replaced - Metal Halide (MH) or High Pressure Sodium (HPS).

| Metal Halide Lamp Wattage (W) | Metal Halide Initial Light Output (lm) | Minimum LED Lamp Initial Light Output (lm) | Current LED Ordinary Location Retrofit Lamps Active Cooling | Current LED Selectable Ordinary Location Retrofit Lamps Active Cooling | Current LED Selectable Ordinary Location Retrofit Lamps Passive Cooling | Current LED Hazardous Location Retrofit Lamps Active Cooling |
|---|---|---|---|---|---|---|
| 50 | 3,200 | 2,000 | LED21ED17 | LED/LC/ED17 | LED/LC/ED17P | LED21ED17/HAZ |
| 70 | 5,200 | 3,000 | LED21ED17 | LED/LC/ED17 | LED/LC/ED17P | LED21ED17/HAZ |
| 100 | 8,100 | 5,000 | LED35ED17; LED45ED17 | LED/LC/ED17 | | LED35ED17/HAZ; LED45ED17/HAZ |
| 150 | 12,000 | 7,500 | LED50ED23.5 | LED/LC/ED23.5 | LED/LC/ED23.5P; LED/LC/ED28P | |
| 175 | 11,000 | 7,000 | LED45ED17; LED50ED23.5 | LED/LC/ED17; LED/LC/ED23.5 | LED/LC/ED23.5P; LED/LC/ED28P | |
| 250 | 19,100 | 12,000 | LED80ED23.5 | LED/LC/ED23.5 | LED/LC/ED28P | LED80ED23.5/HAZ |
| 320 | 25,600 | 16,500 | LED115ED28 | LED/LC/ED28 | | |
| 350 | 28,400 | 18,000 | LED115ED28 | LED/LC/ED28 | | |
| 360 | 29,400 | 19,000 | LED150ED28; LED120ED18 | LED/LC/ED28 | | LED150ED28/HAZ |
| 400 | 33,100 | 21,500 | LED150ED28; LED180ED18 | LED/LC/ED28; LED/LC/ED37 | | LED150ED28/HAZ |
| 750 | 72,300 | 46,500 | LED360ED37 | LED/LC/ED37 | | |
| 1,000 | 100,280 | 65,000 | LED450BT56; LED470BT56 | LED/LC/ED37 | | |
| 1,500 | 153,000 | 99,450 | LED520BT56 | | | |

| HPS Lamp Wattage (W) | HPS Initial Light Output (lm) | Minimum LED Lamp Initial Light Output (lm) | Current LED Ordinary Location Retrofit Lamps Active Cooling | Current LED Selectable Ordinary Location Retrofit Lamps Active Cooling | Current LED Selectable Ordinary Location Retrofit Lamps Passive Cooling | Current LED Hazardous Location Retrofit Lamps Active Cooling |
|---|---|---|---|---|---|---|
| 50 | 4,500 | 2,500 | LED21ED17 | LED/LC/ED17 | LED/LC/ED17P | LED21ED17/HAZ |
| 70 | 6,300 | 4,000 | LED35ED17 | LED/LC/ED17 | LED/LC/ED17P | LED35ED17/HAZ |
| 100 | 9,500 | 6,000 | LED45ED17; LED50ED23.5 | LED/LC/ED17; LED/LC/ED23.5 | LED/LC/ED23.5P; LED/LC/ED28P | LED45ED17/HAZ |
| 150 | 13,000 | 8,500 | LED80ED23.5 | LED/LC/ED23.5 | LED/LC/ED28P | LED80ED23.5/HAZ |
| 200 | 19,500 | 12,500 | | LED/LC/ED23.5 | | |
| 250 | 26,000 | 17,000 | LED115ED28; LED120ED18 | LED/LC/ED28 | | |
| 310 | 33,200 | 21,500 | LED150ED28 | LED/LC/ED28 | | LED150ED28/HAZ |
| 400 | 44,000 | 29,000 | LED180ED18; LED270BT56 | LED/LC/ED37 | | |
| 600 | 66,000 | 42,500 | LED360ED37 | LED/LC/ED37 | | |
| 750 | 82,500 | 53,500 | LED450BT56 | LED/LC/ED37 | | |
| 1,000 | 110,000 | 73,000 | LED470BT56; LED520BT56 | | | |

# LED Lamps - HID

Current offers unmatched flexibility in a **HID LED Replacement Lamp**.
Select wattage and color temperature at the flick of a switch.

LumenChoice® + SpectraChoice™ ED17, ED23.5 and ED28 lamps maximize the potential to reduce inventory and streamline product lists. These lamps allow installers to react to a wide variety of needs, providing the ability to adjust both the color temperature of the light and the brightness. Utilizing proprietary active cooling technology, Selectable LED HID lamps still match the length and diameter of the HID ANSI profile, so size isn't an issue when trying to fit these lamps into existing fixtures.

But what about when it's known a site prefers a specific color temperature? Selectable LumenChoice® ED37 replacement lamps provide a single color temperature SKU with lumen level selectability to ensure that you always have the perfect amount of light for any space at your site.

LumenChoice®




**Select** wattage (lumens) using built-in switch.

SpectraChoice™




**Select** color temperature using built-in switch.




***Even more versatility***
Each E26 lamp comes with a mogul base adapter.
Lamps may be used in E26 or E39/EX39 sockets.

## Selectable LumenChoice® + SpectraChoice™ HID Replacement - Type B

| Bulb Shape | Base Type | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | MOD (in) | Selectable Watts* | Selectable Lumens (Initial)* | Selectable Color Temp. (Initial)* | Wattage Replacement[7] | CRI | Rated Life L70 (Hrs)[1] | DLC® ID[3,4] | Location Rating[5,6] |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LED Replacement Lamp for HID - Ballast Bypass (Type B) | | | | | | | | | | | | | | | |
| ED17 | E26/ EX39 | 93303384 | LED/LC/ED17/7SC | 120-277 | 3 | 5.4 | 2.6 | 21<br>35*<br>45 | 3,400<br>5,500*<br>7,000 | 3000K<br>4000K*<br>5000K | 50W HPS / 70W MH<br>70W HPS / 100W MH<br>100W HPS / 175W MH | >70 | 50,000 | - | Damp |
| | E26/ EX39 | 93314526 | LED/LC/ED17/7SC/120-347 | 120-347 | 3 | 5.4 | 2.6 | 21<br>35*<br>45 | 3,400<br>5,500*<br>7,000 | 3000K<br>4000K*<br>5000K | 50W HPS / 70W MH<br>70W HPS / 100W MH<br>100W HPS / 175W MH | >70 | 50,000 | - | Damp |
| ED23.5 | E26/ EX39 | 93312104 | LED/LC/ED23.5M/7SC | 120-277 | 3 | 7.8 | 3.7 | 50<br>65<br>80* | 8,200<br>10,500<br>12,500* | 3000K<br>4000K<br>5000K* | 100W HPS / 150W MH<br>150W HPS / 150W MH<br>150W HPS / 250W MH | >70 | 50,000 | - | Damp |
| | EX39 | 93312106 | LED/LC/ED23.5/7SC | 120-277 | 3 | 7.8 | 3.7 | 50<br>65<br>80* | 8,200<br>10,500<br>12,500* | 3000K<br>4000K<br>5000K* | 100W HPS / 150W MH<br>150W HPS / 150W MH<br>150W HPS / 250W MH | >70 | 50,000 | S-4V5N0G | Damp |
| | EX39 | 93314766 | LED/LC/ED23.5/7SC/277-480 | 277-480 | 3 | 7.8 | 3.7 | 50<br>65<br>80* | 8,200<br>10,500<br>12,500* | 3000K<br>4000K<br>5000K* | 100W HPS / 150W MH<br>150W HPS / 150W MH<br>150W HPS / 250W MH | >70 | 50,000 | S-Y2WDPN / S-S2HLFY | Damp |
| ED28 | EX39 | 93312102 | LED/LC/ED28/7SC | 120-277 | 3 | 8.3 | 4.1 | 90<br>115<br>150* | 14,000<br>18,000<br>23,500* | 3000K<br>4000K<br>5000K* | 200W HPS / 250W MH<br>250W HPS / 350W MH<br>310W HPS / 400W MH | >70 | 50,000 | S-MB9GRL / S-NMTK94 | Damp |
| | EX39 | 93314772 | LED/LC/ED28/7SC/277-480 | 277-480 | 3 | 8.3 | 4.1 | 90<br>115<br>150* | 14,000<br>18,000<br>23,500* | 3000K<br>4000K<br>5000K* | 200W HPS / 250W MH<br>250W HPS / 350W MH<br>310W HPS / 400W MH | >70 | 50,000 | S-WWN1WP / S-3WC1C9 | Damp |

## Selectable LumenChoice® HID Replacement - Type B

| Bulb Shape | Base Type | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | MOD (in) | Selectable Watts* | Selectable Lumens (Initial)* | Color Temp. (Initial) | Wattage Replacement[7] | CRI | Rated Life L70 (Hrs)[1] | DLC® ID[3,4] | Location Rating[5,6] |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LED Replacement Lamp for HID - Ballast Bypass (Type B) | | | | | | | | | | | | | | | |
| ED37 | EX39 | 93321818 | LED/LC/ED37/740/208-277 | 208-277 | 3 | 11.3 | 5.6 | 200<br>325<br>450* | 35,000<br>53,500<br>68,000* | 4000K | 400W HPS / 400W MH<br>750W HPS / 750W MH<br>750W HPS / 1000W MH | >70 | 50,000 | S-TQ7WXV | Damp |
| | EX39 | 93311586 | LED/LC/ED37/740 | 277-480 | 3 | 11.3 | 5.6 | 200<br>325<br>450* | 35,000<br>53,500<br>68,000* | 4000K | 400W HPS / 400W MH<br>750W HPS / 750W MH<br>750W HPS / 1000W MH | >70 | 50,000 | S-ZZMLJT | Damp |
| | EX39 | 93321820 | LED/LC/ED37/750/208-277 | 208-277 | 3 | 11.3 | 5.6 | 200<br>325<br>450* | 35,000<br>53,500<br>68,000* | 5000K | 400W HPS / 400W MH<br>750W HPS / 750W MH<br>750W HPS / 1000W MH | >70 | 50,000 | S-T4ZBKH | Damp |
| | EX39 | 93311587 | LED/LC/ED37/750 | 277-480 | 3 | 11.3 | 5.6 | 200<br>325<br>450* | 35,000<br>53,500<br>68,000* | 5000K | 400W HPS / 400W MH<br>750W HPS / 750W MH<br>750W HPS / 1000W MH | >70 | 50,000 | S-25L41Q | Damp |

## Warm Selectable LumenChoice® + SpectraChoice™ HID Replacement - Type B

| Bulb Shape | Base Type | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | MOD (in) | Selectable Watts* | Selectable Lumens (Initial)* | Selectable Color Temp. (Initial)* | Wattage Replacement[7] | CRI | Rated Life L70 (Hrs)[1] | DLC®[3,4] | Location Rating[5,6] |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LED Replacement Lamp for HID - Ballast Bypass (Type B) | | | | | | | | | | | | | | | |
| ED17 | E26/ EX39 | 93315986 | LED/LC/ED17/7WSC/120-347 | 120-347 | 3 | 5.4 | 2.6 | 21 | 2,450 | 1800K | 35W HPS / 50W MH | >70 | 50,000 | - | Damp |
| | | | | | | | | | 3,000 | 2200K | 35W HPS / 50W MH | | | | |
| | | | | | | | | | 3,300 | 2700K | 50W HPS / 50W MH | | | | |
| | | | | | | | | 35* | 3,950 | 1800K | 35W HPS / 50W MH | | | | |
| | | | | | | | | | 4,900* | 2200K* | 50W HPS / 70W MH | | | | |
| | | | | | | | | | 5,350 | 2700K | 70W HPS / 70W MH | | | | |
| | | | | | | | | 45 | 4,900 | 1800K | 50W HPS / 70W MH | | | | |
| | | | | | | | | | 6,200 | 2200K | 70W HPS / 70W MH | | | | |
| | | | | | | | | | 6,650 | 2700K | 70W HPS / 100W MH | | | | |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = 1
[3] E26 based products are not eligible for DLC. Not all product variations on this page are DLC qualified. Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
[4] Do not use with phase-cut dimmers. Dimming functions only with external Variac control devices.
[5] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[6] Not suitable for air-tight explosive or hazardous fixtures.
[7] Wattage Replacement levels correspond with wattage levels. Wattage Replacements based on NEMA Standards Publication LL 10-2020 *Replacing HID Lamps with LED Lamps: Light Output Equivalency Claims.*
* Default wattage and color temperature settings noted by "*" in tables above.
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## Leading the way in **energy savings** for HID replacements

Incorporating state-of-the-art active cooling and LEDs, GE UXL LED Lamps provide maximum energy savings and utility rebate potential for key HID wattages. The UXL ED37 lamps provide up to 65,000 lumens, achieving 1000W Metal Halide equivalency, while using only 330 Watts – a 27% savings vs. other 1000W replacements at 450 Watts. The UXL ED28 lamps provide up to 23,500 lumens, achieving 400W Metal Halide equivalency, while using only 125 Watts – a 17% savings vs. other 400W replacements at 150 Watts. UXL lamps feature three wattage levels that may be selected using a built-in switch, offering the chance to save even more energy instantly if an application allows for lower light levels. The lamp shapes adhere to the maximum ANSI length and diameter of the traditional HID lamps they are meant to replace, just like other GE LED lamps, while setting a new standard for lumens per watt.



ED28



ED37

## **Selectable LumenChoice® UXL HID Replacement** - Type B

| Bulb Shape | Base Type | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | MOD (in) | Selectable Watts* | Selectable Lumens (Initial)* | Color Temp. (Initial) | Wattage Replacement[7] | CRI | Rated Life L70 (Hrs)[1] | DLC*[3] ID[3,4] | Location Rating[5,6] |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **LED Replacement Lamp for HID - Ballast Bypass (Type B)** | | | | | | | | | | | | | | | |
| ED28 | EX39 | 93324112 | LED/LC/ED28/740UXL | 120-277 | 3 | 8.3 | 4.1 | 73<br>95<br>125* | 14,000<br>18,000<br>23,500* | 4000K | 200W HPS / 250W MH<br>250W HPS / 350W MH<br>310W HPS / 400W MH | >70 | 50,000 | - | Damp |
| | EX39 | 93324118 | LED/LC/ED28/750UXL | 120-277 | 3 | 8.3 | 4.1 | 73<br>95<br>125* | 14,000<br>18,000<br>23,500* | 5000K | 200W HPS / 250W MH<br>250W HPS / 350W MH<br>310W HPS / 400W MH | >70 | 50,000 | - | Damp |
| ED37 | EX39 | 93324104 | LED/LC/ED37/740UXL | 277-480 | 3 | 11.3 | 5.6 | 210<br>270<br>330* | 42,000<br>53,500<br>65,000* | 4000K | 400W HPS / 400W MH<br>750W HPS / 750W MH<br>750W HPS / 1000W MH | >70 | 50,000 | - | Damp |
| | EX39 | 93324106 | LED/LC/ED37/750UXL | 277-480 | 3 | 11.3 | 5.6 | 210<br>270<br>330* | 42,000<br>53,500<br>65,000* | 5000K | 400W HPS / 400W MH<br>750W HPS / 750W MH<br>750W HPS / 1000W MH | >70 | 50,000 | - | Damp |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = 1
[3] Not all product variations on this page are DLC qualified. Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
[4] Do not use with phase-cut dimmers. Dimming functions only with external Variac control devices.
[5] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[6] Not suitable for air-tight explosive or hazardous fixtures.
[7] Wattage Replacement levels correspond with wattage levels. Wattage Replacements based on NEMA Standards Publication LL 10-2020 *Replacing HID Lamps with LED Lamps: Light Output Equivalency Claims.*
* Default wattage and color temperature settings noted by "*" in tables above.
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## **Unmatched lumen output** from an LED lamp

GE LED High Output BT56 lamps provide industry-leading lumen output, making it possible to upgrade more applications to LED without replacing the entire fixture. GE lamps adhere to the BT56 ANSI profile for length and diameter to ensure that they will fit into existing fixture applications and utilize the existing optics. The existing fixture is wired to bypass the ballast, which reduces energy use and eliminates the need to check ballast compatibility. Benefits of retrofitting to the HO BT56 lamps include energy savings, with up to a 68% reduction in wattage, and maintenance savings due to the longevity of the LED HID lamps (50,000 hours vs. 3,000 hours for a typical 1500W Metal Halide). Target markets for these lamps are Parks and Recreation sports lighting and high mast applications.






## High Output BT56 HID Replacement

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | MOD (in) | Lumens (Initial) | Color Temp. | CRI | Wattage Replacement[6] | Rated Life L70 (Hrs)[1] | DLC[4,5] | Location Rating[3] |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **LED Replacement Lamp for HID - Ballast Bypass (Type B)** | | | | | | | | | | | | | | | |
| BT56 | EX39 | 470 | 93303389 | LED470BT56/740 | 277-480 | 3 | 12.8 | 5.6 | 85,000 | 4000K | >70 | 1000W HPS/1000W MH | 50,000 | S-E56HRP | Damp, Enclosed |
| | EX39 | 520 | 93320138 | LED520BT56/740/208-277 | 208-277 | 3 | 12.8 | 5.6 | 106,000 | 4000K | >70 | 1000W HPS/1500W MH | 50,000 | S-8J5CHR | Damp, Enclosed |
| | EX39 | 520 | 93320144 | LED520BT56/750/208-277 | 208-277 | 3 | 12.8 | 5.6 | 106,000 | 5000K | >70 | 1000W HPS/1500W MH | 50,000 | S-7CHFSW | Damp, Enclosed |
| | EX39 | 520 | 93322984 | LED520BT56/740/277-480 | 277-480 | 3 | 12.8 | 5.6 | 106,000 | 4000K | >70 | 1000W HPS/1500W MH | 50,000 | S-RB19J3 | Damp, Enclosed |
| | EX39 | 520 | 93322990 | LED520BT56/750/277-480 | 277-480 | 3 | 12.8 | 5.6 | 106,000 | 5000K | >70 | 1000W HPS/1500W MH | 50,000 | S-MMD144 | Damp, Enclosed |

These products are covered by U.S. Patents 10788163 and 10508776. These products may also be covered by other U.S. patents or pending applications.


[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity from Current = 1
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[4] Not all product variations on this page are DLC qualified. Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
[5] Do not use with phase-cut dimmers. Dimming functions only with external Variac control devices.
[6] Wattage Replacements based on NEMA Standards Publication LL 10-2020 *Replacing HID Lamps with LED Lamps: Light Output Equivalency Claims.*
Please note Current lamps are not for sale for use in Yukon Territory in Canada

# LED Lamps - HID

Current offers an industry-exclusive **400W LED HID Replacement in an ED18 Shape**.

GE LED lamps for HID replacement utilize a proprietary design with active cooling, which allows for high output from a compact size. The length and diameter match HID ANSI profiles. These lamps feature omnidirectional light output, with similar distribution to traditional HID lamps. This enables GE LED lamps to fit in a variety of fixtures while providing equivalent light levels to HID, making it possible to upgrade more applications to LED without replacing an entire fixture. All of the GE LED lamps in this category are Type B, which means the fixture is re-wired to bypass the ballast.

## **Lamp Drawings** (not drawn to scale)



LU400

ED18



LED180

## **ED18 HID Replacement** - Type B

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | MOD (in) | Lumens (Initial) | Color Temp. | CRI | Wattage Replacement[6] | Rated Life L70 (Hrs)[1] | DLC[4,5] | Location Rating[3] |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **LED Replacement Lamp for HID - Ballast Bypass (Type B)** | | | | | | | | | | | | | | | |
| ED18 | EX39 | 120 | 93320018 | LED120ED18/730/277-480 | 277-480 | 3 | 9.7 | 3.0 | 20,000 | 3000K | >70 | 250W HPS/360W MH | 50,000 | S-47FGTZ | Damp |
| | EX39 | 120 | 93320024 | LED120ED18/740/277-480 | 277-480 | 3 | 9.7 | 3.0 | 20,000 | 4000K | >70 | 250W HPS/360W MH | 50,000 | S-1NR1YH | Damp |
| | EX39 | 120 | 93320030 | LED120ED18/750/277-480 | 277-480 | 3 | 9.7 | 3.0 | 20,000 | 5000K | >70 | 250W HPS/360W MH | 50,000 | S-MQFM9J | Damp |
| | EX39 | 180 | 93312096 | LED180ED18/730 | 120-277 | 3 | 9.7 | 3.0 | 30,000 | 3000K | >70 | 400W HPS/400W MH | 50,000 | S-F26H3J | Damp |
| | EX39 | 180 | 93312098 | LED180ED18/740 | 120-277 | 3 | 9.7 | 3.0 | 30,000 | 4000K | >70 | 400W HPS/400W MH | 50,000 | S-WN2HR8 | Damp |
| | EX39 | 180 | 93312100 | LED180ED18/750 | 120-277 | 3 | 9.7 | 3.0 | 30,000 | 5000K | >70 | 400W HPS/400W MH | 50,000 | S-BG0B87 | Damp |
| | EX39 | 180 | 93323715 | LED180ED18/722/277-480 | 277-480 | 3 | 9.7 | 3.0 | 26,000 | 2200K | >70 | 250W HPS/360W MH | 50,000 | - | Damp |
| | EX39 | 180 | 93320000 | LED180ED18/730/277-480 | 277-480 | 3 | 9.7 | 3.0 | 30,000 | 3000K | >70 | 400W HPS/400W MH | 50,000 | S-LCDXR9 | Damp |
| | EX39 | 180 | 93320006 | LED180ED18/740/277-480 | 277-480 | 3 | 9.7 | 3.0 | 30,000 | 4000K | >70 | 400W HPS/400W MH | 50,000 | S-9792TD | Damp |
| | EX39 | 180 | 93320012 | LED180ED18/750/277-480 | 277-480 | 3 | 9.7 | 3.0 | 30,000 | 5000K | >70 | 400W HPS/400W MH | 50,000 | S-HYQC7Z | Damp |

These products are covered by U.S. Patents 10788163 and 10508776. These products may also be covered by other U.S. patents or pending applications.

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity from Current = 1
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[4] Not all product variations on this page are DLC qualified. Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
[5] Do not use with phase-cut dimmers. Dimming functions only with external Variac control devices.
[6] Wattage Replacements based on NEMA Standards Publication LL 10-2020 *Replacing HID Lamps with LED Lamps: Light Output Equivalency Claims.*
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## LED HID - Type B

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | MOD (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Wattage Replacement[7] | Rated Life L70 (Hrs)[1] | DLC® ID[3,4] | Location Rating[5,6] |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **LED Replacement Lamps for HID - Ballast Bypass (Type B)** | | | | | | | | | | | | | | | |
| ED17 | E26 | 21 | 27729 | LED21ED17/740 | 120-277 | 3 | 5.4 | 2.6 | 3,400 | 4000K | >70 | 50W HPS / 70W MH | 50,000 | - | Damp |
| | E26 | 21 | 27732 | LED21ED17/750 | 120-277 | 3 | 5.4 | 2.6 | 3,400 | 5000K | >70 | 50W HPS / 70W MH | 50,000 | - | Damp |
| | E26 | 35 | 93112114 | LED35ED17/730 | 120-277 | 3 | 5.4 | 2.6 | 5,000 | 3000K | >70 | 70W HPS / 100W MH | 50,000 | - | Damp |
| | E26 | 35 | 27602 | LED35ED17/740 | 120-277 | 3 | 5.4 | 2.6 | 5,000 | 4000K | >70 | 70W HPS / 100W MH | 50,000 | - | Damp |
| | E26 | 35 | 27724 | LED35ED17/750 | 120-277 | 3 | 5.4 | 2.6 | 5,000 | 5000K | >70 | 70W HPS / 100W MH | 50,000 | - | Damp |
| | E26 | 45 | 93116975 | LED45ED17/835 | 120-277 | 3 | 5.4 | 2.6 | 6,000 | 3500K | >70 | 100W HPS / 100W MH | 50,000 | - | Damp |
| | E26 | 45 | 93148082 | LED45ED17/740 | 120-277 | 3 | 5.4 | 2.6 | 7,000 | 4000K | >70 | 100W HPS / 175W MH | 50,000 | - | Damp |
| | E26 | 45 | 93148081 | LED45ED17/750 | 120-277 | 3 | 5.4 | 2.6 | 7,000 | 5000K | >70 | 100W HPS / 175W MH | 50,000 | - | Damp |
| ED23.5 | E26 | 80 | 22768 | LED80ED23.5M/740 | 120-277 | 3 | 7.8 | 3.7 | 12,000 | 4000K | >70 | 150W HPS / 250W MH | 50,000 | - | Damp |
| | E26 | 80 | 93125008 | LED80ED23.5M/750 | 120-277 | 3 | 7.8 | 3.7 | 12,000 | 5000K | >70 | 150W HPS / 250W MH | 50,000 | - | Damp |
| | EX39 | 50 | 22679 | LED50ED23.5/740 | 120-277 | 3 | 7.8 | 3.7 | 7,500 | 4000K | >70 | 100W HPS / 150W MH | 50,000 | P2LJ433Z | Damp |
| | EX39 | 50 | 22739 | LED50ED23.5/750 | 120-277 | 3 | 7.8 | 3.7 | 7,500 | 5000K | >70 | 100W HPS / 150W MH | 50,000 | P9E7B4MB | Damp |
| | EX39 | 50 | 93154637 | LED50ED23.5/740/277/480 | 277-480 | 3 | 7.8 | 3.7 | 7,500 | 4000K | >70 | 100W HPS / 150W MH | 50,000 | S-QSEC3A | Damp |
| | EX39 | 80 | 22635 | LED80ED23.5/740 | 120-277 | 3 | 7.8 | 3.7 | 12,000 | 4000K | >70 | 150W HPS / 250W MH | 50,000 | PHJ4LA1W | Damp |
| | EX39 | 80 | 22676 | LED80ED23.5/750 | 120-277 | 3 | 7.8 | 3.7 | 12,000 | 5000K | >70 | 150W HPS / 250W MH | 50,000 | PYL1MPL2 | Damp |
| | EX39 | 80 | 93154642 | LED80ED23.5/740/277/480 | 277-480 | 3 | 7.8 | 3.7 | 12,000 | 4000K | >70 | 150W HPS / 250W MH | 50,000 | S-TUGPZM | Damp |
| | EX39 | 80 | 93154640 | LED80ED23.5/750/277/480 | 277-480 | 3 | 7.8 | 3.7 | 12,000 | 5000K | >70 | 150W HPS / 250W MH | 50,000 | S-1FJ4CK | Damp |
| ED28 | EX39 | 115 | 93112197 | LED115ED28/730 | 120-277 | 3 | 8.3 | 4.1 | 18,000 | 3000K | >70 | 250W HPS / 350W MH | 50,000 | PE646DNU / S-PJV8RX | Damp |
| | EX39 | 115 | 22622 | LED115ED28/740 | 120-277 | 3 | 8.3 | 4.1 | 18,000 | 4000K | >70 | 250W HPS / 350W MH | 50,000 | PONSAR2J / S-7Y6F60 | Damp |
| | EX39 | 115 | 22623 | LED115ED28/750 | 120-277 | 3 | 8.3 | 4.1 | 18,000 | 5000K | >70 | 250W HPS / 350W MH | 50,000 | PZFIPZUL / S-VVTYR7 | Damp |
| | EX39 | 115 | 93139853 | LED115ED28/740/277/480 | 277-480 | 3 | 8.3 | 4.1 | 18,000 | 4000K | >70 | 250W HPS / 350W MH | 50,000 | PZ3P5P7U/PEQF29S7 | Damp |
| | EX39 | 150 | 93112198 | LED150ED28/730 | 120-277 | 3 | 8.3 | 4.1 | 23,500 | 3000K | >70 | 310W HPS / 400W MH | 50,000 | PAVD2D0E | Damp |
| | EX39 | 150 | 22611 | LED150ED28/740 | 120-277 | 3 | 8.3 | 4.1 | 23,500 | 4000K | >70 | 310W HPS / 400W MH | 50,000 | P53Y3N60 | Damp |
| | EX39 | 150 | 22613 | LED150ED28/750 | 120-277 | 3 | 8.3 | 4.1 | 23,500 | 5000K | >70 | 310W HPS / 400W MH | 50,000 | P1EL9LHG | Damp |
| ED18 | EX39 | 120 | 93320018 | LED120ED18/730/277-480 | 277-480 | 3 | 9.7 | 3.0 | 20,000 | 3000K | >70 | 250W HPS / 360W MH | 50,000 | S-47FGTZ | Damp |
| | EX39 | 120 | 93320024 | LED120ED18/740/277-480 | 277-480 | 3 | 9.7 | 3.0 | 20,000 | 4000K | >70 | 250W HPS / 360W MH | 50,000 | S-1NR1YH | Damp |
| | EX39 | 120 | 93320030 | LED120ED18/750/277-480 | 277-480 | 3 | 9.7 | 3.0 | 20,000 | 5000K | >70 | 250W HPS / 360W MH | 50,000 | S-MQFM9J | Damp |
| | EX39 | 180 | 93312096 | LED180ED18/730 | 120-277 | 3 | 9.7 | 3.0 | 30,000 | 3000K | >70 | 400W HPS / 400W MH | 50,000 | S-F26H3J | Damp |
| | EX39 | 180 | 93312098 | LED180ED18/740 | 120-277 | 3 | 9.7 | 3.0 | 30,000 | 4000K | >70 | 400W HPS / 400W MH | 50,000 | S-WN2HR8 | Damp |
| | EX39 | 180 | 93312100 | LED180ED18/750 | 120-277 | 3 | 9.7 | 3.0 | 30,000 | 5000K | >70 | 400W HPS / 400W MH | 50,000 | S-BG0B87 | Damp |
| | EX39 | 180 | 93323715 | LED180ED18/722/277-480 | 277-480 | 3 | 9.7 | 3.0 | 26,000 | 2200K | >70 | 250W HPS / 360W MH | 50,000 | - | Damp |
| | EX39 | 180 | 93320000 | LED180ED18/730/277-480 | 277-480 | 3 | 9.7 | 3.0 | 30,000 | 3000K | >70 | 400W HPS / 400W MH | 50,000 | S-LCDXR9 | Damp |
| | EX39 | 180 | 93320006 | LED180ED18/740/277-480 | 277-480 | 3 | 9.7 | 3.0 | 30,000 | 4000K | >70 | 400W HPS / 400W MH | 50,000 | S-9792TD | Damp |
| | EX39 | 180 | 93320012 | LED180ED18/750/277-480 | 277-480 | 3 | 9.7 | 3.0 | 30,000 | 5000K | >70 | 400W HPS / 400W MH | 50,000 | S-HYQC7Z | Damp |
| BT56 | EX39 | 270 | 93153080 | LED270BT56/740/120/277 | 120-277 | 3 | 12.3 | 5.6 | 40,000 | 4000K | >70 | 400W HPS / 400W MH | 50,000 | PG8499V4 | Damp |
| | EX39 | 270 | 93095547 | LED270BT56/740 | 277-480 | 3 | 12.3 | 5.6 | 40,000 | 4000K | >70 | 400W HPS / 400W MH | 50,000 | PW0OLOQL | Damp |
| | EX39 | 270 | 93095553 | LED270BT56/750 | 277-480 | 3 | 12.3 | 5.6 | 40,000 | 5000K | >70 | 400W HPS / 400W MH | 50,000 | PUZP8RVI | Damp |
| | EX39 | 450 | 93153123 | LED450BT56/750/208/277 | 208-277 | 3 | 12.3 | 5.6 | 65,000 | 5000K | >70 | 750W HPS / 1000W MH | 50,000 | PD4K2UXF | Damp |
| | EX39 | 450 | 93096445 | LED450BT56/740 | 277-480 | 3 | 12.3 | 5.6 | 65,000 | 4000K | >70 | 750W HPS / 1000W MH | 50,000 | PLNCOZ5Z | Damp |
| | EX39 | 450 | 93096547 | LED450BT56/750 | 277-480 | 3 | 12.3 | 5.6 | 65,000 | 5000K | >70 | 750W HPS / 1000W MH | 50,000 | PH8F9ZNF | Damp |
| | EX39 | 470 | 93303389 | LED470BT56/740 | 277-480 | 3 | 12.8 | 5.6 | 85,000 | 4000K | >70 | 1000W HPS / 1000W MH | 50,000 | S-E56HRP | Damp |
| | EX39 | 520 | 93320138 | LED520BT56/740/208-277 | 208-277 | 3 | 12.8 | 5.6 | 106,000 | 4000K | >70 | 1000W HPS / 1500W MH | 50,000 | S-8J5CHR | Damp |
| | EX39 | 520 | 93320144 | LED520BT56/750/208-277 | 208-277 | 3 | 12.8 | 5.6 | 106,000 | 5000K | >70 | 1000W HPS / 1500W MH | 50,000 | S-7CHFSW | Damp |
| | EX39 | 520 | 93322984 | LED520BT56/740/277-480 | 277-480 | 3 | 12.8 | 5.6 | 106,000 | 4000K | >70 | 1000W HPS / 1500W MH | 50,000 | S-RB19J3 | Damp |
| | EX39 | 520 | 93322990 | LED520BT56/750/277-480 | 277-480 | 3 | 12.8 | 5.6 | 106,000 | 5000K | >70 | 1000W HPS / 1500W MH | 50,000 | S-MMD144 | Damp |

**Additional Information for LED Replacement Lamps for HID: Open and Closed Rated - Ballast bypass required**
**These products are covered by U.S. Patents 10788163 and 10508776. These products may also be covered by other U.S. patents or pending applications.**

## LED HID Accessories

| Order Code | Description | Carton Qty[2] | Additional Information |
|---|---|---|---|
| 93151372 | LED/E26/EX39/ADAPTER | 60 | E26/EX39 Socket Adapter |
| 93313551 | LED-HID-TETHER-KIT | 20 | 1 Tether Kit |
| 93313553 | LED-HID-4A-FUSE-KIT | 20 | 1 Fuse (4A), 1 Fuse Holder |
| 93313555 | LED-HID-8A-FUSE-KIT | 20 | 1 Fuse (8A), 1 Fuse Holder |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = 1
[3] E26 based products are not eligible for DLC. Not all product variations on this page are DLC qualified. Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
[4] Do not use with phase-cut dimmers. Dimming functions only with external Variac control devices.
[5] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[6] Not suitable for air-tight explosive or hazardous fixtures.
[7] Wattage Replacement levels correspond with wattage levels. Wattage Replacements based on NEMA Standards Publication LL 10-2020 *Replacing HID Lamps with LED Lamps: Light Output Equivalency Claims.*
Please note Current lamps are not for sale for use in Yukon Territory in Canada

# LED Lamps - HID

Current offers a cost-effective LED conversion in a **Passive HID LED Replacement Lamp**. Select wattage and color temperature at the flick of a switch.



Current's Passive Selectable ED23.5 LED HID Replacement Lamps offer a cost effective solution for less demanding applications. Upgrade to LED in lower wattage HID applications that use the ED23.5 or ED28 shape (up to a 100W high pressure sodium, up to 175W metal halide), and significantly increase CRI compared to High Pressure Sodium Lamps, from 21 CRI to 70 CRI. The Passive cooling lamps (no fan) have electronic thermal management to gradually reduce the light as ambient temperatures increase.

LumenChoice® + SpectraChoice™ ED23.5 lamps feature built-in switches to easily allow the change of wattage and color temperature, no tools required. One lamp can cover many applications, reducing inventory & simplifying BOMs.

LumenChoice®+ SpectraChoice™

Current's Passive Selectable LED HID Lamps maintain ANSI length and diameter, ensuring that the lamps will fit into fixtures and utilize existing optics. These lamps feature omnidirectional light output, with similar distribution to traditional HID lamps. This enables GE LED lamps to fit in a variety of fixtures while providing equivalent light levels to HID and utilizing the existing optics. All of the GE LED lamps in this category are Type B, which means the fixture is re-wired to bypass the ballast.

**Lamp Comparison**

| | ED23.5 HID Lamp | Active Cooling Selectable ED23.5 | Passive Cooling Selectable ED23.5 | Other Passive Cooling LED Lamps |
|---|---|---|---|---|
| |  |  |  |  |
| Wattage Levels (W) | | 50 / 65 / 80 | 32 / 39 / 46 | 36 / 45 / 54 |
| Lumen Levels (lm) | | 8,000 / 10,300 / 12,000 | 5,000 / 6,300 / 7,500 | 5,040 / 6,300 / 7,560 |
| Color Temp. Levels (K) | | 3000K / 4000K / 5000K | 3000K / 4000K / 5000K | 3000K / 4000K / 5000K |
| Base Options | | E26 (with EX39 Adapter) or EX39 | EX39 | EX39 |
| Length (in) | | 7.8 in | 7.8 in | 9.69 in |
| Diameter (in) | | 3.7 in | 3.7 in | 3.35 in |

LumenChoice®+ SpectraChoice™

Select wattage (lumens) and color temperature using built-in switch




Passive Cooling Selectable ED17



## Passive Selectable LumenChoice® + SpectraChoice™ LED HID Replacement - Type B

| Bulb Shape | Base Type | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | MOD (in) | Selectable Watts* | Selectable Lumens (Initial)* | Selectable Color Temp. (Initial)* | Wattage Replacement[6] | CRI | Rated Life L70 (Hrs)[1] | DLC[4,5] | Location Rating[3] |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **LED Replacement Lamp for HID - Ballast Bypass (Type B)** | | | | | | | | | | | | | | | |
| ED17 | E26 | 93316026 | LED/LC/ED17P/7SC/120-347 | 120-347 | 3 | 5.6 | 2.6 | 13<br>19<br>25* | 2,300<br>3,200<br>4,000* | 3000K<br>4000K*<br>5000K | 35W HPS / 50W MH<br>50W HPS / 70W MH<br>70W HPS / 70W MH | >70 | 50,000 | - | Damp |
| ED23.5 | EX39 | 93314601 | LED/LC/ED23.5P/7SC | 120-277 | 3 | 7.8 | 3.7 | 32<br>39<br>46* | 5,000<br>6,300<br>7,500* | 3000K<br>4000K<br>5000K* | 70W HPS / 150W MH<br>70W HPS / 150W MH<br>100W HPS / 175W MH | >70 | 50,000 | S-NDF684 | Damp |
| ED28 | EX39 | 93318804 | LED/LC/ED28P/7SC | 120-277 | 3 | 8.3 | 4.1 | 46<br>58<br>70* | 8,400<br>10,000<br>12,000* | 3000K<br>4000K<br>5000K* | 100W HPS / 150W MH<br>150W HPS / 150W MH<br>150W HPS / 250W MH | >70 | 50,000 | S-CTTCL4 / S-6P5VLS | Damp |

These products are covered by U.S. Patent 10508776. These products may also be covered by other U.S. patents or pending applications.

## Passive Warm Selectable LumenChoice® + SpectraChoice™ HID Replacement - Type B

| Bulb Shape | Base Type | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | MOD (in) | Selectable Watts* | Selectable Lumens (Initial)* | Selectable Color Temp. (Initial)* | Wattage Replacement[6] | CRI | Rated Life L70 (Hrs)[1] | DLC[4,5] | Location Rating[3] |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **LED Replacement Lamp for HID - Ballast Bypass (Type B)** | | | | | | | | | | | | | | | |
| ED17 | E26 | 93318489 | LED/LC/ED17P/7WSC/120-347 | 120-347 | 3 | 5.6 | 2.6 | 13 | 1,600 | 1800K | 35W HPS / 50W MH | >70 | 50,000 | - | Damp |
| | | | | | | | | | 2,000 | 2200K | 35W HPS / 50W MH | | | | |
| | | | | | | | | | 2,200 | 2700K | 35W HPS / 50W MH | | | | |
| | | | | | | | | 19 | 2,200 | 1800K | 35W HPS / 50W MH | | | | |
| | | | | | | | | | 2,700 | 2200K | 35W HPS / 50W MH | | | | |
| | | | | | | | | | 3,000 | 2700K | 35W HPS / 50W MH | | | | |
| | | | | | | | | 25* | 2,800 | 1800K | 35W HPS / 50W MH | | | | |
| | | | | | | | | | 3,400* | 2200K* | 35W HPS / 50W MH | | | | |
| | | | | | | | | | 3,900 | 2700K | 50W HPS / 70W MH | | | | |
| ED28 | EX39 | 93319614 | LED/LC/ED28P/7WSC | 120-277 | 3 | 8.3 | 4.1 | 46 | 6,300 | 1800K | 70W HPS / 70W MH | >70 | 50,000 | - | Damp |
| | | | | | | | | | 7,600 | 2200K | 70W HPS / 100W MH | | | | |
| | | | | | | | | | 8,400 | 2700K | 100W HPS / 150W MH | | | | |
| | | | | | | | | 58 | 7,600 | 1800K | 70W HPS / 100W MH | | | | |
| | | | | | | | | | 9,300 | 2200K | 100W HPS / 100W MH | | | | |
| | | | | | | | | | 10,000 | 2700K | 150W HPS / 150W MH | | | | |
| | | | | | | | | 70* | 9,000 | 1800K | 100W HPS / 100W MH | | | | |
| | | | | | | | | | 11,000* | 2200K* | 150W HPS / 100W MH | | | | |
| | | | | | | | | | 12,000 | 2700K | 150W HPS / 150W MH | | | | |

These products are covered by U.S. Patent 10508776. These products may also be covered by other U.S. patents or pending applications.

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity from Current = 1
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[4] Not all product variations on this page are DLC qualified. Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
[5] Do not use with phase-cut dimmers. Use integrated switch for dimming.
[6] Wattage Replacements based on NEMA Standards Publication LL 10-2020 *Replacing HID Lamps with LED Lamps: Light Output Equivalency Claims.*
**Default wattage and color temperature settings noted by "*" in tables above.*
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## **HID LED Replacement Lamp** Case Studies

470W High Output BT56 LED Replacement lamps were used to retrofit 1500W Metal Halide fixtures at a baseball field in Riverview, New Brunswick, Canada. For more details around the retrofit and the resulting benefits that they realized, visit www.LED.com/inspiration/ballfield-benefits-from-new-high-output-led-lamp.



Drone images capture the before and after of the baseball field highlighting the uniform light coverage after the LED BT56 installation.



## **HID LED Replacement Lamp** Case Studies

Improvements in lighting can make a huge impact on the safety and security of a site. In the example below, 250W Metal Halide HID Lamps were replaced with 80W Type B ED23.5 LED HID Lamps, resulting in a noticeable improvement in visibility and light coverage.



Before: 250W Metal Halide Lamps



After: 80W ED23.5 LED HID Lamps

## **HID LED Replacement Lamp** Case Studies

Residential post top street lights in New Brunswick were upgraded using GE LED Lamps. Warm SpectraChoice™ Selectable ED17 lamps replaced 100W High Pressure Sodium lamps. The 2700K color temperature setting maintained a warm feel for residents, whiter than HPS but not too blue, and the 45W setting provided plenty of light.










**Before:** 100W High Pressure Sodium (HPS) lamps emit a yellow-orange glow throughout the neighborhood, washing out colors due to low CRI. Warm white lights on the houses appear to be a cooler blue color temperature relative to HPS.

**After:** 45W LED lamps produce a warm white light, and improved CRI allows colors to be seen, like the orange driveway markers. The light appears visually brighter. Warm white lights on the houses appear to be consistent with the 2700K LED street lights.

**Lamp Drawings** (not drawn to scale)

ED17 HID Lamp




Active Cooling Selectable ED17



Passive Cooling Selectable ED17



ED28 HID Lamp



Passive Cooling Selectable ED28



## Warm Selectable LumenChoice® + SpectraChoice™ HID Replacement - Type B

| Bulb Shape | Base Type | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | MOD (in) | Selectable Watts* | Selectable Lumens (Initial)* | Selectable Color Temp. (Initial)* | Wattage Replacement[6] | CRI | Rated Life L70 (Hrs)[1] | DLC[*3,7] | Location Rating[4,5] |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LED Replacement Lamp for HID - Ballast Bypass (Type B) | | | | | | | | | | | | | | | |
| ED17 | E26/ EX39 | 93315986 | LED/LC/ED17/7WSC/120-347 | 120-347 | 3 | 5.4 | 2.6 | 21 | 2,450 | 1800K | 35W HPS / 50W MH | >70 | 50,000 | - | Damp |
| | | | | | | | | | 3,000 | 2200K | 35W HPS / 50W MH | | | | |
| | | | | | | | | | 3,300 | 2700K | 50W HPS / 50W MH | | | | |
| | | | | | | | | 35* | 3,950 | 1800K | 35W HPS / 50W MH | | | | |
| | | | | | | | | | 4,900* | 2200K* | 50W HPS / 70W MH | | | | |
| | | | | | | | | | 5,350 | 2700K | 70W HPS / 70W MH | | | | |
| | | | | | | | | 45 | 4,900 | 1800K | 50W HPS / 70W MH | | | | |
| | | | | | | | | | 6,200 | 2200K | 70W HPS / 70W MH | | | | |
| | | | | | | | | | 6,650 | 2700K | 70W HPS / 100W MH | | | | |

## Passive Warm Selectable LumenChoice® + SpectraChoice™ HID Replacement - Type B

| Bulb Shape | Base Type | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | MOD (in) | Selectable Watts* | Selectable Lumens (Initial)* | Selectable Color Temp. (Initial)* | Wattage Replacement[6] | CRI | Rated Life L70 (Hrs)[1] | DLC[*3,7] | Location Rating[4,5] |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LED Replacement Lamp for HID - Ballast Bypass (Type B) | | | | | | | | | | | | | | | |
| ED17 | E26 | 93318489 | LED/LC/ED17P/7WSC/120-347 | 120-347 | 3 | 5.6 | 2.6 | 13 | 1,600 | 1800K | 35W HPS / 50W MH | >70 | 50,000 | - | Damp |
| | | | | | | | | | 2,000 | 2200K | 35W HPS / 50W MH | | | | |
| | | | | | | | | | 2,200 | 2700K | 35W HPS / 50W MH | | | | |
| | | | | | | | | 19 | 2,200 | 1800K | 35W HPS / 50W MH | | | | |
| | | | | | | | | | 2,700 | 2200K | 35W HPS / 50W MH | | | | |
| | | | | | | | | | 3,000 | 2700K | 35W HPS / 50W MH | | | | |
| | | | | | | | | 25* | 2,800 | 1800K | 35W HPS / 50W MH | | | | |
| | | | | | | | | | 3,400* | 2200K* | 35W HPS / 50W MH | | | | |
| | | | | | | | | | 3,900 | 2700K | 50W HPS / 70W MH | | | | |
| ED28 | EX39 | 93319614 | LED/LC/ED28P/7WSC | 120-277 | 3 | 8.3 | 4.1 | 46 | 6,300 | 1800K | 70W HPS / 70W MH | >70 | 50,000 | - | Damp |
| | | | | | | | | | 7,600 | 2200K | 70W HPS / 100W MH | | | | |
| | | | | | | | | | 8,400 | 2700K | 100W HPS / 150W MH | | | | |
| | | | | | | | | 58 | 7,600 | 1800K | 70W HPS / 100W MH | | | | |
| | | | | | | | | | 9,300 | 2200K | 100W HPS / 100W MH | | | | |
| | | | | | | | | | 10,000 | 2700K | 150W HPS / 150W MH | | | | |
| | | | | | | | | 70* | 9,000 | 1800K | 100W HPS / 100W MH | | | | |
| | | | | | | | | | 11,000* | 2200K* | 150W HPS / 100W MH | | | | |
| | | | | | | | | | 12,000 | 2700K | 150W HPS / 150W MH | | | | |
| These products are covered by U.S. Patent 10508776. These products may also be covered by other U.S. patents or pending applications. | | | | | | | | | | | | | | | |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = 1
[3] E26 based products are not eligible for DLC. Not all product variations on this page are DLC qualified. Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
[4] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[5] Not suitable for air-tight explosive or hazardous fixtures.
[6] Wattage Replacement levels correspond with wattage levels. Wattage Replacements based on NEMA Standards Publication LL 10-2020 *Replacing HID Lamps with LED Lamps: Light Output Equivalency Claims.*
[7] Do not use with phase-cut dimmers. Use integrated switch for dimming.
* Default wattage and color temperature settings noted by "*" in tables above.
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## **LED Lamps –** HID for Hazardous Locations

Current offers the industry's most extensive portfolio of LED Lamps certified for use in hazardous locations. LED hazardous location lamps offer an opportunity to realize the benefits of an upgrade to LED lighting at an affordable cost. Retrofits certified to UL844 allow existing hazardous location fixtures to be used, while replacing old HID lamps and bypassing the ballasts. Lamps can provide an attractive ROI when entire fixture upgrades may be cost prohibitive, allowing hazardous location facilities to save on energy costs and improve light quality and reliability without compromising safety.

LED HID Lamps approved for hazardous locations provide customers an innovative lighting solution. These lamps maintain the key features of standard GE LED HID Lamps, with a proprietary active cooling design that allows high output from a compact form, with omnidirectional light output. With E26-based hazardous location lamps, Current also includes an E39 socket adapter in the kit for mogul base applications. This eliminates the possibility of ordering a lamp with the wrong base. The heat profile of Current's LED lamps is lower than traditional HID, which equates to a lower overall temperature code. This may provide additional benefits to a facility, beyond the lower energy consumption and increased longevity of the lamps themselves.



ED17 ED23.5 ED28

## **LED HID** - Type B - Hazardous Locations

| Bulb Shape | Base Type* | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | MOD (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Wattage Replacement[8] | Rated Life L70 (Hrs)[1] | DLC*ID[3,4] | Location Rating [5,@] |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **LED Replacement Lamps for HID - Ballast Bypass (Type B) - Hazardous Locations** | | | | | | | | | | | | | | | |
| ED17 | E26/EX39 | 21 | 93134832 | LED21ED17/730/HAZ | 120-277 | 3 | 5.4 | 2.6 | 3,000 | 3000K | >70 | 50W HPS / 70W MH | 50,000 | - | Damp |
| | E26/EX39 | 21 | 93134833 | LED21ED17/740/HAZ | 120-277 | 3 | 5.4 | 2.6 | 3,000 | 4000K | >70 | 50W HPS / 70W MH | 50,000 | - | Damp |
| | E26/EX39 | 21 | 93134834 | LED21ED17/750/HAZ | 120-277 | 3 | 5.4 | 2.6 | 3,000 | 5000K | >70 | 50W HPS / 70W MH | 50,000 | - | Damp |
| | E26/EX39 | 35 | 93134830 | LED35ED17/740/HAZ | 120-277 | 3 | 5.4 | 2.6 | 5,000 | 4000K | >70 | 70W HPS / 100W MH | 50,000 | - | Damp |
| | E26/EX39 | 35 | 93134831 | LED35ED17/750/HAZ | 120-277 | 3 | 5.4 | 2.6 | 5,000 | 5000K | >70 | 70W HPS / 100W MH | 50,000 | - | Damp |
| | E26/EX39 | 45 | 93134846 | LED45ED17/730/HAZ | 120-277 | 3 | 5.4 | 2.6 | 6,000 | 3000K | >70 | 100W HPS / 100W MH | 50,000 | - | Damp |
| | E26/EX39 | 45 | 93134847 | LED45ED17/740/HAZ | 120-277 | 3 | 5.4 | 2.6 | 6,000 | 4000K | >70 | 100W HPS / 100W MH | 50,000 | - | Damp |
| | E26/EX39 | 45 | 93134848 | LED45ED17/750/HAZ | 120-277 | 3 | 5.4 | 2.6 | 6,000 | 5000K | >70 | 100W HPS / 100W MH | 50,000 | - | Damp |
| ED23.5 | E26/EX39 | 80 | 93141934 | LED80ED23.5/740/HAZ | 120-277 | 3 | 7.8 | 3.7 | 12,000 | 4000K | >70 | 150W HPS / 250W MH | 50,000 | - | Damp |
| | E26/EX39 | 80 | 93141935 | LED80ED23.5/750/HAZ | 120-277 | 3 | 7.8 | 3.7 | 12,000 | 5000K | >70 | 150W HPS / 250W MH | 50,000 | - | Damp |
| | EX39 | 80 | 93148146 | LED80ED23.5/740/277/480/HAZ | 277-480 | 3 | 7.8 | 3.7 | 12,000 | 4000K | >70 | 150W HPS / 250W MH | 50,000 | S-3GZE5Y | Damp |
| | EX39 | 80 | 93148147 | LED80ED23.5/750/277/480/HAZ | 277-480 | 3 | 7.8 | 3.7 | 12,000 | 5000K | >70 | 150W HPS / 250W MH | 50,000 | S-O48JK5 | Damp |
| ED28 | EX39 | 150 | 93154635 | LED150ED28/740/HAZ | 120-277 | 3 | 8.3 | 4.1 | 23,500 | 4000K | >70 | 310W HPS / 400W MH | 50,000 | S-EB9LHA | Damp |
| | EX39 | 150 | 93154636 | LED150ED28/750/HAZ | 120-277 | 3 | 8.3 | 4.1 | 23,500 | 5000K | >70 | 310W HPS / 400W MH | 50,000 | S-S2QAV1 | Damp |
| | EX39 | 150 | 93154647 | LED150ED28/740/277/480/HAZ | 277-480 | 3 | 8.3 | 4.1 | 23,500 | 4000K | >70 | 310W HPS / 400W MH | 50,000 | S-ZN9G32 | Damp |
| | EX39 | 150 | 93154648 | LED150ED28/750/277/480/HAZ | 277-480 | 3 | 8.3 | 4.1 | 23,500 | 5000K | >70 | 310W HPS / 400W MH | 50,000 | S-6UW8HL | Damp |

**Additional Information for LED Replacement Lamps for HID: Open and Closed Rated - Ballast bypass required**
**These products are covered by U.S. Patents 10788163 and 10508776. These products may also be covered by other U.S. patents or pending applications.**

*** EX39 socket adapter is included with HAZ E26 based lamps for mogul base applications.**

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = 1
[3] E26 based products are not eligible for DLC. Not all product variations on this page are DLC qualified. Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
[4] Do not use with phase-cut dimmers. Dimming functions only with external Variac control devices.
[5] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[8] Wattage Replacement levels correspond with wattage levels. Wattage Replacements based on NEMA Standards Publication LL 10-2020 *Replacing HID Lamps with LED Lamps: Light Output Equivalency Claims.*
[@] See Installation Guide for applicable Hazardous Location luminaire fittings
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## What's Considered a Hazardous Location?

The National Electrical Code (NEC) defines hazardous locations in terms of CLASS, DIVISION and GROUP:

- **CLASS I** locations are those in which flammable gases or vapors are or may be present in the air in quantities sufficient to produce explosive or ignitable mixtures.
- **CLASS II** locations are those that are hazardous because of the presence of combustible dust.

Each CLASS is further defined as either DIVISION 1 or DIVISION 2.

- **DIVISION 1** is an environment that is normally hazardous.
- **DIVISION 2** is an environment that is not normally hazardous.

**GROUP** defines the specific hazardous material in the surrounding atmosphere. See the table below for specific examples.

| NEC Class | Division | Group | Typical Atmosphere and Auto-ignition Temperatures |
|---|---|---|---|
| I - Gases, Vapors | 2 - Not normally present | A | Acetylene (305°C, 581°F) |
| | | B | Hydrogen (502°C, 986°F) manufactured gases containing more than 30% hydrogen (by volume) |
| | | C | Ethylene (450°C, 842°F)<br>Cylopropane (503°C, 938°F) |
| | | D | Hexane (225°C, 437°F)<br>Butane (288°C, 550°F)<br>Propane (450°C, 842°F)<br>Acetone (465°C, 869°F)<br>Benzene (420°C, 788°F)<br>Gasoline (280°-471°C, 536°-880°F) |
| II - Combustible Dusts | 1 - Normally present<br>2 - Not normally present | E | Metal Dusts (Aluminum, Magnesium) |
| | | F | Carbonaceous Dusts (Coal, Carbon black, Charcoal, Coke) |
| | | G | Dusts not in Groups E or F (Flour, Grain, Wood, Plastic) |

*Typical Hazardous Substances and Auto-ignition Temperatures by Group*

## How are LED Retrofits Certified?

UL evaluates Retrofit Luminaire Conversion Kits for Use in Hazardous Locations in accordance with the appropriate Standards. LED Lamps are UL-certified as part of Retrofit Kits that also include an installation guide detailing instructions for retrofitting hazardous location luminaires and a fixture label that indicates the lamp being used and associated new temperature code.

See lamp installation guides for full luminaire fitting details.

### Current Hazardous Location Lamps – Approved UL Fixtures by Classification

| Classifications: Class 1, Division 2, Groups A, B, C, D | | | |
|---|---|---|---|
| UL HazLoc Fixture Type | ED17 | ED23.5 | ED28 |
| GE Filtr-Gard® H2 | Yes | Yes | Yes |
| GE Powr-Gard® H9 | - | - | - |
| Appleton Mercmaster™ II | Yes | Yes | Yes |
| Appleton Mercmaster™ III | Yes | Yes | Yes |
| Crouse-Hinds Champ® VMV | Yes | Yes | Yes |
| Thomas & Betts Hazlux® 3 | Yes | Yes | Yes |
| Hubbell Killark® VM Series | Yes | Yes | Yes |
| Holophane Petrolux® P3M | Yes | Yes | - |
| Holophane Petrolux® II PETL | - | - | Yes |

| Classifications: Class 2, Division 1, Groups E,F, G; Class 2, Division 2, Groups F, G | | | |
|---|---|---|---|
| UL HazLoc Fixture Type | ED17 | ED23.5 | ED28 |
| GE Filtr-Gard® H2 | - | - | - |
| GE Powr-Gard® H9 | Yes | Yes | - |
| Appleton Mercmaster™ II | Yes | Yes | Yes |
| Appleton Mercmaster™ III | Yes | Yes | Yes |
| Crouse-Hinds Champ® VMV | Yes | - | Yes |
| Thomas & Betts Hazlux® 3 | Yes | Yes | Yes |
| Hubbell Killark® VM Series | Yes | Yes | Yes |
| Holophane Petrolux® P3M | Yes | Yes | - |
| Holophane Petrolux® II PETL | - | - | Yes |

## Ohio Manufacturing Facility Replaces Dated HPS Lamps with New Current LED HID Lamps Approved for Hazardous Locations



Before: 250W High Pressure Sodium Lamps



After: 45W ED17 LED HID Lamps

An Ohio-based company needed a solution for a dimly lit manufacturing plant, and Current jumped at the opportunity to help. This wasn't a normal lamp refit, but Current knew its expansive LED Lamp portfolio had a product up for the challenge.

From the outset of the project, it was apparent that the customer needed lamps that would fit into traditional hazardous rated High Pressure Sodium (HPS) fixtures. Installation needed to be quick to avoid downtime, and budgets were tight, so avoiding significant renovations was preferred. The new LED HID replacement lamps needed to be approved for hazardous rated fixtures, as the plant deals with hazardous materials in its processes.

**The Solution**

Current recommended its Hazardous LED HID Replacement Lamps. These LED lamps are designed for those rugged environments where long lasting performance is a necessity. Current's LED HID replacement lamps for hazardous locations are certified for use in a variety of hazardous location luminaires, including Class I Division 2, Class II Division 1, and Class II Division 2 applications.

With a much longer life compared to a standard HID lamp, these LED lamps would provide consistent, dependable lighting in a facility that desperately needed it. The LED lamps use much less energy compared with their HPS counterparts. This not only saves money, but it also provides the facility with an improved temperature code. This is important as it reduces the ambient temperature of the fixture by an average of 95°C in the most commonly used fixtures. By lowering the temperature code, you decrease the air temperature around the fixture, which makes for a safer operating environment. This allows customers the ability to install higher lumen lamps in locations that they were previously only able to provide low wattage/lumen lamps.

**Why Current's Lamps**

One consideration for this plant was ongoing maintenance. Its existing lighting was not easy to replace and required significant manpower to maintain or update. Current was able to give them a solution that would last 2.5 times longer while still delivering a more efficient and effective solution. At the beginning of the installation, the team quickly realized they had fixtures with both medium (E26) and mogul (E39) sockets, which posed an issue with managing multiple lamp designs for the installation. Current's product team prepared for this exact scenario by including a mogul-base (E39) adapter with each lamp. Current's product strategy eliminated the possibility of ordering a lamp with the wrong base and the installer having to come back at a later date at an additional charge. This also reduces the SKU count for a project.

In addition to the longer life of LEDs, the industrial plant was also drawn to the fact that Current's lamps can go from a 250W HPS Lamp all the way down to 45W, which means increased savings in addition to longer life. The plant is now realizing $25,000 annual savings compared to their traditional lamps. Over the life of the lamp, they will save $125,000, and switching to Current's Hazardous Location LED HID replacement lamps will help them achieve payback in just 9 months.

Many manufacturing areas face uneven light distribution and dark spots. Most common is burned out lamps that cost time and money to replace because operations have to stop while these are fixed. Current's hazardous location lamps offer a five-year/50,000-hour warranty to give the end user peace of mind and avoid these issues.

**The Results**


Installing the lamps was a smooth process. Once the new lights were turned on, the change was obvious: Areas were brighter.


The feedback from members working in the facility is overwhelmingly positive. They report that spaces are much brighter, providing better visibility in places that used to be very dark, and making the plant look and feel like a better place to work. In fact, the facility has already requested additional lamp retrofits in the plant due to the success and effectiveness they are witnessing after just a few weeks.

“The rooms look fantastic, it’s way easier to work and see, and instantly modernizes and brightens the entire area. It’s hard to believe, and somewhat embarrassing, that we lived with and just accepted the old lighting for so long,” the plant manager said.

Another worker added, “The new LED lamps make a drastic difference throughout our facility. With the new upgrade from the old yellow tinted HPS lights, some areas that once had a dark and gloomy feeling have now become areas where our employees want to work. It is amazing how something so little can improve the area and the site’s morale so much.”

Current’s Hazardous Location LED HID Replacement Lamps were the perfect solution for this manufacturing plant. Now, with better lighting, lower maintenance costs and reduced energy expenses, the facility can be safer and more productive.





## **LED Lamps** - Type A Plug-ins

Type A LED plug-in lamps are direct replacements for pin-based compact fluorescent lamps. These lamps operate from CFL ballasts. Horizontal and vertical orientation lamps are offered in order to minimize energy consumption and improve fixture efficiency. Choose the lamp orientation that suits the application.



## Catalog Logic:

**Bulb Shape:** Bulb shape followed by its size (the maximum diameter of the bulb expressed in eighths of an inch).

**Base Type:** ANSI Base

**Watts:** Nominal Lamp Watts on ballast

**Order Code:** Use the order code when ordering to ensure that you receive the exact product you require

**Description:** Lamp Model Description

**Carton Quantity:** Number of lamps packed in a carton

**MOL (in):** Maximum Overall Length in inches

**Lumens:** Light output (as defined by FTC Lamp Label Rules)

**Color Temperature (K):** A measure of the visual "warmth" or "coolness" of the light from the lamp. The higher the value, the whiter or "cooler" the light appears.

**Color Rendering Index (CRI or R):** An indication of the ability of the lamp to render object colors in a normal natural way. The higher the number (0-100), the better the color appearance.

**Wattage Replacement:** Wattage of Traditional Lamp the LED Lamp is meant to replace

**Rated Life L70:** Hours of operation the lamp will provide before reaching 70% of its original lumen output

**Dimmable:** Indicates whether a lamp is dimmable or not

**DLC:** Indicates whether product is listed on the DesignLights Consortium Qualified Products List

**Location Rating:** Location Rating as defined for LED Lamps by UL 1993


**Additional Information:** Typical application and/or other important information

| Bulb Shape | Base Type | Lamp Watts | Order Code | Description | Carton Qty[2] | MOL (In) | Lumens (Initial) | Color Temp (Initial) | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | Dim-mable | DLC*[4] | Location Rating[3] | Additional Information# |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Vertical Type A 4-pin** | | | | | | | | | | | | | | | |
| Plug-In | G24q/GX24q | 9 | 33994 | LED9G24Q-H/827 | 6 | 5.31 | 1100 | 2700K | 80 | 13/18/26 | 50,000 | - | S-6PKGMC | Damp | Requires Electronic Ballast, Fully Enclosed |


**LED9GX24Q-H/827**

- LED9 — Wattage
- GX24Q — Base
- H — Orientation (H = Horizontal, V = Vertical)
- 8 — CRI (8 = 80)
- 27 — CCT (27 = 2700K)

## Lamp **Drawings** (not drawn to scale)




Type A
GX24q




Type A
G24q


Type A
G24d



Type A
G24q



## Type A - 2-pin Plug-ins







## Selectable SpectraChoice™ 2-pin Plug-in Lamps - Type A


| Bulb Shape | Base Type | Lamp Watts | Order Code | Description | Carton Qty[2] | MOL (In) | Lumens (Initial)* | Color Temp* (Initial) | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | DLC® ID[4] | Location Rating[3] | Additional Information^ |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Vertical Type A G24d 2-pin** | | | | | | | | | | | | | | |
| Plug-In | G24d | 10.5 | 93300091 | LED11G24d-V/8SC-4PK | 24 | 6.2 | 1000<br>1100<br>1100<br>1100* | 2700K<br>3000K<br>3500K<br>4000K* | 80 | 13/18/26 | 50,000 | - | Damp | SpectraChoice™<br>Selectable Color Temperature (4000K Default),<br>Requires Magnetic Ballast, Fully Enclosed, 4 pack |
| **Horizontal Type A G24d 2-Pin** | | | | | | | | | | | | | | |
| Plug-In | G24d | 10.5 | 93300090 | LED11G24d-H/8SC-4PK | 24 | 6.6 | 1000<br>1100<br>1100<br>1100* | 2700K<br>3000K<br>3500K<br>4000K* | 80 | 13/18/26 | 50,000 | - | Damp | SpectraChoice™<br>Selectable Color Temperature (4000K Default),<br>Requires Magnetic Ballast, Fully Enclosed, 4 pack |

## 2-pin Plug-in Lamps - Type A

| Bulb Shape | Base Type | Lamp Watts | Order Code | Description | Carton Qty[2] | MOL (In) | Lumens (Initial) | Color Temp (Initial) | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | DLC® ID[4] | Location Rating[3] | Additional Information^ |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Type A GX23 2-pin** | | | | | | | | | | | | | | |
| Plug-In | GX23 | 5 | 91404 | LED5GX23/827 | 6 | 6.7 | 500 | 2700K | 80 | 13 | 50,000 | - | Damp | Requires Magnetic Ballast, Fully Enclosed |
| | GX23 | 5 | 91405 | LED5GX23/830 | 6 | 6.7 | 530 | 3000K | 80 | 13 | 50,000 | - | Damp | Requires Magnetic Ballast, Fully Enclosed |
| | GX23 | 5 | 91407 | LED5GX23/835 | 6 | 6.7 | 545 | 3500K | 80 | 13 | 50,000 | - | Damp | Requires Magnetic Ballast, Fully Enclosed |
| | GX23 | 5 | 91408 | LED5GX23/840 | 6 | 6.7 | 560 | 4000K | 80 | 13 | 50,000 | - | Damp | Requires Magnetic Ballast, Fully Enclosed |
| | GX23 | 5 | 91410 | LED5GX23/850 | 6 | 6.7 | 565 | 5000K | 80 | 13 | 50,000 | - | Damp | Requires Magnetic Ballast, Fully Enclosed |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[4] DLC® does not have a category for two-pin plug-in lamps
* Default wattage and color temperature settings noted by "*" in tables above.
^ Check ballast compatibility at LED.com/LED2pin-compatibility
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## Type A - 4-pin Plug-ins




## Selectable SpectraChoice™ 4-pin Plug-in Lamps - Type A

| Bulb Shape | Base Type | Lamp Watts | Order Code | Description | Carton Qty[2] | MOL (In) | Lumens (Initial)* | Color Temp* (Initial) | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | DLC® ID[4] | Location Rating[3] | Additional Information^ |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Vertical Type A 4-pin** | | | | | | | | | | | | | | |
| Plug-In | G24q/GX24q | 9 | 93300089 | LED9G24q-V/8SC-4PK | 24 | 5.9 | 1000<br>1100<br>1100<br>1100 | 2700K<br>3000K<br>3500K<br>4000K* | 80 | 13/18/26 | 50,000 | S-WU5YE2 | Damp | SpectraChoice™<br>Selectable Color Temperature (4000K Default), Requires Electronic Ballast, Fully Enclosed, 4 pack |
| | GX24q | 18.5 | 93314806 | LED19GX24q-V/8SC | 12 | 6.5 | 1850<br>1850<br>1850<br>1850* | 2700K<br>3000K<br>3500K<br>4000K* | 80 | 32/42 | 50,000 | - | Damp | SpectraChoice™<br>Selectable Color Temperature (4000K Default), Requires Electronic Ballast |
| **Horizontal Type A 4-pin** | | | | | | | | | | | | | | |
| Plug-In | GX24q | 18.5 | 93314804 | LED19GX24q-H/8SC | 12 | 6.8 | 1850<br>1850<br>1850<br>1850* | 2700K<br>3000K<br>3500K<br>4000K* | 80 | 32/42 | 50,000 | - | Damp | SpectraChoice™<br>Selectable Color Temperature (4000K Default), Requires Electronic Ballast |

## 4-pin Plug-in Lamps - Type A

| Bulb Shape | Base Type | Lamp Watts | Order Code | Description | Carton Qty[2] | MOL (In) | Lumens (Initial) | Color Temp (Initial) | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | DLC® ID[4] | Location Rating[3] | Additional Information# |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Horizontal Type A 4-pin** | | | | | | | | | | | | | | |
| Plug-In | G24q/GX24q | 9 | 33994 | LED9G24Q-H/827 | 6 | 5.31 | 1100 | 2700K | 80 | 13/18/26 | 50,000 | S-6PKGMC | Damp | Requires Electronic Ballast, Fully Enclosed |
| | G24q/GX24q | 9 | 33997 | LED9G24Q-H/830 | 6 | 5.31 | 1200 | 3000K | 80 | 13/18/26 | 50,000 | S-RVMH0C | Damp | Requires Electronic Ballast, Fully Enclosed |
| | G24q/GX24q | 9 | 33998 | LED9G24Q-H/835 | 6 | 5.31 | 1200 | 3500K | 80 | 13/18/26 | 50,000 | S-HOEDLY | Damp | Requires Electronic Ballast, Fully Enclosed |
| | G24q/GX24q | 9 | 33999 | LED9G24Q-H/840 | 6 | 5.31 | 1200 | 4000K | 80 | 13/18/26 | 50,000 | S-3FW29C | Damp | Requires Electronic Ballast, Fully Enclosed |

## High Lumen Biax 2G11 Plug-in Lamps - Type A


| Bulb Shape | Base Type | Lamp Watts | Order Code | Description | Carton Qty[2] | MOL (In) | Lumens (Initial) | Color Temp (Initial) | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | DLC® ID[4] | Location Rating[3] | Additional Information# |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **High Lumen Biax Type A (HLBX)** | | | | | | | | | | | | | | |
| HLBX | 2G11 | 17 | 39073 | LED172G11/830/10 | 10 | 22.3 | 2150 | 3000K | 80 | 40 | 50,000 | - | Damp | Instant or PRS Ballast |
| | 2G11 | 17 | 39074 | LED172G11/835/10 | 10 | 22.3 | 2150 | 3500K | 80 | 40 | 50,000 | - | Damp | Instant or PRS Ballast |
| | 2G11 | 17 | 39075 | LED172G11/840/10 | 10 | 22.3 | 2200 | 4000K | 80 | 40 | 50,000 | - | Damp | Instant or PRS Ballast |
| | 2G11 | 17 | 39076 | LED172G11/850/10 | 10 | 22.3 | 2200 | 5000K | 80 | 40 | 50,000 | - | Damp | Instant or PRS Ballast |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[4] Not all product variations on this page are DLC qualified. Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
[5] Lumen levels correspond with color temperature for selectable lamps
* Default wattage and color temperature settings noted by "*" in tables above.
# Check ballast compatibility at LED.com/LED4pin-compatibility for G24q/GX24q lamps. Check ballast compatibility at LED.com/LED2G11-compatibility for 2G11 lamps.
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## **LED Lamps** – Type B Plug-ins

Type B LED plug-in lamps offer the opportunity to replace pin-based compact fluorescent lamps and eliminate costs related to the ballasts. Type B lamps operate from mains voltage. The fixture is re-wired to bypass the ballast. Horizontal and vertical orientation lamps are offered in order to minimize energy consumption and improve fixture efficiency. Choose the lamp orientation that suits the application.

Lamp **Drawings** (not drawn to scale)



| Base | G23 | GX23 | GX23-2 | G24 | G24 | G24 | G24 |
|---|---|---|---|---|---|---|---|
| Fits In Sockets | G23 | GX23 | GX23-2 | G24d<br>G24q<br>GX24q | G24d<br>G24q<br>GX24q | G24d<br>G24q<br>GX24q | G24d<br>G24q<br>GX24q |
| Input Voltage | 120-277 | 120-277 | 120-277 | 120-277 | 120-277 | 120-347 | 120-347 |
| Color Temperature | 2700K<br>3000K<br>3500K<br>4000K | 2700K<br>3000K<br>3500K<br>4000K<br>5000K | 2700K<br>3000K<br>3500K<br>4000K | 2700K<br>3000K<br>3500K<br>4000K | 2700K<br>3000K<br>3500K<br>4000K | SpectraChoice™<br>2700K<br>3000K<br>3500K<br>4000K | SpectraChoice™<br>2700K<br>3000K<br>3500K<br>4000K |
| Rated Life (L70) | 50,000 | 50,000 | 20,000 | 20,000 | 50,000 | 50,000 | 50,000 |
| Lumens | 500 | 500 | 800 | 850 | 1200 | 1100 | 1850 |
| Light Distribution | Directional | Directional | Omnidirec-tional | Omnidirec-tional | Omnidirec-tional | Directional | Directional |
| Wattage | 5W | 5W | 7.5W | 7.5W | 10W | 10.5W | 18W |
| CFL Equivalent | 7/9W | 13W | 13W | 13W | 18W | 13/18/26W | 32/42W |



## Catalog Logic:

**Bulb Shape:**
Bulb shape followed by its size (the maximum diameter of the bulb expressed in eighths of an inch).

**Watts:**
Energy Used (as defined by FTC Lamp Label Rules)

**Base Type:**
ANSI Base

**Order Code:**
Use the order code when ordering to ensure that you receive the exact product you require

**Description:**
Lamp Model Description

**Volts:**
Lamp data is based on operation at rated voltage

**Carton Quantity:**
Number of lamps packed in a carton

**MOL (in):**
Maximum Overall Length in inches

**Lumens:**
Light output (as defined by FTC Lamp Label Rules)

**Selectable Color Temp. (K):**
A selectable switch to choose "warmth" or "coolness" of the light from the lamp. The higher the value, the whiter or "cooler" the light appears.

**Color Rendering Index (CRI or R):**
An indication of the ability of the lamp to render object colors in a normal natural way. The higher the number (0-100), the better the color appearance.

**Wattage Replacement:**
Wattage of Traditional Lamp the LED Lamp is meant to replace

**Rated Life L70:**
Hours of operation the lamp will provide before reaching 70% of its original lumen output

**DLC:**
Indicates whether product is listed on the DesignLights Consortium Qualified Products List

**Location Rating:**
Location Rating as defined for LED Lamps by UL 1993


**Additional Information:**
Typical application and/or other important information

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (In) | Lumens (Initial)[5] | Selectable Color Temp. (Initial)* | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | DLC*[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Vertical Type B 2-pin - Fits in G24d and G24q sockets - Selectable Color Temperature - Ballast Bypass** | | | | | | | | | | | | | | | |
| Plug-In  | G24 | 10.5 | 93300088 | LED11BG24-V/8SC/120-347-4PK | 120-347 | 24 | 5.9 | 1000<br>1100<br>1100<br>1100 | 2700K<br>3000K<br>3500K<br>4000K | 80 | 13/18/26 | 50,000 | - | Damp | SpectraChoice™ (4000K Default) Selectable Color Temperature, Ballast Bypass, Fully Enclosed, 4 pack |

**LED11BG24-H/8SC/120-347-4PK**

- LED11B — Wattage
- B = Type B
- G24 — Base
- H = Horizontal, V = Vertical, O = Omnidirectional — Orientation
- 8 = 80 — CRI
- SC = SpectraChoice (Selectable CCT)
- 120-347 — Voltage Range
- 4PK = Inner pack of 4 lamps (Smallest unit of sale downstream)

## Base Identification (not drawn to scale)




**2G11 Base**
Replaces 2G11




**G23 Base**
Replaces G23



**GX23 Base**
Replaces GX23



**GX23-2 Base**
Replaces GX23-2



**G24 Base**
Replaces G24d, G24q, GX24q

## **LED Lamps** – SpectraChoice™ Type B Plug-ins


SpectraChoice™ Type B Plug-in lamps feature built-in switches to select color temperature. Horizontal and vertical orientation lamps are offered in order to minimize energy consumption and improve fixture efficiency. Choose the lamp orientation that suits the application.

SpectraChoice™




# **LED Lamps** - Plug-in - Type B


Type B LED plug-in lamps can be used in a variety of compact fluorescent sockets. By re-wiring the socket and eliminating concerns related to ballast compatibility, a single lamp can fit and operate in a wider variety of sockets. Type B LED plug-in lamp bases do not have exclusionary features related to specific wattages like CFL lamps do. A 2-pin G24 lamp can fit in 2-pin G24d or 4-pin G24q/GX24q sockets as shown below.




Wiring Diagram for G24d 2-pin Sockets




Wiring Diagram for G24q/GX24q 4-pin Sockets





## **Ballast Bypass Selectable SpectraChoice™ G24 Plug-in Lamps** - Type B

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (In) | MOD (In) | Lumens (Initial)* | Selectable Color Temp. (Initial)* | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Vertical Type B 2-pin - Fits in G24d and G24q sockets - Selectable Color Temperature - Ballast Bypass** | | | | | | | | | | | | | | | | |
| Plug-In | | | | | | | | | | | | | | | | |
|  | G24 | 10.5 | 93300088 | LED11BG24-V/8SC/120-347-4PK | 120-347 | 24 | 5.9 | 3.1 | 1000<br>1100<br>1100<br>1100* | 2700K<br>3000K<br>3500K<br>4000K* | 80 | 13/18/26 | 50,000 | - | Damp | SpectraChoice™ Selectable Color Temperature (4000K Default), Ballast Bypass, Fully Enclosed, 4 pack |
|  | G24 | 18 | 93312489 | LED18BG24-V/8SC/120-347 | 120-347 | 12 | 6.5 | 3.6 | 1850<br>1850<br>1850<br>1850* | 2700K<br>3000K<br>3500K<br>4000K* | 80 | 32/42 | 50,000 | - | Damp | SpectraChoice™ Selectable Color Temperature (4000K Default), Ballast Bypass, Fully Enclosed |
| **Horizontal Type B 2-pin - Fits in G24d and G24q sockets - Selectable Color Temperature - Ballast Bypass** | | | | | | | | | | | | | | | | |
| Plug-In | | | | | | | | | | | | | | | | |
|  | G24 | 10.5 | 93300087 | LED11BG24-H/8SC/120-347-4PK | 120-347 | 24 | 6.4 | 1.9 | 1000<br>1100<br>1100<br>1100* | 2700K<br>3000K<br>3500K<br>4000K* | 80 | 13/18/26 | 50,000 | - | Damp | SpectraChoice™ Selectable Color Temperature (4000K Default), Ballast Bypass, Fully Enclosed, 4 pack |
|  | G24 | 18 | 93312525 | LED18BG24-H/8SC/120-347 | 120-347 | 12 | 6.8 | 2.3 | 1850<br>1850<br>1850<br>1850* | 2700K<br>3000K<br>3500K<br>4000K* | 80 | 32/42 | 50,000 | - | Damp | SpectraChoice™ Selectable Color Temperature (4000K Default), Ballast Bypass, Fully Enclosed |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[4] DLC® does not have a category for two-pin plug-in lamps
* Default wattage and color temperature settings noted by "*" in tables above.
Please note Current lamps are not for sale for use in Yukon Territory in Canada







G24 Base
Replaces G24d & G24q

## Ballast Bypass Omnidirectional G24 Plug-in Lamps - Type B

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (In) | MOD (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Omnidirectional Type B 2-pin - Fits in G24d and G24q sockets - Ballast Bypass** | | | | | | | | | | | | | | | | |
| Plug-In | G24 | 7.5 | 93300068 | LED8BG24-O/827-4PK | 120-277 | 24 | 4.4 | 1.5 | 800 | 2700K | 80 | 13 | 20,000 | - | Damp | Fully Enclosed, 4 pack |
| | G24 | 7.5 | 93300069 | LED8BG24-O/830-4PK | 120-277 | 24 | 4.4 | 1.5 | 850 | 3000K | 80 | 13 | 20,000 | - | Damp | Fully Enclosed, 4 pack |
| | G24 | 7.5 | 93300080 | LED8BG24-O/835-4PK | 120-277 | 24 | 4.4 | 1.5 | 850 | 3500K | 80 | 13 | 20,000 | - | Damp | Fully Enclosed, 4 pack |
| | G24 | 7.5 | 93300081 | LED8BG24-O/840-4PK | 120-277 | 24 | 4.4 | 1.5 | 850 | 4000K | 80 | 13 | 20,000 | - | Damp | Fully Enclosed, 4 pack |
| **Omnidirectional Type B 2-pin - Fits in G24d and G24q sockets - Ballast Bypass** | | | | | | | | | | | | | | | | |
| Plug-In | G24 | 10 | 93300082 | LED10BG24-O/827-4PK | 120-277 | 24 | 5.4 | 1.8 | 1100 | 2700K | 80 | 18 | 50,000 | - | Damp | Fully Enclosed, 4 pack |
| | G24 | 10 | 93300083 | LED10BG24-O/830-4PK | 120-277 | 24 | 5.4 | 1.8 | 1200 | 3000K | 80 | 18 | 50,000 | - | Damp | Fully Enclosed, 4 pack |
| | G24 | 10 | 93300084 | LED10BG24-O/835-4PK | 120-277 | 24 | 5.4 | 1.8 | 1200 | 3500K | 80 | 18 | 50,000 | - | Damp | Fully Enclosed, 4 pack |
| | G24 | 10 | 93300086 | LED10BG24-O/840-4PK | 120-277 | 24 | 5.4 | 1.8 | 1200 | 4000K | 80 | 18 | 50,000 | - | Damp | Fully Enclosed, 4 pack |





GX23-2 Base
Replaces GX23-2

## Ballast Bypass Omnidirectional GX23-2 Plug-in Lamps - Type B

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (In) | MOD (in) | Lumens (Initial) | Color Temp (Initial) | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Omnidirectional GX23-2 Plug-in Type B - Ballast Bypass** | | | | | | | | | | | | | | | | |
| Plug-In | GX23-2 | 7.5 | 93312531 | LED8BGX23-2-O/827 | 120-277 | 24 | 4.7 | 1.5 | 800 | 2700K | 80 | 13 | 20,000 | - | Damp | Ballast Bypass, Fully Enclosed |
| | GX23-2 | 7.5 | 93312537 | LED8BGX23-2-O/830 | 120-277 | 24 | 4.7 | 1.5 | 800 | 3000K | 80 | 13 | 20,000 | - | Damp | Ballast Bypass, Fully Enclosed |
| | GX23-2 | 7.5 | 93312543 | LED8BGX23-2-O/835 | 120-277 | 24 | 4.7 | 1.5 | 800 | 3500K | 80 | 13 | 20,000 | - | Damp | Ballast Bypass, Fully Enclosed |
| | GX23-2 | 7.5 | 93312549 | LED8BGX23-2-O/840 | 120-277 | 24 | 4.7 | 1.5 | 800 | 4000K | 80 | 13 | 20,000 | - | Damp | Ballast Bypass, Fully Enclosed |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[4] DLC® does not have a category for two-pin plug-in lamps
Please note Current lamps are not for sale for use in Yukon Territory in Canada





G23 Base
Replaces G23

## Ballast Bypass G23 Plug-in Lamps - Type B

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (In) | Lumens (Initial) | Color Temp. (Initial) | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **G23 Plug-In Type B - Ballast Bypass** | | | | | | | | | | | | | | | |
| Plug-In | G23 | 5 | 93312465 | LED5BG23/827 | 120-277 | 24 | 5.4 | 500 | 2700K | 80 | 7/9 | 50,000 | - | Damp | Ballast Bypass, Fully Enclosed |
| | G23 | 5 | 93312471 | LED5BG23/830 | 120-277 | 24 | 5.4 | 500 | 3000K | 80 | 7/9 | 50,000 | - | Damp | Ballast Bypass, Fully Enclosed |
| | G23 | 5 | 93312477 | LED5BG23/835 | 120-277 | 24 | 5.4 | 500 | 3500K | 80 | 7/9 | 50,000 | - | Damp | Ballast Bypass, Fully Enclosed |
| | G23 | 5 | 93312483 | LED5BG23/840 | 120-277 | 24 | 5.4 | 500 | 4000K | 80 | 7/9 | 50,000 | - | Damp | Ballast Bypass, Fully Enclosed |





GX23 Base
Replaces GX23

## Ballast Bypass GX23 Plug-in Lamps - Type B

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (In) | Lumens (Initial) | Color Temp. (Initial) | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | DLC® ID[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **GX23 Plug-in Type B - Ballast Bypass** | | | | | | | | | | | | | | | |
| Plug-In | GX23 | 5 | 93312495 | LED5BGX23/827 | 120-277 | 24 | 6.8 | 500 | 2700K | 80 | 13 | 50,000 | - | Damp | Ballast Bypass, Fully Enclosed |
| | GX23 | 5 | 93312501 | LED5BGX23/830 | 120-277 | 24 | 6.8 | 500 | 3000K | 80 | 13 | 50,000 | - | Damp | Ballast Bypass, Fully Enclosed |
| | GX23 | 5 | 93312507 | LED5BGX23/835 | 120-277 | 24 | 6.8 | 500 | 3500K | 80 | 13 | 50,000 | - | Damp | Ballast Bypass, Fully Enclosed |
| | GX23 | 5 | 93312513 | LED5BGX23/840 | 120-277 | 24 | 6.8 | 500 | 4000K | 80 | 13 | 50,000 | - | Damp | Ballast Bypass, Fully Enclosed |
| | GX23 | 5 | 93312519 | LED5BGX23/850 | 120-277 | 24 | 6.8 | 500 | 5000K | 80 | 13 | 50,000 | - | Damp | Ballast Bypass, Fully Enclosed |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[4] Not all product variations on this page are DLC qualified. DLC® does not have a category for two-pin plug-in lamps. Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
Please note Current lamps are not for sale for use in Yukon Territory in Canada

**LED Lamps** – SpectraChoice™ Type B Plug-ins

SpectraChoice™ Type B Plug-in lamps feature built-in switches to select color temperature. Horizontal and vertical orientation lamps are offered in order to minimize energy consumption and improve fixture efficiency. Choose the lamp orientation that suits the application.

SpectraChoice™










## SpectraChoice™ Ballast Bypass High Lumen Biax® 2G11 Plug-In Lamps - Type B

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (In) | Lumens (Initial)* | Selectable Color Temp (Initial)* | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | DLC*[4] | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **High Lumen Biax® Type B (HLBX) - Ballast Bypass** | | | | | | | | | | | | | | | |
| HLBX | 2G11 | 9 | 93318810 | LED9B2G11/8SC | 120-277 | 24 | 9.1 | 1000 | 3000K<br>3500K<br>4000K*<br>5000K | 80 | 18 | 50,000 | - | Damp | |
| | 2G11 | 10 | 93318816 | LED10B2G11/8SC | 120-277 | 24 | 12.8 | 1200 | 3000K<br>3500K<br>4000K*<br>5000K | 80 | 24 | 50,000 | - | Damp | |
| | 2G11 | 16 | 93318822 | LED16B2G11/8SC | 120-277 | 24 | 16.6 | 2000 | 3000K<br>3500K<br>4000K*<br>5000K | 80 | 36 | 50,000 | - | Damp | |
| | 2G11 | 17 | 93318828 | LED17B2G11/8SC | 120-277 | 24 | 22.5 | 2200 | 3000K<br>3500K<br>4000K*<br>5000K | 80 | 40 | 50,000 | - | Damp | |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
[4] Not all product variations on this page are DLC qualified. Visit qpl.designlights.org/solid-state-lighting to confirm qualification.
* Default wattage and color temperature settings noted by "*" in tables above.
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## **LED Lamps** – PARs

Current offers LED PAR lamps featuring the exclusive Visual Comfort Lens design. With advanced optics and reduced glare, these lamps offer the light qualities desired by merchants for retail applications.

High output and value lines are also available to serve applications needing higher lumens or when advanced optics are not required.



## Catalog Logic:

**Bulb Shape:** Bulb shape followed by its size (the maximum diameter of the bulb expressed in eighths of an inch).

**Base Type:** ANSI Base

**Watts:** Energy Used (as defined by FTC Lamp Label Rules)

**Order Code:** Use the order code when ordering to ensure that you receive the exact product you require

**Description:** Lamp Model Description

**Volts:** Lamp data is based on operation at rated voltage

**Carton Quantity:** Number of lamps packed in a carton

**MOL (in):** Maximum Overall Length in inches

**Lumens:** Light output (as defined by FTC Lamp Label Rules)

**Color Temperature (K):** A measure of the visual "warmth" or "coolness" of the light from the lamp. The higher the value, the whiter or "cooler" the light appears.

**CBCP:** Center Beam Candle Power

**Color Rendering Index (CRI or R):** An indication of the ability of the lamp to render object colors in a normal natural way. The higher the number (0-100), the better the color appearance.

**Wattage Replacement:** Wattage of Traditional Lamp the LED Lamp is meant to replace

**Rated Life L70:** Hours of operation the lamp will provide before reaching 70% of its original lumen output

**Dimmable:** Indicates whether a lamp is dimmable or not

**Location Rating:** Location Rating as defined for LED Lamps by UL 1993

**Beam Angle:** Degrees

**Housing Color:** Color of lamp body


**Additional Information:** Typical application and/or other important information

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | CBCP | Color Temp. (Initial) | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Beam Angle | Housing Color | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **PAR38 - Low Glare - Visual Comfort Lens** | | | | | | | | | | | | | | | | | | |
| PAR38 | E26 | 18 | 93311937 | LED18DP38ROW940/25 | 120 | 6 | 5.2 | 1700 | 6500 | 4000K | 90 | 120 | 25,000 | Yes | Wet | 25° | White | CEC Title 20 |


## LED18DP38ROW940/25

- Wattage
- D = Dimmable
- Bulb Shape (P=PAR, sometimes dropped for space)
- Generational indicator
- O = Outdoor (Wet rated)
- Body color (W= White)
- CRI (9 = 90)
- CCT (40 = 4000K)
- Beam Angle (25 = 25 degrees)


## Lamp **Drawings** (not drawn to scale)




PAR16




PAR20




PAR30




PAR30L



PAR30LHO



PAR38



PAR38HO

## Selectable LED Lamps – PARs

Experience the flexibility of lighting that adapts to your needs. Current's PAR20, PAR30 and PAR30L lamps provide SpectraChoice™ for selectable color temperature and BeamSelect to easily change between 25° and 40° beam angles, all with the flick of a switch, no tools required. Lamps available in both black and white housings.

LumenChoice® + SpectraChoice™ and BeamSelect PAR38 lamps maximize the potential to reduce inventory and streamline product lists. These lamps allow installers to react to a wide variety of needs, providing the ability to adjust the color temperature of the light and the brightness, along with the beam angle, to provide the best light for every environment. Lamps available in both black and white housings.

### Selectable PAR20 Lamps







### Selectable SpectraChoice™ and BeamSelect Directional Lamps

| Bulb Shape | Base Type | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Watts | Lumens (Initial) | Selectable Beam Angle | CBCP | Selectable Color Temp. (Initial) | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Housing Color | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **PAR 20 Selectable** | | | | | | | | | | | | | | | | | | |
| PAR20 | E26 | 93322373 | LED5DP20W/9SC/BC | 120 | 6 | 3.4 | 5.5 | 500 | 25°<br>40°* | 1900<br>800* | 2700K<br>3000K*<br>3500K<br>4000K<br>5000K | 90 | 50 | 25,000 | Yes | Damp | White | CEC Title 20, Enclosed |
| | E26 | 93322379 | LED5DP20B/9SC/BC | 120 | 6 | 3.4 | 5.5 | 500 | 25°<br>40°* | 1900<br>800* | 2700K<br>3000K*<br>3500K<br>4000K<br>5000K | 90 | 50 | 25,000 | Yes | Damp | Black | CEC Title 20, Enclosed |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
* Default settings noted by "*" in tables above
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## Selectable PAR30 Short Neck Lamps







## Selectable SpectraChoice™ and BeamSelect Directional Lamps

| Bulb Shape | Base Type | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Watts | Lumens (Initial) | Selectable Beam Angle | CBCP | Selectable Color Temp. (Initial) | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Housing Color | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **PAR 30 Selectable** | | | | | | | | | | | | | | | | | | |
| PAR30 | E26 | 93322385 | LED10DP30W/9SC/BC | 120 | 6 | 3.7 | 10 | 1000 | 25°<br>40°* | 3600<br>1500* | 2700K<br>3000K*<br>3500K<br>4000K<br>5000K | 90 | 75 | 25,000 | Yes | Damp | White | CEC Title 20, Enclosed |
| | E26 | 93322391 | LED10DP30B/9SC/BC | 120 | 6 | 3.7 | 10 | 1000 | 25°<br>40°* | 3600<br>1500* | 2700K<br>3000K*<br>3500K<br>4000K<br>5000K | 90 | 75 | 25,000 | Yes | Damp | Black | CEC Title 20, Enclosed |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
* Default settings noted by "*" in tables above
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## Selectable PAR30 Long Neck Lamps




## Selectable SpectraChoice™ and BeamSelect Directional Lamps

| Bulb Shape | Base Type | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Watts | Lumens (Initial) | Selectable Beam Angle | CBCP | Selectable Color Temp. (Initial) | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Housing Color | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **PAR 30 Long Neck Selectable** | | | | | | | | | | | | | | | | | | |
| PAR30L | E26 | 93322397 | LED10DP30LW/9SC/BC | 120 | 6 | 4.7 | 10 | 1000 | 25°<br>40°* | 3600<br>1500* | 2700K<br>3000K*<br>3500K<br>4000K<br>5000K | 90 | 75 | 25,000 | Yes | Damp | White | CEC Title 20, Enclosed |
| | E26 | 93322403 | LED10DP30LB/9SC/BC | 120 | 6 | 4.7 | 10 | 1000 | 25°<br>40°* | 3600<br>1500* | 2700K<br>3000K*<br>3500K<br>4000K<br>5000K | 90 | 75 | 25,000 | Yes | Damp | Black | CEC Title 20, Enclosed |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
* Default settings noted by "*" in tables above
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## Selectable PAR38 Lamps

SpectraChoice™

BeamSelect

LumenChoice®




## Selectable LumenChoice® + SpectraChoice™ and BeamSelect Directional Lamps

| Bulb Shape | Base Type | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Selectable Watts | Selectable Lumens (Initial) | Selectable Beam Angle | CBCP | Selectable Color Temp. (Initial) | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Housing Color | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **PAR 38 Selectable** | | | | | | | | | | | | | | | | | | |
| PAR38 | E26 | 93322409 | LED/LC/DP38W/9SC/BC | 120 | 6 | 5.3 | 9 | 900 | 25°<br>40°* | 3700<br>1500* | 2700K<br>3000K*<br>3500K<br>4000K<br>5000K | 90 | 75<br>100<br>120 | 25,000 | Yes | Wet | White | CEC Title 20, Enclosed |
| | | | | | | | 12 | 1200 | 25°<br>40°* | 4700<br>1800* | | | | | | | | |
| | | | | | | | 15* | 1450* | 25°<br>40°* | 5400<br>2200* | | | | | | | | |
| | E26 | 93322415 | LED/LC/DP38B/9SC/BC | 120 | 6 | 5.3 | 9 | 900 | 25°<br>40°* | 3700<br>1500* | 2700K<br>3000K*<br>3500K<br>4000K<br>5000K | 90 | 75<br>100<br>120 | 25,000 | Yes | Wet | Black | CEC Title 20, Enclosed |
| | | | | | | | 12 | 1200 | 25°<br>40°* | 4700<br>1800* | | | | | | | | |
| | | | | | | | 15* | 1450* | 25°<br>40°* | 5400<br>2200* | | | | | | | | |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Wet Location – Location in which water or other liquid can drip, splash, or flow on or against electrical equipment
When installing outdoors, ensure the socket used is suitably Listed for use in Wet locations and socket gaskets provided by the manufacturer are correctly attached.
* Default settings noted by "*" in tables above
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## Directional Lamps (PAR16 - PAR20)

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | CBCP | Color Temp. (Initial) | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Beam Angle | Housing Color | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Compact PAR16** | | | | | | | | | | | | | | | | | | |
| PAR16 | E26 | 6 | 93305603 | LED6DP16W830/35-6PK | 120 | 24 | 3.0 | 550 | 1000 | 3000K | 80 | 60 | 25,000 | Yes | Damp | 35° | White | 6 pack |
| **Compact PAR20** | | | | | | | | | | | | | | | | | | |
| PAR20 | E26 | 7 | 93349 | LED7DP203B827/20 | 120 | 6 | 3.5 | 500 | 2500 | 2700K | 80 | 50 | 25,000 | Yes | Damp | 20° | Black | |
| | E26 | 7 | 93360 | LED7DP203W827/20 | 120 | 6 | 3.5 | 500 | 2500 | 2700K | 80 | 50 | 25,000 | Yes | Damp | 20° | White | |
| | E26 | 7 | 93311901 | LED7DP20OB927/35 | 120 | 6 | 3.5 | 500 | 966 | 2700K | 90 | 50 | 25,000 | Yes | Wet | 35° | Black | CEC Title 20 |
| | E26 | 7 | 93311900 | LED7DP20OW927/35 | 120 | 6 | 3.5 | 500 | 966 | 2700K | 90 | 50 | 25,000 | Yes | Wet | 35° | White | CEC Title 20 |
| | E26 | 7 | 93327 | LED7DP203B830/20 | 120 | 6 | 3.5 | 520 | 2500 | 3000K | 80 | 50 | 25,000 | Yes | Damp | 20° | Black | |
| | E26 | 7 | 93347 | LED7DP203W830/20 | 120 | 6 | 3.5 | 520 | 2500 | 3000K | 80 | 50 | 25,000 | Yes | Damp | 20° | White | |
| | E26 | 7 | 93311903 | LED7DP20OB930/35 | 120 | 6 | 3.5 | 520 | 966 | 3000K | 90 | 50 | 25,000 | Yes | Wet | 35° | Black | CEC Title 20 |
| | E26 | 7 | 93311902 | LED7DP20OW930/35 | 120 | 6 | 3.5 | 520 | 966 | 3000K | 90 | 50 | 25,000 | Yes | Wet | 35° | White | CEC Title 20 |

## Directional Lamps (PAR20 - High Output)

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | CBCP | Color Temp. (Initial) | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Beam Angle | Housing Color | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **PAR 20 - High Output** | | | | | | | | | | | | | | | | | | |
| PAR20 | E26 | 10 | 93318877 | LED10DP20W930/35 | 120 | 6 | 3.5 | 900 | 2300 | 3000K | 90 | 100 | 25,000 | Yes | Damp | 35° | White | CEC Title 20 |

## Directional Lamps (PAR30 - Visual Comfort Lens)

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | CBCP | Color Temp. (Initial) | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Beam Angle | Housing Color | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **PAR30 - Low Glare - Visual Comfort Lens** | | | | | | | | | | | | | | | | | | |
| PAR30 | E26 | 12 | 93311923 | LED12DP30RW927/25 | 120 | 6 | 3.6 | 1050 | 3800 | 2700K | 90 | 75 | 25,000 | Yes | Damp | 25° | White | CEC Title 20 |
| | E26 | 12 | 93311925 | LED12DP30RB927/40 | 120 | 6 | 3.6 | 1050 | 2200 | 2700K | 90 | 75 | 25,000 | Yes | Damp | 40° | Black | CEC Title 20 |
| | E26 | 12 | 93311924 | LED12DP30RW927/40 | 120 | 6 | 3.6 | 1050 | 2200 | 2700K | 90 | 75 | 25,000 | Yes | Damp | 40° | White | CEC Title 20 |
| | E26 | 12 | 93311926 | LED12DP30RW930/25 | 120 | 6 | 3.6 | 1050 | 3900 | 3000K | 90 | 75 | 25,000 | Yes | Damp | 25° | White | CEC Title 20 |
| | E26 | 12 | 93311927 | LED12DP30RW930/40 | 120 | 6 | 3.6 | 1050 | 2200 | 3000K | 90 | 75 | 25,000 | Yes | Damp | 40° | White | CEC Title 20 |
| **PAR30 Long Neck - Low Glare - Visual Comfort Lens** | | | | | | | | | | | | | | | | | | |
| PAR30L | E26 | 12 | 93312005 | LED12DP30LRW927/25 | 120 | 6 | 4.7 | 1050 | 3800 | 2700K | 90 | 75 | 25,000 | Yes | Damp | 25° | White | CEC Title 20 |
| | E26 | 12 | 93312006 | LED12DP30LRW927/40 | 120 | 6 | 4.7 | 1050 | 2200 | 2700K | 90 | 75 | 25,000 | Yes | Damp | 40° | White | CEC Title 20 |
| | E26 | 12 | 93312007 | LED12DP30LRW930/25 | 120 | 6 | 4.7 | 1050 | 3900 | 3000K | 90 | 75 | 25,000 | Yes | Damp | 25° | White | CEC Title 20 |
| | E26 | 12 | 93312008 | LED12DP30LRW930/40 | 120 | 6 | 4.7 | 1050 | 2200 | 3000K | 90 | 75 | 25,000 | Yes | Damp | 40° | White | CEC Title 20 |
| | E26 | 12 | 93316394 | LED12DP30LRB930/40 | 120 | 6 | 4.7 | 1050 | 2200 | 3000K | 90 | 75 | 25,000 | Yes | Damp | 40° | Black | CEC Title 20 |

## Directional Lamps (PAR30 - Value)

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | CBCP | Color Temp. (Initial) | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Beam Angle | Housing Color | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **PAR30 - TIR Lens** | | | | | | | | | | | | | | | | | | |
| PAR30 | E26 | 12 | 93153892 | LED12DP30VOW830/25-4PK | 120 | 16 | 3.66 | 850 | 3400 | 3000K | 80 | 75 | 15,000 | Yes | Wet | 25° | White | 4 pack |
| **PAR30 Long Neck - TIR Lens** | | | | | | | | | | | | | | | | | | |
| PAR30L | E26 | 12 | 93153891 | LED12DP30LVOW830/ 25-4PK | 120 | 16 | 4.69 | 850 | 3400 | 3000K | 80 | 75 | 15,000 | Yes | Wet | 25° | White | 4 pack |

## Directional Lamps (PAR30 - High Output)

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | CBCP | Color Temp. (Initial) | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Beam Angle | Housing Color | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **PAR 30 Long Neck - High Output - Universal 120-277V - Finned Heat Sink** | | | | | | | | | | | | | | | | | | |
| PAR30L | E26 | 18 | 75089 | LED18P30LW83015 | 120-277 | 6 | 4.6 | 1800 | 15500 | 3000K | 80 | 75 | 25,000 | - | Damp | 15° | White | |
| | E26 | 18 | 75091 | LED18P30LW83025 | 120-277 | 6 | 4.6 | 1800 | 7000 | 3000K | 80 | 75 | 25,000 | - | Damp | 25° | White | |
| | E26 | 18 | 75065 | LED18P30LW93015 | 120-277 | 6 | 4.6 | 1400 | 12500 | 3000K | 90 | 75 | 25,000 | - | Damp | 15° | White | |
| | E26 | 18 | 75078 | LED18P30LW93025 | 120-277 | 6 | 4.6 | 1400 | 5000 | 3000K | 90 | 75 | 25,000 | - | Damp | 25° | White | |
| **PAR 30 Long Neck - High Output - Smooth Heat Sink** | | | | | | | | | | | | | | | | | | |
| PAR30L | E26 | 20 | 93318893 | LED20DP30LW930/35 | 120 | 6 | 4.7 | 2100 | 3750 | 3000K | 90 | 150 | 25,000 | Yes | Damp | 35° | White | CEC Title 20 |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
Wet Location – Location in which water or other liquid can drip, splash, or flow on or against electrical equipment.
When installing outdoors, ensure the socket used is suitably Listed for use in Wet locations and socket gaskets provided by the manufacturer are correctly attached.
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## Directional Lamps (PAR38 - Visual Comfort Lens)

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | CBCP | Color Temp. (Initial) | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | Dim-mable | Location Rating[3] | Beam Angle | Housing Color | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **PAR38 - Low Glare - Visual Comfort Lens** | | | | | | | | | | | | | | | | | | |
| PAR38 | E26 | 12 | 93311944 | LED12DP38ROW927/25 | 120 | 6 | 5.2 | 1050 | 5400 | 2700K | 90 | 100 | 25,000 | Yes | Wet | 25° | White | CEC Title 20 |
| | E26 | 12 | 93311945 | LED12DP38ROW927/40 | 120 | 6 | 5.2 | 1050 | 2300 | 2700K | 90 | 100 | 25,000 | Yes | Wet | 40° | White | CEC Title 20 |
| | E26 | 12 | 93311946 | LED12DP38ROW930/25 | 120 | 6 | 5.2 | 1050 | 5400 | 3000K | 90 | 100 | 25,000 | Yes | Wet | 25° | White | CEC Title 20 |
| | E26 | 12 | 93311947 | LED12DP38ROW930/40 | 120 | 6 | 5.2 | 1050 | 2300 | 3000K | 90 | 100 | 25,000 | Yes | Wet | 40° | White | CEC Title 20 |
| | E26 | 12 | 93318835 | LED12DPAR38ROW927/25 | 120 | 6 | 5.2 | 1300 | 5800 | 2700K | 90 | 100 | 25,000 | Yes | Wet | 25° | White | CEC Title 20 |
| | E26 | 12 | 93318841 | LED12DPAR38ROW927/40 | 120 | 6 | 5.2 | 1300 | 3000 | 2700K | 90 | 100 | 25,000 | Yes | Wet | 40° | White | CEC Title 20 |
| | E26 | 12 | 93318847 | LED12DPAR38ROW930/25 | 120 | 6 | 5.2 | 1300 | 5800 | 3000K | 90 | 100 | 25,000 | Yes | Wet | 25° | White | CEC Title 20 |
| | E26 | 12 | 93318853 | LED12DPAR38ROW930/40 | 120 | 6 | 5.2 | 1300 | 3000 | 3000K | 90 | 100 | 25,000 | Yes | Wet | 40° | White | CEC Title 20 |
| | E26 | 16 | 93313077 | LED16DP38ROW930/15 | 120 | 6 | 5.2 | 1550 | 15000 | 3000K | 90 | 120 | 25,000 | Yes | Wet | 15° | White | CEC Title 20 |
| | E26 | 16 | 93313079 | LED16DP38ROW830/15 | 120 | 6 | 5.2 | 1800 | 18000 | 3000K | 80 | 120 | 25,000 | Yes | Wet | 15° | White | |
| | E26 | 16 | 93313081 | LED16DP38ROS830/15 | 120 | 6 | 5.2 | 1800 | 18000 | 3000K | 80 | 120 | 25,000 | Yes | Wet | 15° | Silver | |
| | E26 | 18 | 92923 | LED18D38W3927/25 | 120 | 6 | 5.31 | 1250 | 4900 | 2700K | 92 | 100 | 25,000 | Yes | Damp | 25° | White | |
| | E26 | 18 | 93311929 | LED18DP38ROW927/25 | 120 | 6 | 5.2 | 1550 | 5800 | 2700K | 90 | 120 | 25,000 | Yes | Wet | 25° | White | CEC Title 20 |
| | E26 | 18 | 93311930 | LED18DP38ROW927/40 | 120 | 6 | 5.2 | 1550 | 3700 | 2700K | 90 | 150 | 25,000 | Yes | Wet | 40° | White | CEC Title 20 |
| | E26 | 18 | 92961 | LED18D38W3830/15 | 120 | 6 | 5.31 | 1750 | 20000 | 3000K | 81 | 150 | 25,000 | Yes | Damp | 15° | White | |
| | E26 | 18 | 93311932 | LED18DP38ROB930/25 | 120 | 6 | 5.2 | 1550 | 6000 | 3000K | 90 | 120 | 25,000 | Yes | Wet | 25° | Black | CEC Title 20 |
| | E26 | 18 | 93311931 | LED18DP38ROW930/25 | 120 | 6 | 5.2 | 1550 | 6000 | 3000K | 90 | 120 | 25,000 | Yes | Wet | 25° | White | CEC Title 20 |
| | E26 | 18 | 93311933 | LED18DP38ROS930/25 | 120 | 6 | 5.2 | 1550 | 6000 | 3000K | 90 | 120 | 25,000 | Yes | Wet | 25° | Silver | CEC Title 20 |
| | E26 | 18 | 93311934 | LED18DP38ROW930/40 | 120 | 6 | 5.2 | 1550 | 3800 | 3000K | 90 | 150 | 25,000 | Yes | Wet | 40° | White | CEC Title 20 |
| | E26 | 18 | 93316388 | LED18DP38ROB930/40 | 120 | 6 | 5.2 | 1550 | 3800 | 3000K | 90 | 150 | 25,000 | Yes | Wet | 40° | Black | CEC Title 20 |
| | E26 | 18 | 93311935 | LED18DP38ROW935/25 | 120 | 6 | 5.2 | 1700 | 6500 | 3500K | 90 | 120 | 25,000 | Yes | Wet | 25° | White | CEC Title 20 |
| | E26 | 18 | 93311936 | LED18DP38ROW935/40 | 120 | 6 | 5.2 | 1700 | 4200 | 3500K | 90 | 150 | 25,000 | Yes | Wet | 40° | White | CEC Title 20 |
| | E26 | 18 | 93311937 | LED18DP38ROW940/25 | 120 | 6 | 5.2 | 1700 | 6500 | 4000K | 90 | 120 | 25,000 | Yes | Wet | 25° | White | CEC Title 20 |
| | E26 | 18 | 93311938 | LED18DP38ROW940/40 | 120 | 6 | 5.2 | 1700 | 4200 | 4000K | 90 | 150 | 25,000 | Yes | Wet | 40° | White | CEC Title 20 |
| | E26 | 18 | 93311939 | LED18DP38ROW950/25 | 120 | 6 | 5.2 | 1700 | 6500 | 5000K | 90 | 120 | 25,000 | Yes | Wet | 25° | White | CEC Title 20 |
| | E26 | 18 | 93311940 | LED18DP38ROW950/40 | 120 | 6 | 5.2 | 1700 | 4200 | 5000K | 90 | 150 | 25,000 | Yes | Wet | 40° | White | CEC Title 20 |

## Directional Lamps (PAR38 – High Output)

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | CBCP | Color Temp. (Initial) | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | Dim-mable | Location Rating[3] | Beam Angle | Housing Color | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **PAR 38 - High Output - TIR Lens - Smooth Housing** | | | | | | | | | | | | | | | | | | |
| PAR38 | E26 | 27 | 93314739 | LED27DP38OW830/15 | 120 | 6 | 5.3 | 3100 | 20000 | 3000K | 80 | 250 | 25,000 | Yes | Wet | 15° | White | |
| | E26 | 27 | 93314751 | LED27DP38OW830/25 | 120 | 6 | 5.3 | 3100 | 10000 | 3000K | 80 | 250 | 25,000 | Yes | Wet | 25° | White | |
| | E26 | 27 | 93314753 | LED27DP38OW830/40 | 120 | 6 | 5.3 | 3100 | 5000 | 3000K | 80 | 250 | 25,000 | Yes | Wet | 40° | White | |
| | E26 | 27 | 93314755 | LED27DP38OW835/15 | 120 | 6 | 5.3 | 3100 | 20000 | 3500K | 80 | 250 | 25,000 | Yes | Wet | 15° | White | |
| | E26 | 27 | 93314757 | LED27DP38OW835/25 | 120 | 6 | 5.3 | 3100 | 10000 | 3500K | 80 | 250 | 25,000 | Yes | Wet | 25° | White | |
| | E26 | 27 | 93314759 | LED27DP38OW835/40 | 120 | 6 | 5.3 | 3100 | 5000 | 3500K | 80 | 250 | 25,000 | Yes | Wet | 40° | White | |
| **PAR 38 - High Output - TIR Lens - Finned Heat Sink** | | | | | | | | | | | | | | | | | | |
| PAR38 | E26 | 32 | 88801 | LED32DP38W830/25 | 120 | 6 | 5.12 | 3000 | 13000 | 3000K | 80 | 250 | 25,000 | Yes | Wet | 25° | White | |
| | E26 | 32 | 88810 | LED32DP38W830/40 | 120 | 6 | 5.12 | 3000 | 6000 | 3000K | 80 | 250 | 25,000 | Yes | Wet | 40° | White | |
| | E26 | 32 | 30233 | LED32DP38W835/15 | 120 | 6 | 5.12 | 3100 | 25000 | 3500K | 80 | 250 | 25,000 | Yes | Wet | 15° | White | |
| | E26 | 32 | 30239 | LED32DP38W835/40 | 120 | 6 | 5.12 | 3100 | 6000 | 3500K | 80 | 250 | 25,000 | Yes | Wet | 40° | White | |
| | E26 | 32 | 20109 | LED32P38W830/15 | 120-277 | 6 | 5.12 | 3000 | 25000 | 3000K | 80 | 250 | 25,000 | - | Wet | 15° | White | |
| | E26 | 32 | 20130 | LED32P38W830/25 | 120-277 | 6 | 5.12 | 3000 | 13000 | 3000K | 80 | 250 | 25,000 | - | Wet | 25° | White | |
| | E26 | 32 | 20137 | LED32P38W830/40 | 120-277 | 6 | 5.12 | 3000 | 6000 | 3000K | 80 | 250 | 25,000 | - | Wet | 40° | White | |

## Directional Lamps (PAR38 - Value)

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | CBCP | Color Temp. (Initial) | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | Dim-mable | Location Rating[3] | Beam Angle | Housing Color | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **PAR38 - TIR Lens** | | | | | | | | | | | | | | | | | | |
| PAR38 | E26 | 15 | 93153880 | LED15DP38VOW830/35-4PK | 120 | 16 | 5.31 | 1300 | 2300 | 3000K | 80 | 90 | 15,000 | Yes | Wet | 35° | White | 4 pack |


[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
Wet Location – Location in which water or other liquid can drip, splash, or flow on or against electrical equipment
When installing outdoors, ensure the socket used is suitably Listed for use in Wet locations and socket gaskets provided by the manufacturer are correctly attached.
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## **LED Lamps** – MR16s


LED MR16 lamps are the perfect solution for high output in decorative lighting applications. The lamps are dimmable, long-lasting and available in a variety of beam angles and color temperatures.




## Lamp **Drawings** (not drawn to scale)




MR16




MR16
GU10

# LED Lamps - Directional

## Catalog Logic:




| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (In) | Lumens (Initial) | CBCP | Color Temp (Initial) | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | Dim-mable | Location Rating[3] | Beam Angle | Housing Color | Additional Information^ |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **12 Volt AC/DC MR16** | | | | | | | | | | | | | | | | | | |
| | GU5.3 | 6.5 | 75155 | LED6.5DMR16W82715 | 12 | 6 | 1.87 | 500 | 4900 | 2700K | 80 | 50 | 25,000 | Yes | Damp | 15° | White | |




## Directional Lamps (MR16-GU10)

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (In) | Lumens (Initial) | CBCP | Color Temp (Initial) | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | Dim-mable | Location Rating[3] | Beam Angle | Housing Color | Additional Information^ |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **12 Volt AC/DC MR16** | | | | | | | | | | | | | | | | | | |
|  | GU5.3 | 6.5 | 75155 | LED6.5DMR16W82715 | 12 | 6 | 1.87 | 500 | 4900 | 2700K | 80 | 50 | 25,000 | Yes | Damp | 15° | White | |
| | GU5.3 | 6.5 | 75153 | LED6.5DMR16W83015 | 12 | 6 | 1.87 | 520 | 4900 | 3000K | 80 | 50 | 25,000 | Yes | Damp | 15° | White | |
| | GU5.3 | 6.5 | 75158 | LED6.5DMR16W84015 | 12 | 6 | 1.87 | 550 | 5000 | 4000K | 80 | 50 | 25,000 | Yes | Damp | 15° | White | |
| | GU5.3 | 6.5 | 93226 | LED6.5DMR16W82725 | 12 | 6 | 1.79 | 500 | 2350 | 2700K | 80 | 50 | 25,000 | Yes | Damp | 25° | White | |
| | GU5.3 | 6.5 | 93222 | LED6.5DMR16W83025 | 12 | 6 | 1.79 | 520 | 2350 | 3000K | 80 | 50 | 25,000 | Yes | Damp | 25° | White | |
|  | GU5.3 | 6.5 | 93228 | LED6.5DMR16W84025 | 12 | 6 | 1.79 | 550 | 2400 | 4000K | 80 | 50 | 25,000 | Yes | Damp | 25° | White | |
| | GU5.3 | 6.5 | 93227 | LED6.5DMR16W82735 | 12 | 6 | 1.79 | 500 | 1350 | 2700K | 80 | 50 | 25,000 | Yes | Damp | 35° | White | |
| | GU5.3 | 6.5 | 93097010 | LED6.5DMR16B82735 | 12 | 6 | 1.79 | 500 | 1350 | 2700K | 80 | 50 | 25,000 | Yes | Damp | 35° | Black | |
| | GU5.3 | 6.5 | 93223 | LED6.5DMR16W83035 | 12 | 6 | 1.79 | 520 | 1350 | 3000K | 80 | 50 | 25,000 | Yes | Damp | 35° | White | |
| | GU5.3 | 6.5 | 93229 | LED6.5DMR16W84035 | 12 | 6 | 1.79 | 550 | 1400 | 4000K | 80 | 50 | 25,000 | Yes | Damp | 35° | White | |
| **Value 12 Volt AC/DC MR16** | | | | | | | | | | | | | | | | | | |
|  | GU5.3 | 4.5 | 34560 | LED4.5MR1682735 | 12 | 6 | 1.78 | 380 | 1000 | 2700K | 80 | 35 | 25,000 | Yes | Dry | 35° | White | |
| | GU5.3 | 4.5 | 34561 | LED4.5MR1683035 | 12 | 6 | 1.78 | 400 | 1000 | 3000K | 80 | 35 | 25,000 | Yes | Dry | 35° | White | |
| | GU5.3 | 4.5 | 34563 | LED4.5MR1684035 | 12 | 6 | 1.78 | 400 | 1100 | 4000K | 80 | 35 | 25,000 | Yes | Dry | 35° | White | |
| | GU5.3 | 6.5 | 34606 | LED6.5MR1682725 | 12 | 6 | 1.78 | 500 | 2350 | 2700K | 80 | 50 | 25,000 | Yes | Dry | 25° | White | |
|  | GU5.3 | 6.5 | 34607 | LED6.5MR1682735 | 12 | 6 | 1.78 | 500 | 1350 | 2700K | 80 | 50 | 25,000 | Yes | Dry | 35° | White | |
| | GU5.3 | 6.5 | 34611 | LED6.5MR1683025 | 12 | 6 | 1.78 | 530 | 2350 | 3000K | 80 | 50 | 25,000 | Yes | Dry | 25° | White | |
| | GU5.3 | 6.5 | 34625 | LED6.5MR1683035 | 12 | 6 | 1.78 | 530 | 1350 | 3000K | 80 | 50 | 25,000 | Yes | Dry | 35° | White | |
| **120V GU10** | | | | | | | | | | | | | | | | | | |
| | GU10 | 4 | 93305604 | LED4D/GU10W830/35-6PK | 120 | 24 | 2.1 | 320 | 370 | 3000K | 80 | 35 | 25,000 | Yes | Damp | 35° | White | 6 pack |
| | GU10 | 5.5 | 93305605 | LED5D/GU10W830/35-6PK | 120 | 24 | 2.1 | 500 | 595 | 3000K | 80 | 50 | 25,000 | Yes | Damp | 35° | White | 6 pack |

^ Check dimmer and transformer compatibility at LED.com/dimming

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
Dry Location – Location not normally subject to dampness, but may include a location subject to temporary dampness (i.e., building under construction, provided ventilation is adequate to prevent an accumulation of moisture)
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## **LED Lamps** – RS Cans

RS Cans make downlight retrofits easy, with a medium base pigtail. Use the existing socket for power and provide a finished look to the ceiling without having to replace the existing fixture.




SpectraChoice™

### Selectable SpectraChoice™ RS Cans

The new SpectraChoice™ Selectable RS Can Downlights are the perfect solution to give an updated look to ceilings with recessed lighting.

Make color temperature selections easily at any time with an integrated switch, no tools required.

## Catalog Logic:

**Bulb Shape:** Bulb shape followed by its size (the maximum diameter of the bulb expressed in eighths of an inch).

**Base Type:** ANSI Base

**Watts:** Energy Used (as defined by FTC Lamp Label Rules)

**Order Code:** Use the order code when ordering to ensure that you receive the exact product you require

**Description:** Lamp Model Description

**Volts:** Lamp data is based on operation at rated voltage

**Carton Quantity:** Number of lamps packed in a carton

**MOL (in):** Maximum Overall Length in inches

**Lumens:** Light output (as defined by FTC Lamp Label Rules)

**Color Temperature (K):** A measure of the visual "warmth" or "coolness" of the light from the lamp. The higher the value, the whiter or "cooler" the light appears.

**Color Rendering Index (CRI or R):** An indication of the ability of the lamp to render object colors in a normal natural way. The higher the number (0-100), the better the color appearance.

**Wattage Replacement:** Wattage of Traditional Lamp the LED Lamp is meant to replace

**Rated Life L70:** Hours of operation the lamp will provide before reaching 70% of its original lumen output

**Dimmable:** Indicates whether a lamp is dimmable or not

**Location Rating:** Location Rating as defined for LED Lamps by UL 1993

**Additional Information:** Typical application and/or other important information

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (In) | Lumens (Initial) | Color Temp (Initial) | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **RS Cans** | | | | | | | | | | | | | | | |
| | E26 | 8 | 93162554 | LED8DRS4/9SC-4PK | 120 | 16 | 2.4 | 700 | 2700/3000/4000/5000K | 90 | 65 | 50,000 | Yes | Damp | 4" Can, Pigtail, Title 24-JA8, 4 pack |

**LED8DRS6/9SC-4PK**

- Wattage
- D = Dimmable
- RS = RS Can Trim
- Diameter (inches)
- CRI (9 = 90)
- SC = SpectraChoice™ selectable color temperature
- 4PK = Inner pack of 4 lamps (Smallest unit of sale downstream)


## Selectable SpectraChoice™ RS Cans (Dimmable)

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (In) | Lumens (Initial) | Selectable Color Temperature* | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Selectable RS Cans** | | | | | | | | | | | | | | | |
| **RS Can** | E26 | 8 | 93162554 | LED8DRS4/9SC-4PK | 120 | 16 | 2.4 | 700 | 2700K<br>3000K*<br>4000K<br>5000K | 90 | 65 | 50,000 | Yes | Damp | 4" Can, Pigtail, Title 24-JA8, 4 pack |
| | E26 | 8 | 93162555 | LED8DRS6/9SC-4PK | 120 | 16 | 2.8 | 700 | 2700K<br>3000K*<br>4000K<br>5000K | 90 | 65 | 50,000 | Yes | Damp | 6" Can, Pigtail, Title 24-JA8, 4 pack |
| | E26 | 12 | 93162556 | LED12DRS6/9SC-4PK | 120 | 16 | 2.8 | 1100 | 2700K<br>3000K*<br>4000K<br>5000K | 90 | 90 | 50,000 | Yes | Damp | 6" Can, Pigtail, Title 24-JA8, 4 pack |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
* Default color temperature setting is 3000K.
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## LED Lamps – SpectraChoice™ Reflector Lamps (Dimmable)

SpectraChoice™ Reflector lamps feature built-in switches to select color temperature. These lamps are offered in R20, BR30 and BR40 shapes. Three lamps can cover the vast majority of Reflector applications, providing a great opportunity to reduce inventory and simplify BOMs.




SpectraChoice™





### SpectraChoice™ Reflector Lamps (Dimmable)


| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (In) | Lumens (Initial) | Selectable Color Temp (Initial)* | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **R20** | | | | | | | | | | | | | | | |
| | E26 | 5.5 | 93318859 | LED5DR20/9SC | 120 | 6 | 4.0 | 500 | 2700K<br>3000K*<br>3500K<br>4000K<br>5000K | 90 | 45 | 15,000 | Yes | Damp | CEC Title 20, Enclosed, Frosted, White body |
| **BR30** | | | | | | | | | | | | | | | |
| | E26 | 8 | 93318865 | LED8DBR30/9SC | 120 | 6 | 5.4 | 650 | 2700K<br>3000K*<br>3500K<br>4000K<br>5000K | 90 | 65 | 15,000 | Yes | Damp | CEC Title 20, Enclosed, Frosted, White body |
| **BR40** | | | | | | | | | | | | | | | |
| | E26 | 12 | 93318871 | LED12DBR40/9SC | 120 | 6 | 6.4 | 1050 | 2700K<br>3000K*<br>3500K<br>4000K<br>5000K | 90 | 65 | 15,000 | Yes | Damp | CEC Title 20, Enclosed, Frosted, White body |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
* Lumen levels correspond with color temperature. Default color temperature setting is 3000K.
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## Catalog Logic:




| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (In) | Lumens (Initial) | CBCP | Color Temp (Initial) | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **BR30** | | | | | | | | | | | | | | | | |
| | E26 | 8 | 93305510 | LED8DBR30/940-6PK | 120 | 24 | 5.4 | 650 | | 4000K | 90 | 65 | 15,000 | Yes | Damp | White body, 6 pack, CEC Title 20 |




## Reflector Lamps (Dimmable)

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (In) | Lumens (Initial) | Color Temp (Initial) | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **BR30** | | | | | | | | | | | | | | | |
| | E26 | 8 | 93305498 | LED8DBR30/927-6PK | 120 | 24 | 5.4 | 650 | 2700K | 90 | 65 | 15,000 | Yes | Damp | White body, 6 pack, CEC Title 20 |
| | E26 | 8 | 93305499 | LED8DBR30/930-6PK | 120 | 24 | 5.4 | 650 | 3000K | 90 | 65 | 15,000 | Yes | Damp | White body, 6 pack, CEC Title 20 |
| | E26 | 8 | 93305510 | LED8DBR30/940-6PK | 120 | 24 | 5.4 | 650 | 4000K | 90 | 65 | 15,000 | Yes | Damp | White body, 6 pack, CEC Title 20 |
| | E26 | 8 | 93305512 | LED8DBR30/950-6PK | 120 | 24 | 5.4 | 650 | 5000K | 90 | 65 | 15,000 | Yes | Damp | White body, 6 pack, CEC Title 20 |
| | E26 | 10 | 68160 | LED10DR303/827W | 120 | 6 | 5.4 | 700 | 2700K | 80 | 65 | 25,000 | Yes | Damp | Frosted, White body |
| | E26 | 10 | 68161 | LED10DR303/830W | 120 | 6 | 5.4 | 700 | 3000K | 80 | 65 | 25,000 | Yes | Damp | Frosted, White body |
| | E26 | 10 | 69107 | LED10DR303/850W | 120 | 6 | 5.4 | 700 | 5000K | 80 | 65 | 25,000 | Yes | Damp | Frosted, White body |
| **BR40** | | | | | | | | | | | | | | | |
| | E26 | 12 | 93311897 | LED12DBR40/927 | 120 | 6 | 6.4 | 1050 | 2700K | 90 | 65 | 15,000 | Yes | Damp | Frosted, White body, CEC Title 20 |
| | E26 | 12 | 93311898 | LED12DBR40/930 | 120 | 6 | 6.4 | 1050 | 3000K | 90 | 65 | 15,000 | Yes | Damp | Frosted, White body, CEC Title 20 |
| | E26 | 12 | 93311899 | LED12DBR40/950 | 120 | 6 | 6.4 | 1050 | 5000K | 90 | 65 | 15,000 | Yes | Damp | Frosted, White body, CEC Title 20 |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## Catalog Logic:

**Bulb Shape:**
Bulb shape followed by its size (the maximum diameter of the bulb expressed in eighths of an inch).

**Watts:**
Energy Used (as defined by FTC Lamp Label Rules)

**Base Type:**
ANSI Base

**Order Code:**
Use the order code when ordering to ensure that you receive the exact product you require

**Description:**
Lamp Model Description

**Volts:**
Lamp data is based on operation at rated voltage

**Carton Quantity:**
Number lamps packed in a carton

**MOL (in):**
Maximum Overall Length in inches

**Lumens:**
Light output (as defined by FTC Lamp Label Rules)

**Color Temperature (K):**
A measure of the visual "warmth" or "coolness" of the light from the lamp. The higher the value, the whiter or "cooler" the light appears.

**Color Rendering Index (CRI or R):**
An indication of the ability of the lamp to render object colors in a normal natural way. The higher the number (0-100), the better the color appearance.

**Wattage Replacement:**
Wattage of Traditional Lamp the LED Lamp is meant to replace

**Rated Life L70:**
Hours of operation the lamp will provide before reaching 70% of its original lumen output

**Dimmable:**
Indicates whether a lamp is dimmable or not

**Location Rating:**
Location Rating as defined for LED Lamps by UL 1993


**Additional Information:**
Typical application and/or other important information

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| A19 | | | | | | | | | | | | | | | |
| | E26 | 10 | 93156450 | LED10DA19/827/E-4PK | 120 | 24 | 4.3 | 800 | 2700K | 80 | 60 | 15,000 | Yes | Damp, Enclosed | White, 4 pack |

**LED10DA19/827/E-4PK**

- Wattage
- D = Dimmable
- Bulb Shape
- CRI (8 = 80)
- CCT (27 = 2700K)
- E = Enclosed rated
- 4PK = Inner pack of 4 lamps (Smallest unit of sale downstream)

## Lamp **Drawings** (not drawn to scale)



A15 | A19 GU24 | A19 | A21 | Bright Stik™

## **LED Lamps** – SpectraChoice™ A-Line Lamps (Dimmable)

SpectraChoice™ A-line dimmable lamps feature built-in switches to select color temperature. These lamps are offered in 40, 60, 75 & 100W incandescent equivalent lumen levels. Four lamps can cover the vast majority of A-line applications, providing a great opportunity to reduce inventory and simplify BOMs.

SpectraChoice™




### **Selectable SpectraChoice™ A-Line Lamps** (Dimmable)

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (In) | Lumens (Initial) | Selectable Color Temp. (Initial)* | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **A-Line SpectraChoice™ Selectable Color Temperature** | | | | | | | | | | | | | | | |
| A19 | E26 | 6 | 93313531 | LED6DA19/9SC/E | 120 | 24 | 4.3 | 480 | 2700K* 3000K 3500K 4000K 5000K | 90 | 40 | 15,000 | Yes | Damp, Enclosed | White, CEC Title 20 |
| | E26 | 10 | 93313549 | LED10DA19/9SC/E | 120 | 24 | 4.3 | 800 | 2700K* 3000K 3500K 4000K 5000K | 90 | 60 | 15,000 | Yes | Damp, Enclosed | White, CEC Title 20 |
| | E26 | 13 | 93313543 | LED13DA19/9SC | 120 | 24 | 4.7 | 1100 | 2700K* 3000K 3500K 4000K 5000K | 90 | 75 | 15,000 | Yes | Damp | White, CEC Title 20 |
| | E26 | 15 | 93313537 | LED15DA19/9SC | 120 | 24 | 4.7 | 1600 | 2700K* 3000K 3500K 4000K 5000K | 90 | 100 | 15,000 | Yes | Damp | White, CEC Title 20 |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
* Default color temperature setting is 2700K
Please note Current lamps are not for sale for use in Yukon Territory in Canada

LumenChoice®+
SpectraChoice™




## Selectable LumenChoice® + SpectraChoice™ A-Line Lamps (Dimmable)

| Bulb Shape | Base Type | Order Code | Description | Volts | Carton Qty[2] | MOL (In) | Selectable Watts* | Selectable Lumens (Initial)* | Selectable Color Temp. (Initial)* | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **A-Line Selectable LumenChoice® + SpectraChoice™** | | | | | | | | | | | | | | | |
| A19 | E26 | 93322361 | LED/LC/DA19/9SC | 120 | 12 | 4.7 | 4<br>7*<br>9.5<br>14 | 500<br>800*<br>1100<br>1600 | 2700K*<br>3000K<br>3500K<br>4000K<br>5000K | 90 | 40<br>60<br>75<br>100 | 15,000 | Yes | Damp | White, CEC Title 20 |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
* Default wattage and color temperature settings noted by "*" in tables above
Please note Current lamps are not for sale for use in Yukon Territory in Canada

LumenChoice®+ SpectraChoice™




## Warm Selectable LumenChoice® + SpectraChoice™ A-Line Lamps (Dimmable)

| Bulb Shape | Base Type | Order Code | Description | Volts | Carton Qty[2] | MOL (In) | Selectable Watts* | Selectable Lumens (Initial)* | Selectable Color Temp. (Initial)* | Wattage Replacement | CRI | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **A-Line Warm Selectable LumenChoice® + SpectraChoice™** | | | | | | | | | | | | | | | |
| A19 | E26 | 93322367 | LED/LC/DA19/9WSC | 120 | 12 | 4.7 | 4 | 350 | 1800K | 40W | 90 | 15,000 | Yes | Damp | White, CEC Title 20 |
| | | | | | | | | 400 | 2200K | 40W | | | | | |
| | | | | | | | | 450 | 2500K | 40W | | | | | |
| | | | | | | | | 500 | 2700K | 40W | | | | | |
| | | | | | | | | 500 | 3000K | 40W | | | | | |
| | | | | | | | 7* | 600 | 1800K | 60W | | | | | |
| | | | | | | | | 700* | 2200K* | 60W | | | | | |
| | | | | | | | | 750 | 2500K | 60W | | | | | |
| | | | | | | | | 800 | 2700K | 60W | | | | | |
| | | | | | | | | 800 | 3000K | 60W | | | | | |
| | | | | | | | 9.5 | 800 | 1800K | 75W | | | | | |
| | | | | | | | | 900 | 2200K | 75W | | | | | |
| | | | | | | | | 1000 | 2500K | 75W | | | | | |
| | | | | | | | | 1100 | 2700K | 75W | | | | | |
| | | | | | | | | 1100 | 3000K | 75W | | | | | |
| | | | | | | | 14 | 1100 | 1800K | 100W | | | | | |
| | | | | | | | | 1300 | 2200K | 100W | | | | | |
| | | | | | | | | 1500 | 2500K | 100W | | | | | |
| | | | | | | | | 1600 | 2700K | 100W | | | | | |
| | | | | | | | | 1600 | 3000K | 100W | | | | | |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
* Default wattage and color temperature settings noted by "*" in tables above
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## A-Line Lamps (Dimmable)

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | Dim-mable | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **A19** | | | | | | | | | | | | | | | |
| A19 | E26 | 6 | 93156446 | LED6DA19/827/E-4PK | 120 | 24 | 4.3 | 480 | 2700K | 80 | 40 | 15,000 | Yes | Damp, Enclosed | White, 4 pack |
| | E26 | 6 | 93156447 | LED6DA19/830/E-4PK | 120 | 24 | 4.3 | 480 | 3000K | 80 | 40 | 15,000 | Yes | Damp, Enclosed | White, 4 pack |
| | E26 | 6 | 93156448 | LED6DA19/840/E-4PK | 120 | 24 | 4.3 | 480 | 4000K | 80 | 40 | 15,000 | Yes | Damp, Enclosed | White, 4 pack |
| | E26 | 6 | 93156449 | LED6DA19/850/E-4PK | 120 | 24 | 4.3 | 480 | 5000K | 80 | 40 | 15,000 | Yes | Damp, Enclosed | White, 4 pack |
| | E26 | 10 | 93156450 | LED10DA19/827/E-4PK | 120 | 24 | 4.3 | 800 | 2700K | 80 | 60 | 15,000 | Yes | Damp, Enclosed | White, 4 pack |
| | E26 | 10 | 93156531 | LED10DA19/830/E-4PK | 120 | 24 | 4.3 | 800 | 3000K | 80 | 60 | 15,000 | Yes | Damp, Enclosed | White, 4 pack |
| | E26 | 10 | 93156532 | LED10DA19/840/E-4PK | 120 | 24 | 4.3 | 800 | 4000K | 80 | 60 | 15,000 | Yes | Damp, Enclosed | White, 4 pack |
| | E26 | 10 | 93156533 | LED10DA19/850/E-4PK | 120 | 24 | 4.3 | 800 | 5000K | 80 | 60 | 15,000 | Yes | Damp, Enclosed | White, 4 pack |
| | E26 | 12 | 93156534 | LED12DA19/827/E-4PK | 120 | 24 | 4.7 | 1100 | 2700K | 80 | 75 | 15,000 | Yes | Damp, Enclosed | White, 4 pack |
| | E26 | 12 | 93156535 | LED12DA19/830/E-4PK | 120 | 24 | 4.7 | 1100 | 3000K | 80 | 75 | 15,000 | Yes | Damp, Enclosed | White, 4 pack |
| | E26 | 12 | 93156536 | LED12DA19/840/E-4PK | 120 | 24 | 4.7 | 1100 | 4000K | 80 | 75 | 15,000 | Yes | Damp, Enclosed | White, 4 pack |
| | E26 | 12 | 93156537 | LED12DA19/850/E-4PK | 120 | 24 | 4.7 | 1100 | 5000K | 80 | 75 | 15,000 | Yes | Damp, Enclosed | White, 4 pack |
| | E26 | 15 | 93156538 | LED15DA19/827-4PK | 120 | 24 | 4.7 | 1600 | 2700K | 80 | 100 | 15,000 | Yes | Damp | White, 4 pack |
| | E26 | 15 | 93156539 | LED15DA19/830-4PK | 120 | 24 | 4.7 | 1600 | 3000K | 80 | 100 | 15,000 | Yes | Damp | White, 4 pack |
| | E26 | 15 | 93156540 | LED15DA19/840-4PK | 120 | 24 | 4.7 | 1600 | 4000K | 80 | 100 | 15,000 | Yes | Damp | White, 4 pack |
| | E26 | 15 | 93156541 | LED15DA19/850-4PK | 120 | 24 | 4.7 | 1600 | 5000K | 80 | 100 | 15,000 | Yes | Damp | White, 4 pack |

## A-Line Lamps 90 CRI (Dimmable – Glass)

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | Dim-mable | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **A15** | | | | | | | | | | | | | | | |
| A15 | E26 | 3.5 | 93312022 | LED4DFA15-W/927 | 120 | 12 | 3.5 | 300 | 2700K | 90 | 40 | 15,000 | Yes | Damp | White, CEC Title 20 |
| | E26 | 3.5 | 93142809 | LED4DFA15-C-2PK | 120 | 12 | 3.5 | 300 | 2700K | 80 | 40 | 15,000 | Yes | Damp | Clear, 2 pack |
| | E26 | 3.5 | 93142810 | LED4DFA15-W-2PK | 120 | 12 | 3.5 | 300 | 2700K | 80 | 40 | 15,000 | Yes | Damp | White, 2 pack |
| **A19** | | | | | | | | | | | | | | | |
| A19 | E26 | 4.5 | 93319141 | LED5DFA19/927/E-W | 120 | 24 | 4.4 | 450 | 2700K | 90 | 40 | 15,000 | Yes | Damp, Enclosed | White, CEC Title 20 |
| | E26 | 4.5 | 93319147 | LED5DFA19/927/E-C | 120 | 24 | 4.4 | 450 | 2700K | 90 | 40 | 15,000 | Yes | Damp, Enclosed | Clear, CEC Title 20 |
| | E26 | 7 | 93319153 | LED7DFA19/927/E-W | 120 | 24 | 4.4 | 800 | 2700K | 90 | 60 | 15,000 | Yes | Damp, Enclosed | White, CEC Title 20 |
| | E26 | 7 | 93319159 | LED7DFA19/927/E-C | 120 | 24 | 4.4 | 800 | 2700K | 90 | 60 | 15,000 | Yes | Damp, Enclosed | Clear, CEC Title 20 |
| | E26 | 8 | 93319165 | LED8DFA19/927-W | 120 | 24 | 4.4 | 1100 | 2700K | 90 | 75 | 15,000 | Yes | Damp | White, CEC Title 20 |
| | E26 | 8 | 93319171 | LED8DFA19/927-C | 120 | 24 | 4.4 | 1100 | 2700K | 90 | 75 | 15,000 | Yes | Damp | Clear, CEC Title 20 |
| | E26 | 12 | 93319177 | LED12DFA19/927-W | 120 | 24 | 4.4 | 1600 | 2700K | 90 | 100 | 15,000 | Yes | Damp | White, CEC Title 20 |
| | E26 | 12 | 93319183 | LED12DFA19/927-C | 120 | 24 | 4.4 | 1600 | 2700K | 90 | 100 | 15,000 | Yes | Damp | Clear, CEC Title 20 |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
Wet Location – Location in which water or other liquid can drip, splash, or flow on or against electrical equipment.
When installing outdoors, ensure the socket used is suitably Listed for use in Wet locations and socket gaskets provided by the manufacturer are correctly attached.
Please note Current lamps are not for sale for use in Yukon Territory in Canada


All Glass
A19 White


All Glass 40W
A19 Clear


All Glass 60W
A19 Clear


All Glass 75W
A19 Clear


All Glass 100W
A19 Clear

## A-Line Lamps (High Output)

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **A21** | | | | | | | | | | | | | | | |
| A21 | E26 | 22 | 93309224 | LED22DA21/827 | 120 | 4 | 5.7 | 2610 | 2700K | 80 | 150 | 15,000 | Yes | Wet | White |
| | E26 | 22 | 93309225 | LED22DA21/850 | 120 | 4 | 5.7 | 2610 | 5000K | 80 | 150 | 15,000 | Yes | Wet | White |
| | E26 | 23 | 93309226 | LED23A21/827 | 120 | 4 | 5.7 | 3010 | 2700K | 80 | 200 | 15,000 | No | Wet | White |
| | E26 | 23 | 93309227 | LED23A21/850 | 120 | 4 | 5.7 | 3010 | 5000K | 80 | 200 | 15,000 | No | Wet | White |

## A-Line Lamps (GU24)

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **GU24 Base General Purpose A-Line Lamps** | | | | | | | | | | | | | | | |
| A19 | GU24 | 10 | 93156542 | LED10DA19/GU24/827/E-4PK | 120 | 24 | 4.2 | 800 | 2700K | 80 | 40 | 15,000 | Yes | Damp, Enclosed | White, 4 pack |
| | GU24 | 15 | 93156543 | LED15DA19/GU24/827-4PK | 120 | 24 | 4.4 | 1600 | 2700K | 80 | 100 | 15,000 | Yes | Damp | White, 4 pack |

## A-Line Lamps (3-Way)

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **3-Way General Purpose A-Line Lamps** | | | | | | | | | | | | | | | |
| A19 | E26d | 4/9/13 | 93156602 | LED13A19/30/100/827-4PK | 120 | 24 | 4.7 | 400/980/1400 | 2700K | 80 | 30/70/100 | 15,000 | - | Damp | White, 4 pack |
| A21 | E26d | 5/12/17 | 93156603 | LED17A21/50/150/827-4PK | 120 | 24 | 5.3 | 650/1500/2155 | 2700K | 80 | 50/100/150 | 15,000 | - | Damp | White, 4 pack |

## A-Line Lamps (Value)

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **A19** | | | | | | | | | | | | | | | |
| A19 | E26 | 5 | 93142977 | LED5A19/827-4PK | 120 | 24 | 4.3 | 450 | 2700K | 80 | 40 | 10,000 | - | Damp | White, 4 pack |
| | E26 | 5 | 93142978 | LED5A19/830-4PK | 120 | 24 | 4.3 | 450 | 3000K | 80 | 40 | 10,000 | - | Damp | White, 4 pack |
| | E26 | 5 | 93142979 | LED5A19/840-4PK | 120 | 24 | 4.3 | 450 | 4000K | 80 | 40 | 10,000 | - | Damp | White, 4 pack |
| | E26 | 5 | 93142980 | LED5A19/850-4PK | 120 | 24 | 4.3 | 450 | 5000K | 80 | 40 | 10,000 | - | Damp | White, 4 pack |
| | E26 | 9 | 9342981 | LED9A19/827-4PK | 120 | 24 | 4.3 | 760 | 2700K | 80 | 60 | 10,000 | - | Damp | White, 4 pack |
| | E26 | 9 | 93142982 | LED9A19/830-4PK | 120 | 24 | 4.3 | 760 | 3000K | 80 | 60 | 10,000 | - | Damp | White, 4 pack |
| | E26 | 9 | 93142983 | LED9A19/840-4PK | 120 | 24 | 4.3 | 760 | 4000K | 80 | 60 | 10,000 | - | Damp | White, 4 pack |
| | E26 | 9 | 93142984 | LED9A19/850-4PK | 120 | 24 | 4.3 | 760 | 5000K | 80 | 60 | 10,000 | - | Damp | White, 4 pack |
| **A21** | | | | | | | | | | | | | | | |
| A21 | E26 | 11 | 93142985 | LED11A21/827-4PK | 120 | 24 | 5.2 | 1050 | 2700K | 80 | 75 | 10,000 | - | Damp | White, 4 pack |
| | E26 | 11 | 93142986 | LED11A21/830-4PK | 120 | 24 | 5.2 | 1050 | 3000K | 80 | 75 | 10,000 | - | Damp | White, 4 pack |
| | E26 | 11 | 93142987 | LED11A21/840-4PK | 120 | 24 | 5.2 | 1050 | 4000K | 80 | 75 | 10,000 | - | Damp | White, 4 pack |
| | E26 | 11 | 93142988 | LED11A21/850-4PK | 120 | 24 | 5.2 | 1050 | 5000K | 80 | 75 | 10,000 | - | Damp | White, 4 pack |
| | E26 | 15 | 93142989 | LED15A21/827-4PK | 120 | 24 | 5.2 | 1520 | 2700K | 80 | 100 | 10,000 | - | Damp | White, 4 pack |
| | E26 | 15 | 93142990 | LED15A21/830-4PK | 120 | 24 | 5.2 | 1520 | 3000K | 80 | 100 | 10,000 | - | Damp | White, 4 pack |
| | E26 | 15 | 93142991 | LED15A21/840-4PK | 120 | 24 | 5.2 | 1520 | 4000K | 80 | 100 | 10,000 | - | Damp | White, 4 pack |
| | E26 | 15 | 93142992 | LED15A21/850-4PK | 120 | 24 | 5.2 | 1520 | 5000K | 80 | 100 | 10,000 | - | Damp | White, 4 pack |


## Bright Stik™

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Bright Stik™** | | | | | | | | | | | | | | | |
| Bright Stik™ | E26 | 5.5 | 66256 | LED5.5LS3/827 | 120 | 48 | 4.45 | 450 | 2700K | 80 | 40 | 15,000 | - | Damp | 3 pack |
| | E26 | 5.5 | 75177 | LED5.5LS3/850 | 120 | 48 | 4.45 | 450 | 5000K | 80 | 40 | 15,000 | - | Damp | 3 pack |
| | E26 | 9 | 75184 | LED9LS3/827 | 120 | 48 | 4.45 | 800 | 2700K | 80 | 60 | 15,000 | - | Damp | 3 pack |
| | E26 | 9 | 75588 | LED9LS3/850 | 120 | 48 | 4.45 | 800 | 5000K | 80 | 60 | 15,000 | - | Damp | 3 pack |
| | E26 | 12 | 75590 | LED12LS2/827 | 120 | 32 | 5.24 | 1250 | 2700K | 80 | 75 | 15,000 | - | Damp | 2 pack |
| | E26 | 12 | 75591 | LED12LS2/850 | 120 | 32 | 5.24 | 1250 | 5000K | 80 | 75 | 15,000 | - | Damp | 2 pack |
| | E26 | 15 | 75593 | LED15LS2/827 | 120 | 32 | 5.24 | 1700 | 2700K | 80 | 100 | 15,000 | - | Damp | 2 pack |
| | E26 | 15 | 75644 | LED15LS2/850 | 120 | 32 | 5.24 | 1700 | 5000K | 80 | 100 | 15,000 | - | Damp | 2 pack |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## **LED Lamps** – Decorative

Decorative LED lamps feature LED "filaments" in glass bulbs, mimicking a traditional decorative lamp look. Various shapes, bases and wattages are available in clear and white finishes.



## Catalog Logic:

**Bulb Shape:** Bulb shape followed by its size (the maximum diameter of the bulb expressed in eighths of an inch).

**Base Type:** ANSI Base

**Watts:** Energy Used (as defined by FTC Lamp Label Rules)

**Order Code:** Use the order code when ordering to ensure that you receive the exact product you require

**Description:** Lamp Model Description

**Volts:** Lamp data is based on operation at rated voltage

**Carton Quantity:** Number of lamps packed in a carton

**MOL (in):** Maximum Overall Length in inches

**Lumens:** Light output (as defined by FTC Lamp Label Rules)

**Color Temperature (K):** A measure of the visual "warmth" or "coolness" of the light from the lamp. The higher the value, the whiter or "cooler" the light appears.

**Color Rendering Index (CRI or R):** An indication of the ability of the lamp to render object colors in a normal natural way. The higher the number (0-100), the better the color appearance.

**Wattage Replacement:** Wattage of Traditional Lamp the LED Lamp is meant to replace

**Rated Life L70:** Hours of operation the lamp will provide before reaching 70% of its original lumen output

**Dimmable:** Indicates whether a lamp is dimmable or not

**Location Rating:** Location Rating as defined for LED Lamps by UL 1993


**Additional Information:** Typical application and/or other important information

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Wattage Replace-ment | Rated Life L70 (Hrs)[1] | Dimmable | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Candles** | | | | | | | | | | | | | | | |
| **CA** | E12 | 3.5 | 93142795 | LED4DFCAC-C-2PK | 120 | 12 | 4.6 | 300 | 2700K | 80 | 40 | 15,000 | Yes | Damp | All Glass, Clear, Bent Tip, 2 pack |

**LED4DFCAC-C-2PK**

- Wattage
- D = Dimmable
- F = Filament
- Shape (CA = bent tip Candle, B = Blunt tip, G = Globe)
- Base (C = Candelabra [E12], M = Medium [E26])
- Finish (C = Clear, W = White)
- 2PK = Inner pack of 2 lamps (Smallest unit of sale downstream)

## Lamp **Drawings** (not drawn to scale)



BC BM CAC CAM G16 G25

# LED Lamps - General Purpose


CAM


BM


G25


CAC


BC


G16


A15-VTG


ST19-VTG

## **Decorative** Lamps

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | Dim-mable | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Candles** | | | | | | | | | | | | | | | |
| CA/B | E26 | 2.5 | 93142804 | LED3DFCAM-C-2PK | 120 | 12 | 4.4 | 200 | 2700K | 80 | 25 | 15,000 | Yes | Damp | All Glass, Clear, Bent Tip, 2 pack |
| | E26 | 2.5 | 93142808 | LED3DFCAM-W-2PK | 120 | 12 | 4.4 | 200 | 2700K | 80 | 25 | 15,000 | Yes | Damp | All Glass, White, Bent Tip, 2 pack |
| | E26 | 3.5 | 93142811 | LED4DFBM-C-2PK | 120 | 12 | 3.8 | 300 | 2700K | 80 | 40 | 15,000 | Yes | Damp | All Glass, Clear, 2 pack |
| | E26 | 3.5 | 93142814 | LED4DFBM-W-2PK | 120 | 12 | 3.8 | 300 | 2700K | 80 | 40 | 15,000 | Yes | Damp | All Glass, White, 2 pack |
| | E26 | 3.5 | 93311960 | LED4DFCAM-C/927 | 120 | 12 | 4.4 | 300 | 2700K | 90 | 40 | 15,000 | Yes | Damp | All Glass, Clear, Bent Tip, CEC Title 20 |
| | E26 | 3.5 | 93142812 | LED4DFCAM-C-2PK | 120 | 12 | 4.4 | 300 | 2700K | 80 | 40 | 15,000 | Yes | Damp | All Glass, Clear, Bent Tip, 2 pack |
| | E26 | 3.5 | 93142815 | LED4DFCAM-W-2PK | 120 | 12 | 4.4 | 300 | 2700K | 80 | 40 | 15,000 | Yes | Damp | All Glass, White, Bent Tip, 2 pack |
| | E26 | 5 | 93142855 | LED5DFBM-C-2PK | 120 | 12 | 3.8 | 500 | 2700K | 80 | 60 | 15,000 | Yes | Damp | All Glass, Clear, 2 pack |
| | E26 | 5 | 93142856 | LED5DFBM-W-2PK | 120 | 12 | 3.8 | 500 | 2700K | 80 | 60 | 15,000 | Yes | Damp | All Glass, White, 2 pack |
| | E26 | 5 | 93142851 | LED5DFCAM-C-2PK | 120 | 12 | 4.4 | 500 | 2700K | 80 | 60 | 15,000 | Yes | Damp | All Glass, Clear, Bent Tip, 2 pack |
| | E26 | 5 | 93142852 | LED5DFCAM-W-2PK | 120 | 12 | 4.4 | 500 | 2700K | 80 | 60 | 15,000 | Yes | Damp | All Glass, White, Bent Tip, 2 pack |
| | E12 | 2.5 | 93142792 | LED3DFCAC-C-2PK | 120 | 12 | 4.6 | 200 | 2700K | 80 | 25 | 15,000 | Yes | Damp | All Glass, Clear, Bent Tip, 2 pack |
| | E12 | 2.5 | 93142793 | LED3DFCAC-W-2PK | 120 | 12 | 4.6 | 200 | 2700K | 80 | 25 | 15,000 | Yes | Damp | All Glass, White, Bent Tip, 2 pack |
| | E12 | 3.5 | 93142794 | LED4DFBC-C-2PK | 120 | 12 | 3.9 | 300 | 2700K | 80 | 40 | 15,000 | Yes | Damp | All Glass, Clear, 2 pack |
| | E12 | 3.5 | 93142796 | LED4DFBC-W-2PK | 120 | 12 | 3.9 | 300 | 2700K | 80 | 40 | 15,000 | Yes | Damp | All Glass, White, 2 pack |
| | E12 | 3.5 | 93312028 | LED4DFCAC-C/927 | 120 | 12 | 4.6 | 300 | 2700K | 90 | 40 | 15,000 | Yes | Damp | All Glass, Clear, Bent Tip, CEC Title 20 |
| | E12 | 3.5 | 93142795 | LED4DFCAC-C-2PK | 120 | 12 | 4.6 | 300 | 2700K | 80 | 40 | 15,000 | Yes | Damp | All Glass, Clear, Bent Tip, 2 pack |
| | E12 | 3.5 | 93142797 | LED4DFCAC-W-2PK | 120 | 12 | 4.6 | 300 | 2700K | 80 | 40 | 15,000 | Yes | Damp | All Glass, White, Bent Tip, 2 pack |
| | E12 | 5 | 93142802 | LED5DFBC-C-2PK | 120 | 12 | 3.9 | 500 | 2700K | 80 | 60 | 15,000 | Yes | Damp | All Glass, Clear, 2 pack |
| | E12 | 5 | 93142803 | LED5DFBC-W-2PK | 120 | 12 | 3.9 | 500 | 2700K | 80 | 60 | 15,000 | Yes | Damp | All Glass, White, 2 pack |
| | E12 | 5 | 93142800 | LED5DFCAC-C-2PK | 120 | 12 | 4.6 | 500 | 2700K | 80 | 60 | 15,000 | Yes | Damp | All Glass, Clear, Bent Tip, 2 pack |
| | E12 | 5 | 93142801 | LED5DFCAC-W-2PK | 120 | 12 | 4.6 | 500 | 2700K | 80 | 60 | 15,000 | Yes | Damp | All Glass, White, Bent Tip, 2 pack |
| **Globes** | | | | | | | | | | | | | | | |
| G25 | E26 | 2.8 | 93142805 | LED3DFG25-C-2PK | 120 | 12 | 4.7 | 250 | 2700K | 80 | 25 | 15,000 | Yes | Damp | All Glass, Clear, 2 pack |
| | E26 | 2.8 | 93142807 | LED3DFG25-W-2PK | 120 | 12 | 4.7 | 250 | 2700K | 80 | 25 | 15,000 | Yes | Damp | All Glass, White, 2 pack |
| | E26 | 4 | 93311963 | LED4DFG25-C/927 | 120 | 12 | 4.7 | 350 | 2700K | 90 | 40 | 15,000 | Yes | Damp | All Glass, Clear, CEC Title 20 |
| | E26 | 4 | 93311966 | LED4DFG25-W/927 | 120 | 12 | 4.7 | 350 | 2700K | 90 | 40 | 15,000 | Yes | Damp | All Glass, White, CEC Title 20 |
| | E26 | 4 | 93142847 | LED4DFG25-C-2PK | 120 | 12 | 4.7 | 350 | 2700K | 80 | 40 | 15,000 | Yes | Damp | All Glass, Clear, 2 pack |
| | E26 | 4 | 93142846 | LED4DFG25-W-2PK | 120 | 12 | 4.7 | 350 | 2700K | 80 | 40 | 15,000 | Yes | Damp | All Glass, White, 2 pack |
| | E26 | 5 | 93142850 | LED5DFG25-C-2PK | 120 | 12 | 4.7 | 500 | 2700K | 80 | 60 | 15,000 | Yes | Damp | All Glass, Clear, 2 pack |
| | E26 | 5 | 93142849 | LED5DFG25-W-2PK | 120 | 12 | 4.7 | 500 | 2700K | 80 | 60 | 15,000 | Yes | Damp | All Glass, White, 2 pack |
| G16.5 | E12 | 4 | 93142798 | LED4DFG16C-C-2PK | 120 | 12 | 3.4 | 350 | 2700K | 80 | 40 | 15,000 | Yes | Damp | All Glass, Clear, 2 pack |
| | E12 | 4 | 93142799 | LED4DFG16C-W-2PK | 120 | 12 | 3.4 | 350 | 2700K | 80 | 40 | 15,000 | Yes | Damp | All Glass, White, 2 pack |

## **Vintage Style Decorative** Lamps

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[2] | MOL (in) | Lumens (Initial) | Color Temp. (Initial) | CRI | Wattage Replacement | Rated Life L70 (Hrs)[1] | Dim-mable | Location Rating[3] | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Vintage** | | | | | | | | | | | | | | | |
| A15 | E26 | 3 | 93311928 | LED3DFA15-C-VTG | 120 | 12 | 3.5 | 150 | 2150K | 90 | 25 | 15,000 | Yes | Damp | All Glass, Clear Amber, CEC Title 20 Exempt |
| ST19 | E26 | 5.5 | 93311890 | LED5DFST19-C-VTG | 120 | 12 | 5.3 | 400 | 2150K | 90 | 40 | 15,000 | Yes | Damp | All Glass, Clear Amber, CEC Title 20 Exempt |

[1] The life rating is based on the hours of operation the lamp will provide before reaching 70% of its original lumen output (L70)
[2] Minimum order quantity = Carton Qty
[3] UL 1993 Environmental Requirements for LED LAMPS
Damp Location – Exterior or interior location that is normally or periodically subject to condensation of moisture in, on, or adjacent to electrical equipment, including partially protected locations
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## **LED Lamps** - Inner Pack Lamp Quantity

Packaging configurations vary across the wide range of LED Lamps offered by Current. LED Tubes are packaged in bulk, with no inner pack inside the outer carton. Many lamps, such LED HID, are packaged in individual packs inside the outer carton. The table below details the materials that are packaged into saleable units of **more than one lamp**. These inner pack sizes are noted throughout the catalog in the "Additional Information" column, but the table below is provided as another reference.

| Lamp Category | Order Code | Description | Inner Pack Lamp Qty | Outer Carton Lamp Qty |
|---|---|---|---|---|
| Plug-in | 93300091 | LED11G24d-V/8SC-4PK | 4 | 24 |
| Plug-in | 93300090 | LED11G24d-H/8SC-4PK | 4 | 24 |
| Plug-in | 93300089 | LED9G24q-V/8SC-4PK | 4 | 24 |
| Plug-in | 93300088 | LED11BG24-V/8SC/120-347-4PK | 4 | 24 |
| Plug-in | 93300087 | LED11BG24-H/8SC/120-347-4PK | 4 | 24 |
| Plug-in | 93300068 | LED8BG24-O/827-4PK | 4 | 24 |
| Plug-in | 93300069 | LED8BG24-O/830-4PK | 4 | 24 |
| Plug-in | 93300080 | LED8BG24-O/835-4PK | 4 | 24 |
| Plug-in | 93300081 | LED8BG24-O/840-4PK | 4 | 24 |
| Plug-in | 93300082 | LED10BG24-O/827-4PK | 4 | 24 |
| Plug-in | 93300083 | LED10BG24-O/830-4PK | 4 | 24 |
| Plug-in | 93300084 | LED10BG24-O/835-4PK | 4 | 24 |
| Plug-in | 93300086 | LED10BG24-O/840-4PK | 4 | 24 |
| PAR | 93305603 | LED6DP16W830/35-6PK | 6 | 24 |
| PAR | 93153892 | LED12DP30VOW830/25-4PK | 4 | 16 |
| PAR | 93153891 | LED12DP30LVOW830/25-4PK | 4 | 16 |
| PAR | 93153880 | LED15DP38VOW830/35-4PK | 4 | 16 |
| MR16 | 93305604 | LED4D/GU10W830/35-6PK | 6 | 24 |
| MR16 | 93305605 | LED5D/GU10W830/35-6PK | 6 | 24 |
| RS Can | 93162554 | LED8DRS4/9SC-4PK | 4 | 16 |
| RS Can | 93162555 | LED8DRS6/9SC-4PK | 4 | 16 |
| RS Can | 93162556 | LED12DRS6/9SC-4PK | 4 | 16 |
| Reflector | 93305498 | LED8DBR30/927-6PK | 6 | 24 |
| Reflector | 93305499 | LED8DBR30/930-6PK | 6 | 24 |
| Reflector | 93305510 | LED8DBR30/940-6PK | 6 | 24 |
| Reflector | 93305512 | LED8DBR30/950-6PK | 6 | 24 |
| A-line | 93142809 | LED4DFA15-C-2PK | 2 | 12 |
| A-line | 93142810 | LED4DFA15-W-2PK | 2 | 12 |
| A-line | 93156446 | LED6DA19/827/E-4PK | 4 | 24 |
| A-line | 93156447 | LED6DA19/830/E-4PK | 4 | 24 |
| A-line | 93156448 | LED6DA19/840/E-4PK | 4 | 24 |
| A-line | 93156449 | LED6DA19/850/E-4PK | 4 | 24 |
| A-line | 93156450 | LED10DA19/827/E-4PK | 4 | 24 |
| A-line | 93156531 | LED10DA19/830/E-4PK | 4 | 24 |
| A-line | 93156532 | LED10DA19/840/E-4PK | 4 | 24 |
| A-line | 93156533 | LED10DA19/850/E-4PK | 4 | 24 |
| A-line | 93156534 | LED12DA19/827/E-4PK | 4 | 24 |
| A-line | 93156535 | LED12DA19/830/E-4PK | 4 | 24 |
| A-line | 93156536 | LED12DA19/840/E-4PK | 4 | 24 |
| A-line | 93156537 | LED12DA19/850/E-4PK | 4 | 24 |
| A-line | 93156538 | LED15DA19/827-4PK | 4 | 24 |
| A-line | 93156539 | LED15DA19/830-4PK | 4 | 24 |
| A-line | 93156540 | LED15DA19/840-4PK | 4 | 24 |
| A-line | 93156541 | LED15DA19/850-4PK | 4 | 24 |
| A-line | 93156542 | LED10DA19/GU24/827/E-4PK | 4 | 24 |
| A-line | 93156543 | LED15DA19/GU24/827-4PK | 4 | 24 |
| A-line | 93156602 | LED13A19/30/100/827-4PK | 4 | 24 |
| A-line | 93156603 | LED17A21/50/150/827-4PK | 4 | 24 |
| A-line | 93142977 | LED5A19/827-4PK | 4 | 24 |
| A-line | 93142978 | LED5A19/830-4PK | 4 | 24 |
| A-line | 93142979 | LED5A19/840-4PK | 4 | 24 |
| A-line | 93142980 | LED5A19/850-4PK | 4 | 24 |
| A-line | 93142981 | LED9A19/827-4PK | 4 | 24 |
| A-line | 93142982 | LED9A19/830-4PK | 4 | 24 |
| A-line | 93142983 | LED9A19/840-4PK | 4 | 24 |
| A-line | 93142984 | LED9A19/850-4PK | 4 | 24 |
| A-line | 93142985 | LED11A21/827-4PK | 4 | 24 |
| A-line | 93142986 | LED11A21/830-4PK | 4 | 24 |
| A-line | 93142987 | LED11A21/840-4PK | 4 | 24 |
| A-line | 93142988 | LED11A21/850-4PK | 4 | 24 |
| A-line | 93142989 | LED15A21/827-4PK | 4 | 24 |
| A-line | 93142990 | LED15A21/830-4PK | 4 | 24 |
| A-line | 93142991 | LED15A21/840-4PK | 4 | 24 |
| A-line | 93142992 | LED15A21/850-4PK | 4 | 24 |
| Bright Stik™ | 66256 | LED5.5LS3/827 | 3 | 48 |
| Bright Stik™ | 75177 | LED5.5LS3/850 | 3 | 48 |
| Bright Stik™ | 75184 | LED9LS3/827 | 3 | 48 |
| Bright Stik™ | 75588 | LED9LS3/850 | 3 | 48 |
| Bright Stik™ | 75590 | LED12LS2/827 | 2 | 32 |
| Bright Stik™ | 75591 | LED12LS2/850 | 2 | 32 |
| Bright Stik™ | 75593 | LED15LS2/827 | 2 | 32 |
| Bright Stik™ | 75644 | LED15LS2/850 | 2 | 32 |
| Decorative | 93142804 | LED3DFCAM-C-2PK | 2 | 12 |
| Decorative | 93142808 | LED3DFCAM-W-2PK | 2 | 12 |
| Decorative | 93142811 | LED4DFBM-C-2PK | 2 | 12 |
| Decorative | 93142814 | LED4DFBM-W-2PK | 2 | 12 |
| Decorative | 93142812 | LED4DFCAM-C-2PK | 2 | 12 |
| Decorative | 93142815 | LED4DFCAM-W-2PK | 2 | 12 |
| Decorative | 93142855 | LED5DFBM-C-2PK | 2 | 12 |
| Decorative | 93142856 | LED5DFBM-W-2PK | 2 | 12 |
| Decorative | 93142851 | LED5DFCAM-C-2PK | 2 | 12 |
| Decorative | 93142852 | LED5DFCAM-W-2PK | 2 | 12 |
| Decorative | 93142792 | LED3DFCAC-C-2PK | 2 | 12 |
| Decorative | 93142793 | LED3DFCAC-W-2PK | 2 | 12 |
| Decorative | 93142794 | LED4DFBC-C-2PK | 2 | 12 |
| Decorative | 93142796 | LED4DFBC-W-2PK | 2 | 12 |
| Decorative | 93142795 | LED4DFCAC-C-2PK | 2 | 12 |
| Decorative | 93142797 | LED4DFCAC-W-2PK | 2 | 12 |
| Decorative | 93142802 | LED5DFBC-C-2PK | 2 | 12 |
| Decorative | 93142803 | LED5DFBC-W-2PK | 2 | 12 |
| Decorative | 93142800 | LED5DFCAC-C-2PK | 2 | 12 |
| Decorative | 93142801 | LED5DFCAC-W-2PK | 2 | 12 |
| Decorative | 93142805 | LED3DFG25-C-2PK | 2 | 12 |
| Decorative | 93142807 | LED3DFG25-W-2PK | 2 | 12 |
| Decorative | 93142847 | LED4DFG25-C-2PK | 2 | 12 |
| Decorative | 93142846 | LED4DFG25-W-2PK | 2 | 12 |
| Decorative | 93142850 | LED5DFG25-C-2PK | 2 | 12 |
| Decorative | 93142849 | LED5DFG25-W-2PK | 2 | 12 |
| Decorative | 93142798 | LED4DFG16C-C-2PK | 2 | 12 |
| Decorative | 93142799 | LED4DFG16C-W-2PK | 2 | 12 |



# TRADITIONAL
# LAMPS & BALLASTS


Current carries a full family of Traditional lamps that feature plug-and-play simplicity. Our engineering leadership over the years in Traditional lighting has resulted in products that provide the exceptional light quality that you know and love.

# Traditional Lamps




**Linear** Fluorescent lighting, first introduced by GE in 1939, continues to offer low operating costs and long life.


## **Lamp Drawings** (not drawn to scale)




T9 Circline (1-1/8" diameter) 4-Pin Base (G10q)




T5 (5/8" diameter) Miniature Bi-Pin Base (G5)




T6 (3/4" diameter) Single Pin Base (Fa8)




T8 (1" diameter) Single Pin Base (Fa8)




T8 (1" diameter) Medium Bi-Base (G13)




T8 (1" diameter) Recessed Double Contact Base (R17d)




T10 (11/4" diameter) Recessed Double Contact Base (R17d)




Mod-U-Line® T8/U6 (1" diameter) Medium Bi-Pin Base (G13)




Mod-U-Line® T12/U3 (1 1/2" diameter) Medium Bi-Pin Base (G13)




Mod-U-Line® T12/U6 (1-1/2" diameter) Medium Bi-Pin Base (G13)




T12 (1-1/2" Diameter) Single Pin Base (Fa8)




T12 (1-1/2" Diameter) Medium Bi-Pin Base (G13)



T12 (1-1/2" Diameter) Recessed Double Contact Base (R17d)




T17 (2-1/8" diameter) Mogul Bi-Pin (G20)



Power Groove® (2-1/8" diameter)
Recessed Double Contact Base (R17d)

## **Base Identification** (not drawn to scale)



Miniature Bi-Pin G5 | Medium Bi-Pin G13 | Mogul Bi-Pin G20 | Single Pin Fa8 | Recessed Double Contact R17d | 4-Pin G10q (Circline)

## Catalog Logic:

The following terms and descriptions can help you when checking fluorescent lamp specifications and when ordering products. Within each product line, lamps are divided into families and listed by bulb, base and then wattage.

**Color Rendering Index (CRI or R):** An indication of the ability of the lamp to render object colors in a normal natural way. The higher the number (0-100), the better the color appearance

**Bulb Shape:** followed by its size (the maximum diameter of the bulb expressed in eighths of an inch).

**Order Code:** Use the order code when ordering to ensure that you receive the exact product you require.

**Color Temperature – Kelvins (K):** A measure of the visual "warmth" or "coolness" of the light from the lamp. The higher the value, the whiter or "cooler" the light appears.

**Nominal Length (in):** Lamp length including base and/or pins.

**Means Lumens:** Lamp light output at 40% of rated lamp life or 8K hours for lamps exceeding 20K hours life.

**Watts:** Energy used (as defined by FTC Lamp Label Rules). To estimate energy consumption (kWh), multiply watts x hours of use and divide by 1000.

**Carton Quantity:** Number of lamps packed in a carton

**Initial Lumens:** Lamp light output after the initial 100 hours of operation.

**Description:** Lamp Model Description

**Rated Life (hours):** Life (as defined by FTC Lamp Label Rules) is rated life in hours.

**Base:** The type of base

**LED Replacement:** Current offers a wide range of LED replacement lamps. The LED lamp models are provided as general guidance. Often, there will be more than one LED Lamp that may be used to replace a Traditional lamp. For Traditional lamps that operated off a ballast, the ballast bypass (UL Type B) LED option is given unless otherwise noted. The application should be considered when selecting an LED replacement lamp. Sometimes, Traditional lamps do not have a suitable LED replacement due to special application considerations, such as very high heat. Contact Current for additional guidance if the appropriate LED solution is unclear.

| | | | | | | | | | | | | | Type B LED Replacement | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Bulb Shape | Base Type | Watts | Nominal Length (in.) | Order Code | Description | Carton Qty | Rated Life (3hr/Start) | Rated Life (12hr/Start) | Initial Lumens | Mean Lumens | Color Temp. | CRI | Order Code | Description |
| **T5 High Efficiency** | | | | | | | | | | | | | | |
| T5 | G5 | 14 | 21.6 | 31590 | F14W/T5/830/ECO | 40 | 30,000 | 36,000 | 1,350 | 1,240 | 3000K | 85 | 93319133 | LEDLCBDT5/G2/8SC/120-347 |

## F14W/T5/830/ECO

- F14W: Identifies as Fluorescent lamp
- T5: Identifies either the lamp's wattage or its length in inches
- 830: Identifies the lamp shape and the bulb diameter in eighths of an inch
- ECO: Identifies the lamp finish or color
- TCLP: Identifies TCLP compliance

Lamp Contains Mercury.
Manage in Accord with Disposal Laws.
See **www.lamprecycle.org** or 1-800-327-0097

**Fluorescent Phase-Out Regulations**: Several US states have enacted legislation that prohibit/will prohibit the sale of Linear and Compact Fluorescent Lamps within their state. For more information including effective dates, please visit www.LED.com/lamplegislation

## T5 Starcoat Ecolux® Lamps

| Bulb Shape | Base Type | Watts | Nominal Length (in.) | Order Code | Description | Carton Qty[1] | Rated Life (3hr/Start) | Rated Life (12hr/Start) | Initial Lumens | Mean Lumens | Color Temp. | CRI | Notes | Type B LED Replacement Order Code | Type B LED Replacement Description |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **T5 High Efficiency** | | | | | | | | | | | | | | | |
| T5 | G5 | 14 | 21.6 | 31590 | F14W/T5/830/ECO | 40 | 30,000 | 36,000 | 1,350 | 1,240 | 3000K | 85 | | 93319133 | LEDLCBDT5/G2/8SC/120-347 |
| | G5 | 14 | 21.6 | 46671 | F14W/T5/835/ECO | 40 | 30,000 | 36,000 | 1,350 | 1,240 | 3500K | 85 | | 93319133 | LEDLCBDT5/G2/8SC/120-347 |
| | G5 | 14 | 21.6 | 46673 | F14W/T5/841/ECO | 40 | 30,000 | 36,000 | 1,350 | 1,240 | 4100K | 85 | | 93319133 | LEDLCBDT5/G2/8SC/120-347 |
| | G5 | 21 | 33.4 | 46677 | F21W/T5/830/ECO | 40 | 30,000 | 36,000 | 2,100 | 1,930 | 3000K | 85 | | 93319131 | LEDLCBDT5/G3/8SC/120-347 |
| | G5 | 21 | 33.4 | 46684 | F21W/T5/835/ECO | 40 | 30,000 | 36,000 | 2,100 | 1,930 | 3500K | 85 | | 93319131 | LEDLCBDT5/G3/8SC/120-347 |
| | G5 | 21 | 33.4 | 46687 | F21W/T5/841/ECO | 40 | 30,000 | 36,000 | 2,100 | 1,930 | 4100K | 85 | | 93319131 | LEDLCBDT5/G3/8SC/120-347 |
| | G5 | 28 | 45.2 | 46704 | F28W/T5/830/ECO | 40 | 30,000 | 36,000 | 2,900 | 2,660 | 3000K | 85 | | 93319129 | LEDLCBDT5/G4/8SC/120-347 |
| | G5 | 28 | 45.2 | 46705 | F28W/T5/835/ECO | 40 | 30,000 | 36,000 | 2,900 | 2,660 | 3500K | 85 | | 93319129 | LEDLCBDT5/G4/8SC/120-347 |
| | G5 | 28 | 45.2 | 46706 | F28W/T5/841/ECO | 40 | 30,000 | 36,000 | 2,900 | 2,660 | 4100K | 85 | | 93128486 | LED14BDT5G4840HE |
| **T5 High Output** | | | | | | | | | | | | | | | |
| T5 | G5 | 24 | 21.6 | 46699 | F24W/T5/830/ECO | 40 | 30,000 | 36,000 | 2,000 | 1,840 | 3000K | 85 | | 93319133 | LEDLCBDT5/G2/8SC/120-347 |
| | G5 | 24 | 21.6 | 46700 | F24W/T5/835/ECO | 40 | 30,000 | 36,000 | 2,000 | 1,840 | 3500K | 85 | | 93319133 | LEDLCBDT5/G2/8SC/120-347 |
| | G5 | 24 | 21.6 | 46701 | F24W/T5/841/ECO | 40 | 30,000 | 36,000 | 2,000 | 1,840 | 4100K | 85 | | 93319133 | LEDLCBDT5/G2/8SC/120-347 |
| | G5 | 39 | 33.4 | 46744 | F39W/T5/830/ECO | 40 | 30,000 | 36,000 | 3,500 | 3,220 | 3000K | 85 | | 93319131 | LEDLCBDT5/G3/8SC/120-347 |
| | G5 | 39 | 33.4 | 46745 | F39W/T5/835/ECO | 40 | 30,000 | 36,000 | 3,500 | 3,220 | 3500K | 85 | | 93319131 | LEDLCBDT5/G3/8SC/120-347 |
| | G5 | 54 | 45.2 | 46759 | F54W/T5/830/ECO | 40 | 30,000 | 36,000 | 5,000 | 4,600 | 3000K | 85 | | 93319129 | LEDLCBDT5/G4/8SC/120-347 |
| | G5 | 54 | 45.2 | 46760 | F54W/T5/835/ECO | 40 | 30,000 | 36,000 | 5,000 | 4,600 | 3500K | 85 | | 93100293 | LED25BDT5/G4/835 |
| | G5 | 54 | 45.2 | 46761 | F54W/T5/841/ECO | 40 | 30,000 | 36,000 | 5,000 | 4,600 | 4100K | 85 | | 93100294 | LED25BDT5/G4/840 |
| | G5 | 54 | 45.2 | 46762 | F54W/T5/850/ECO | 40 | 30,000 | 36,000 | 4,800 | 4,410 | 5000K | 85 | | 93100295 | LED25BDT5/G4/850 |
| | G5 | 54 | 45.2 | 46763 | F54W/T5/865/ECO | 40 | 30,000 | 36,000 | 4,750 | 4,370 | 6500K | 85 | | 93100295 | LED25BDT5/G4/850 |

## T5 Preheat Lamps

| Bulb Shape | Base Type | Watts | Nominal Length (in.) | Order Code | Description | Carton Qty[1] | Rated Life (3hr/Start) | Initial Lumens | Mean Lumens | Color Temp. | CRI | Notes | Type B LED Replacement Order Code | Type B LED Replacement Description |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **12" and 21" Short T5** | | | | | | | | | | | | | | |
| T5 | G5 | 8 | 12.0 | 10059 | F8T5/CW | 24 | 5,000 | 400 | 320 | 4100K | 60 | | | |
| | G5 | 13 | 21.0 | 10086 | F13T5/CW | 24 | 5,000 | 850 | 705 | 4100K | 60 | | | |

## T8 Starcoat® Lamps

| Bulb Shape | Base Type | Watts | Nominal Length (in.) | Order Code | Description | Carton Qty[1] | Rated Life (3hr/Start) | Rated Life (12hr/Start) | Initial Lumens | Mean Lumens | Color Temp. | CRI | Notes | Type B LED Replacement Order Code | Type B LED Replacement Description |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **2' T8 Ecolux®** | | | | | | | | | | | | | | | |
| T8 | G13 | 17 | 24.0 | 45741 | F17T8/SP30/ECO | 24 | 30,000 | 36,000 | 1,325 | 1,260 | 3000K | 78 | | 93313567 | LEDLCBDT8/G2/8SC/120-347 |
| | G13 | 17 | 24.0 | 45743 | F17T8/SP35/ECO | 24 | 30,000 | 36,000 | 1,325 | 1,260 | 3500K | 78 | | 39560 | LED9BDT8/G2/835 |
| | G13 | 17 | 24.0 | 45748 | F17T8/SP41/ECO | 24 | 30,000 | 36,000 | 1,325 | 1,260 | 4100K | 78 | | 39561 | LED9BDT8/G2/840 |
| **3' T8 Ecolux®** | | | | | | | | | | | | | | | |
| T8 | G13 | 25 | 36.0 | 45754 | F25T8/SP35/ECO | 24 | 30,000 | 36,000 | 2,080 | 1,970 | 3500K | 78 | | 39547 | LED12BDT8/G3/835 |
| | G13 | 25 | 36.0 | 45756 | F25T8/SP41/ECO | 24 | 30,000 | 36,000 | 2,080 | 1,970 | 4100K | 78 | | 39554 | LED12BDT8/G3/840 |
| **4' T8 Ecolux®** | | | | | | | | | | | | | | | |
| T8 | G13 | 32 | 48.0 | 68850 | F32T8/SPX30/ECO2 | 36 | 30,000 | 36,000 | 2,925 | 2,770 | 3000K | 85 | Δ | 39493 | LED14BDT8/G4/830 |
| | G13 | 32 | 48.0 | 68851 | F32T8/SPX35/ECO2 | 36 | 30,000 | 36,000 | 2,925 | 2,770 | 3500K | 85 | Δ | 39494 | LED14BDT8/G4/835 |
| | G13 | 32 | 48.0 | 68852 | F32T8/SPX41/ECO2 | 36 | 30,000 | 36,000 | 2,925 | 2,770 | 4100K | 85 | Δ | 39498 | LED14BDT8/G4/840 |
| | G13 | 32 | 48.0 | 68853 | F32T8/SPX50/ECO2 | 36 | 30,000 | 36,000 | 2,900 | 2,755 | 5000K | 82 | Δ | 39519 | LED14BDT8/G4/850 |
| | G13 | 32 | 48.0 | 66342 | F32T8/SPX65/ECO2 | 36 | 30,000 | 36,000 | 2,900 | 2,755 | 6500K | 78 | Δ | 39519 | LED14BDT8/G4/850 |

[1] Minimum order quantity = Carton Qty
Δ Impacted by 4' fluorescent state legislation, SKU not for sale in Vermont after 1/1/2024 due to state legislation; for more information please visit www.LED.com/lamplegislation
Please note Current lamps are not for sale for use in Yukon Territory in Canada

****Fluorescent Phase-Out Regulations****: Several US states have enacted legislation that prohibit/will prohibit the sale of Linear and Compact Fluorescent Lamps within their state. For more information including effective dates, please visit www.LED.com/lamplegislation

## **Ultra Energy Saving T8** Lamps

| Bulb Shape | Base Type | Watts | Nominal Length (in.) | Order Code | Description | Carton Qty[1] | Rated Life (3hr/Start) | Rated Life (12hr/Start) | Initial Lumens | Mean Lumens | Color Temp. | CRI | Notes | Type B LED Replacement Order Code | Type B LED Replacement Description |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **4' T8 Ecolux® 25 Watt Lamp** | | | | | | | | | | | | | | | |
| T8 | G13 | 25 | 48.0 | 72129 | F32T8/25W/SPX35/ECO | 36 | 50,000 | 55,000 | 2,500 | 2,350 | 3500K | 85 | Δ | 93117213 | LED11BDT8/G4/835 |
| | G13 | 25 | 48.0 | 72130 | F32T8/25W/SPX41/ECO | 36 | 50,000 | 55,000 | 2,500 | 2,350 | 4100K | 85 | Δ | 93117214 | LED11BDT8/G4/840 |
| | G13 | 25 | 48.0 | 72131 | F32T8/25W/SPX50/ECO | 36 | 50,000 | 55000 | 2500 | 2350 | 5000K | 80 | Δ | 93117215 | LED11BDT8/G4/850 |
| **4' T8 Ecolux® 28 Watt Lamp** | | | | | | | | | | | | | | | |
| T8 | G13 | 28 | 48.0 | 72864 | F28T8/XL/SPX35/ECO | 36 | 45,000 | 50,000 | 2,675 | 2,515 | 3500K | 85 | Δ | 93117213 | LED11BDT8/G4/835 |
| | G13 | 28 | 48.0 | 72866 | F28T8/XL/SPX41/ECO | 36 | 45,000 | 50,000 | 2,675 | 2,515 | 4100K | 82 | Δ | 93117214 | LED11BDT8/G4/840 |
| | G13 | 28 | 48.0 | 72867 | F28T8/XL/SPX50/ECO | 36 | 45,000 | 50,000 | 2,675 | 2,515 | 5000K | 80 | Δ | 93117215 | LED11BDT8/G4/850 |
| **4' T8 Ecolux® High Lumen** | | | | | | | | | | | | | | | |
| T8 | G13 | 32 | 48.0 | 10326 | F32T8/XL/SPX35/HL/ECO | 36 | 40,000 | 45,000 | 3,100 | 2,915 | 3500K | 85 | Δ | 39494 | LED14BDT8/G4/835 |
| | G13 | 32 | 48.0 | 10322 | F32T8/XL/SPX41/HL/ECO | 36 | 40,000 | 45,000 | 3,100 | 2,915 | 4100K | 82 | Δ | 39498 | LED14BDT8/G4/840 |
| | G13 | 32 | 48.0 | 42556 | F32T8/XL/SPX50/HL/ECO | 36 | 40,000 | 45,000 | 3,000 | 2,820 | 5000K | 80 | Δ | 39519 | LED14BDT8/G4/850 |

## **8' T8** Lamps

| Bulb Shape | Base Type | Watts | Nominal Length (in.) | Order Code | Description | Carton Qty[1] | Rated Life (3hr/Start) | Rated Life (12hr/Start) | Initial Lumens | Mean Lumens | Color Temp. | CRI | Notes | Type B LED Replacement Order Code | Type B LED Replacement Description |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **8' T8 XL Extra-Life** | | | | | | | | | | | | | | | |
| T8 | Fa8 | 59 | 96.0 | 68869 | F96T8/XL/SPX35/2 | 24 | 24,000 | 30,000 | 5,950 | 5,650 | 3500K | 85 | | 93319020 | LED42BDT8/G8/Fa8/8SC/120-347 |
| | Fa8 | 59 | 96.0 | 68870 | F96T8/XL/SPX41/2 | 24 | 24,000 | 30,000 | 5,400 | 4,860 | 4100K | 85 | | 93319020 | LED42BDT8/G8/Fa8/8SC/120-347 |
| | Fa8 | 59 | 96.0 | 68871 | F96T8/XL/SPX50/2 | 24 | 24,000 | 30,000 | 5,950 | 5,650 | 5000K | 82 | | 93319020 | LED42BDT8/G8/Fa8/8SC/120-347 |

## **8' T8 High Output** Lamps

| Bulb Shape | Base Type | Watts | Nominal Length (in.) | Order Code | Description | Carton Qty[1] | Rated Life (3hr/Start) | Initial Lumens | Mean Lumens | Color Temp. | CRI | Notes | Type B LED Replacement Order Code | Type B LED Replacement Description |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **8' T8 High Output – Recessed Double Contact** | | | | | | | | | | | | | | |
| T8 | R17D | 86 | 96.0 | 12533 | F96T8/SPX35/HO | 24 | 18,000 | 8,200 | 7,800 | 3500K | 85 | | 93319022 | LED42BDT8/G8/R17d/8SC/120-347 |
| | R17D | 86 | 96.0 | 12534 | F96T8/SPX41/HO | 24 | 18,000 | 8,200 | 7,800 | 4100K | 85 | | 93319022 | LED42BDT8/G8/R17d/8SC/120-347 |
| | R17D | 86 | 96.0 | 12535 | F96T8/SPX50/HO | 24 | 18,000 | 8,200 | 7,800 | 5000K | 82 | | 93319022 | LED42BDT8/G8/R17d/8SC/120-347 |

## **T8 Mod-U-Line®** Lamps

| Bulb Shape | Base Type | Watts | Nominal Length (in.) | Order Code | Description | Carton Qty[1] | Rated Life (3hr/Start) | Initial Lumens | Mean Lumens | Color Temp. | CRI | Notes | Type B LED Replacement Order Code | Type B LED Replacement Description |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **T8 1-5/8" Spacing Ecolux®** | | | | | | | | | | | | | | |
| T8 | G13 | 31 | 22.5 | 72118 | F31T8/SPX35/U/ECO | 15 | 24,000 | 2,775 | 2,440 | 3500K | 82 | | 93320487 | LED13BDT8/U/U6/8SC/120-347 |
| | G13 | 31 | 22.5 | 72119 | F31T8/SPX41/U/ECO | 15 | 24,000 | 2,775 | 2,440 | 4100K | 82 | | 93320487 | LED13BDT8/U/U6/8SC/120-347 |
| **T8 6" Spacing Ecolux®** | | | | | | | | | | | | | | |
| T8 | G13 | 32 | 22.5 | 28145 | F32T8/SP30/U6/ECO | 12 | 20,000 | 2,700 | 2,375 | 3000K | 78 | | 93320487 | LED13BDT8/U/U6/8SC/120-347 |
| | G13 | 32 | 22.5 | 28149 | F32T8/SP35/U6/ECO | 12 | 20,000 | 2,700 | 2,375 | 3500K | 78 | | 93133050 | LED13BDT8/U6/835 |
| | G13 | 32 | 22.5 | 28152 | F32T8/SP41/U6/ECO | 12 | 20,000 | 2,700 | 2,375 | 4100K | 78 | | 93133051 | LED13BDT8/U6/840 |
| | G13 | 32 | 22.5 | 72112 | F32T8/SPX35/U6/ECO | 12 | 20,000 | 2,800 | 2,465 | 3500K | 82 | | 93133050 | LED13BDT8/U6/835 |
| | G13 | 32 | 22.5 | 72113 | F32T8/SPX41/U6/ECO | 12 | 20,000 | 2,800 | 2,465 | 4100K | 82 | | 93133051 | LED13BDT8/U6/840 |

## **Special Application** Lamps

| Bulb Shape | Base Type | Watts | Nominal Length (in.) | Order Code | Description | Carton Qty[1] | Rated Life (3hr/Start) | Rated Life (12hr/Start) | Initial Lumens | Mean Lumens | Color Temp. | CRI | Notes | Type B LED Replacement Order Code | Type B LED Replacement Description |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **covRguard® Shatter Resistant** | | | | | | | | | | | | | | | |
| *(T5 High Efficiency)* | | | | | | | | | | | | | | | |
| T5 | G5 | 28 | 45.2 | 81547 | F28W/T5/835/ECO/CVG | 40 | 30,000 | 36,000 | 2,813 | 2,672 | 3500K | 85 | Blocks UV | | |
| *(T5 High Output)* | | | | | | | | | | | | | | | |
| T5 | G5 | 54 | 45.2 | 48458 | F54T5/841/HO/ECO/CVG | 40 | 30,000 | 36,000 | 4,850 | 4,560 | 4100K | 85 | | 93155904 | LED25BDT5/G4/840/CVG |
| | G5 | 54 | 45.2 | 80311 | F54T5/850/HO/ECO/CVG | 40 | 30,000 | 36,000 | 4,650 | 4,370 | 5000K | 85 | | 93155905 | LED25BDT5/G4/850/CVG |
| **T8 Ecolux® w/ Starcoat®** | | | | | | | | | | | | | | | |
| *(4' T8 (48") Ecolux® w/Starcoat®)* | | | | | | | | | | | | | | | |
| T8 | G13 | 32 | 48.0 | 41126 | F32T8SPX35ECOCVG | 36 | 30,000 | 36,000 | 2,860 | 2,715 | 3500K | 85 | Blocks UV, Δ | 93154588 | LED16BDT8/G4/835XL/CVG |
| | G13 | 32 | 48.0 | 41127 | F32T8SPX41ECOCVG | 36 | 30,000 | 36,000 | 2,860 | 2,715 | 4100K | 85 | Blocks UV, Δ | 93154589 | LED16BDT8/G4/840XL/CVG |
| | G13 | 32 | 48.0 | 15971 | F32T8SPX50ECOCVG | 36 | 30,000 | 36,000 | 2,715 | 2,580 | 5000K | 82 | Blocks UV, Δ | 93154586 | LED16BDT8/G4/850XL/CVG |

[1] Minimum order quantity = Carton Qty
Δ Impacted by 4' fluorescent state legislation, SKU not for sale in Vermont after 1/1/2024 due to state legislation; for more information please visit www.LED.com/lamplegislation
Please note Current lamps are not for sale for use in Yukon Territory in Canada

# **Linear** Fluorescent Lamps

****Fluorescent Phase-Out Regulations****: Several US states have enacted legislation that prohibit/will prohibit the sale of Linear and Compact Fluorescent Lamps within their state. For more information including effective dates, please visit www.LED.com/lamplegislation

## **T12** Lamps

| Bulb Shape | Base Type | Watts | Nominal Length (in.) | Order Code | Description | Carton Qty[1] | Rated Life (3hr/Start) | Initial Lumens | Mean Lumens | Color Temp. | CRI | Notes | Type B LED Replacement Order Code | Type B LED Replacement Description |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **2' T12 - Preheat (TCLP Compliant)** | | | | | | | | | | | | | | |
| T12 | G13 | 20 | 24.0 | 80045 | F20T12/CW/ECO | 24 | 9,000 | 1,200 | 1,150 | 4100K | 60 | | 39561 | LED9BDT8/G2/840 |
| | G13 | 20 | 24.0 | 80047 | F20T12/D/ECO | 24 | 9,000 | 1,025 | 945 | 6500K | 75 | | 39563 | LED9BDT8/G2/850 |
| **4' T12 – Rapid Start (TCLP Compliant)** | | | | | | | | | | | | | | |
| **(34W Watt-Miser® Ecolux®)** | | | | | | | | | | | | | | |
| T12 | G13 | 34 | 48.0 | 66474 | F34CX41/WM/ECO | 30 | 20,000 | 2,500 | 2,200 | 4100K | 87 | Δ | 93117214 | LED11BDT8/G4/840 |
| **(40W Ecolux®)** | | | | | | | | | | | | | | |
| T12 | G13 | 40 | 48.0 | 80096 | F40C50/ECO | 30 | 20,000 | 2,250 | 1,870 | 5000K | 90 | Δ | 93117215 | LED11BDT8/G4/850 |
| | G13 | 40 | 48.0 | 80097 | F40DX/ECO | 30 | 20,000 | 2,050 | 1,740 | 6500K | 90 | Δ | 93117215 | LED11BDT8/G4/850 |
| **8' T12 Instant Start** | | | | | | | | | | | | | | |
| **(8' Instant Start Standard)** | | | | | | | | | | | | | | |
| T12 | Fa8 | 75 | 96.0 | 14652 | F96T12/DX | 15 | 12,000 | 4,300 | 3,870 | 6500K | 90 | | 93319020 | LED42BDT8/G8/Fa8/8SC/120-347 |
| **(8' Instant Start Watt-Miser® XL Extra-life)** | | | | | | | | | | | | | | |
| T12 | Fa8 | 60 | 96.0 | 68052 | F96T12/CW/C/WM | 15 | 12,000 | 3,600 | 2,900 | 4100K | 90 | | 93319020 | LED42BDT8/G8/Fa8/8SC/120-347 |
| | Fa8 | 60 | 96.0 | 66858 | F96T12XL/HL41/WM | 15 | 12,000 | 5,900 | 5,480 | 4100K | 80 | | 93319020 | LED42BDT8/G8/Fa8/8SC/120-347 |
| **T12 High Output (800mA) Rapid Start Recessed Double Contact** | | | | | | | | | | | | | | |
| **(4' High Output)** | | | | | | | | | | | | | | |
| T12 | R17D | 60 | 48.0 | 10773 | F48T12/CW/HO | 24 | 12,000 | 3,825 | 3,320 | 4100K | 60 | Δ | 93319032 | LED18BDT8/G4/R17d/8SC/120-347 |
| | R17D | 60 | 48.0 | 10778 | F48T12/D/HO | 24 | 12,000 | 3,400 | 2,960 | 6500K | 75 | Δ | 93319032 | LED18BDT8/G4/R17d/8SC/120-347 |
| **(5' High Output)** | | | | | | | | | | | | | | |
| T12 | R17D | 75 | 60.0 | 23075 | F60T12/CW/HO 15PK | 15 | 12,000 | 5,150 | 4,480 | 4100K | 60 | | 93319030 | LED24BDT8/G5/R17d/8SC/120-347 |
| | R17D | 75 | 60.0 | 23077 | F60T12/D/HO 15PK | 15 | 12,000 | 4,400 | 3,830 | 6500K | 75 | | 93319030 | LED24BDT8/G5/R17d/8SC/120-347 |
| **(6' High Output)** | | | | | | | | | | | | | | |
| T12 | R17D | 85 | 72.0 | 13697 | F72T12/CW/HO 15PK | 15 | 12,000 | 6,350 | 5,520 | 4100K | 60 | | 93319026 | LED30BDT8/G6/R17d/8SC/120-347 |
| | R17D | 85 | 72.0 | 13699 | F72T12/D/HO 15PK | 15 | 12,000 | 5,350 | 4,650 | 6500K | 75 | | 93319026 | LED30BDT8/G6/R17d/8SC/120-347 |
| **(7' High Output)** | | | | | | | | | | | | | | |
| T12 | R17D | 100 | 84.0 | 13766 | F84T12/CW/HO 15PK | 15 | 12,000 | 7,700 | 6,700 | 4100K | 60 | | 93319024 | LED35BDT8/G7/R17d/8SC/120-347 |
| | R17D | 100 | 84.0 | 13767 | F84T12/D/HO 15PK | 15 | 12,000 | 6,500 | 5,660 | 6500K | 75 | | 93319024 | LED35BDT8/G7/R17d/8SC/120-347 |
| **(8' High Output)** | | | | | | | | | | | | | | |
| T12 | R17D | 95 | 96.0 | 66862 | F96T12/HL41/HO/WM | 15 | 12,000 | 8,850 | 7,920 | 4100K | 77 | | 93319022 | LED42BDT8/G8/R17d/8SC/120-347 |

## **Cold Temperature** Lamps

| Bulb Shape | Base Type | Watts | Nominal Length (in.) | Order Code | Description | Carton Qty[1] | Rated Life (3hr/Start) | Initial Lumens | Mean Lumens | Color Temp | CRI | Notes | Type B LED Replacement Order Code | Type B LED Replacement Description |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **High Output (800mA) Recessed Double Contact** | | | | | | | | | | | | | | |
| T12 | R17D | 110 | 96.0 | 11918 | F96T12/CW/HO/CT | 15 | 12,000 | 8,900 | 7,740 | 4100K | 60 | | 93319022 | LED42BDT8/G8/R17d/8SC/120-347 |
| | R17D | 110 | 96.0 | 11919 | F96T12/D/HO/CT | 15 | 12,000 | 7,600 | 6,610 | 6500K | 75 | | 93319022 | LED42BDT8/G8/R17d/8SC/120-347 |

## **T9 Circline®** Lamps

| Bulb Shape | Base Type | Watts | Nominal Length (in.) | Order Code | Description | Carton Qty[1] | Rated Life (3hr/Start) | Initial Lumens | Mean Lumens | Color Temp. | CRI | Notes | Type B LED Replacement Order Code | Type B LED Replacement Description |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **T9 Circline® Lamps** | | | | | | | | | | | | | | |
| T9 | G10q | 22 | 8.25 | 33774 | FC8T9/CW | 12 | 12,000 | 1,100 | 825 | 4100K | 60 | | | |
| | G10q | 32 | 12.0 | 33890 | FC12T9/CW | 12 | 12,000 | 1,950 | 1,460 | 4100K | 60 | | | |

[1] Minimum order quantity = Carton Qty
Δ Impacted by 4' fluorescent state legislation, SKU not for sale in Vermont after 1/1/2024 due to state legislation; for more information please visit www.LED.com/lamplegislation
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## Regulation Readiness: Fluorescent Phase-Out

In an effort to regulate consumer products that contain mercury, state governments within the USA have passed legislation that will prohibit the sale and distribution of Linear and Compact Fluorescent lamps. The effective date of each state regulation is shown in the table below. This table will continue to evolve as new legislation is passed.

**Regulation Effective Date by Product Category**

| State | Product Category | | | | |
|---|---|---|---|---|---|
| | 4-Foot Linear Fluorescent | All Linear Fluorescent | Screw or Bayonet Based Compact Fluorescent | Pin Based Compact Fluorescent | Mercury Vapor High Intensity Discharge |
| Vermont | 1/1/2024 | | | | |
| California | | 1/1/2025 | 1/1/2024 | 1/1/2025 | |
| Colorado | | 1/1/2025 | 1/1/2024 | 1/1/2025 | |
| Oregon | | 1/1/2025 | 1/1/2024 | 1/1/2025 | |
| Rhode Island | | 1/1/2025 | 1/1/2024 | 1/1/2025 | |
| Hawaii | | 1/1/2026 | 1/1/2025 | 1/1/2026 | |
| Minnesota | | 1/1/2026 | 1/1/2025 | 1/1/2026 | 1/1/2025 |
| Maine | | 1/1/2026 | 1/1/2026 | 1/1/2026 | |
| Illinois | | 1/1/2027 | 1/1/2026 | 1/1/2027 | |
| Washington State | | 1/1/2029 | 1/1/2029 | 1/1/2029 | |

### Mercury in Fluorescent Lighting

Fluorescent technology was developed by General Electric in 1934. While the amount of mercury in each fluorescent lamp has significantly decreased over the past 90 years, a small amount is still required to produce light in all Discharge lamps. When electricity is applied to a fluorescent tube, mercury ions emit energy in the form of ultraviolet (UV) light. UV light is then converted into visible light by interacting with the phosphor coating on the inside of the glass tube. Mercury has electrical characteristics that cannot be matched by other materials and remains a key component of fluorescent lighting.


### Transitioning to LED Lighting

LED (Light Emitting Diode) lamps do not contain mercury, and Current offers a variety of LED lamp options to replace Linear & Compact Fluorescent lamps. The different Types of LED lamps are explained in the following pages. Suggested LED replacements are noted for fluorescent lamps in the tables in this document. These are basic recommendations, but suitability should be evaluated for each specific application where fluorescent lamps were used. For more information about the transition from fluorescent to LED, contact your Current sales representative.

**To learn more about Fluorescent Regulations and LED replacements, please visit www.LED.com/lamplegislation**

**High Intensity** Discharge lighting provides energy efficiency in a compact size for many commercial and industrial applications.

## **Reference Guide** | Bulb Identification




**DIA:** Diameter of bulb at widest point.


**MOL:** Maximum Overall Length including base or pins.

**LCL:** Distance between the center of the arc tube and the Light Center Length reference plane.


**Note:** Lamp drawings are not drawn to scale.
Be sure to check size and dimension information when identifying each lamp.

To convert inches to millimeters, multiply the dimension (in inches) by 25.4 (i.e. 1.5" x 25.4 = 38.1 mm).


## **Filament** Identification






## **Base Identification** (not drawn to scale)




**Lamp Drawings** (not drawn to scale)









**Lamp Drawings** (Conti.) (not drawn to scale)




BD18
Mog




ED23.5
Mog



ED18
Mog



ED23.5
Mog




B17
Med

BD18
Mog


BD23.5
Mog

E25
Mog

ED28
Mog

ED37
Mog

T15
Mog



ED23.5
Mog

ED28
Mog

ED37
Mog

## Base Identification (not drawn to scale)




## Catalog Logic:

**Color Rendering Index (CRI or R):** An indication of the ability of the lamp to render object colors in a normal natural way. The higher the number (0-100), the better the color appearance

**Warning Notice:** Warning and Caution notices for High Intensity Discharge lamps. See pages 76 – 81

**Color Temperature – Kelvins (K):** A measure of the visual "warmth" or "coolness" of the light from the lamp. The higher the value, the whiter or "cooler" the light appears.

**Means Lumens:** Lamp light output at 40% of rated lamp life or 8K hours for lamps exceeding 20K hours life.

**LED Replacement:** Current offers a wide range of LED replacement lamps. The LED lamp models are provided as general guidance. Often, there will be more than one LED Lamp that may be used to replace a Traditional lamp. For Traditional lamps that operated off a ballast, the ballast bypass (UL Type B) LED option is given unless otherwise noted. The application should be considered when selecting an LED replacement lamp. Sometimes, Traditional lamps do not have a suitable LED replacement due to special application considerations, such as very high heat. Contact Current for additional guidance if the appropriate LED solution is unclear.

**Bulb Shape:** followed by its size (the maximum diameter of the bulb expressed in eighths of an inch).

**Watts:** Energy used (as defined by FTC Lamp Label Rules). To estimate energy consumption (kWh), multiply watts x hours of use and divide by 1000.

**Description:** Lamp Model Description

**Rated Life (hours):** Life (as defined by FTC Lamp Label Rules) is rated life in hours.

**LET (Lamp Enclosure Type):** Describes fixture requirements for this lamp

**LCL (in):** Distance between the center of the filament and the Light Center Length reference plane, in inches.

**CBCP (Center beam Candlepower):** For reflector-type lamps, Center Beam Candlepower is the intensity (candelas) at the center of maximum intensity of the beam. Used only for ConstantColor® CMH® Metal Halide Lamps

**Initial Lumens:** Lamp light output after the initial 100 hours of operation.

**Base:** The type of base

**OP (Operating Position)**

**MOL (in):** Maximum Overall Length in inches

**Order Code:** Use the order code when ordering to ensure that you receive the exact product you require.

**Carton Quantity:** Number of lamps packed in a carton

**ANSI Ballast Type:** Ballast type used to operate lamp

| Bulb Shape | Base Type | LET | OP | Watts | MOL (in) | LCL (in) | Order Code | Description | ANSI Ballast Type | Carton Qty | CBCP | Rated Life (hrs*) | Initial Lumens | Mean Lumens | Color Temp. | CRI | Warning Notice | Type B LED Replacement Order Code | Type B LED Replacement Description |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CMH® MR16/MR17 | | | | | | | | | | | | | | | | | | | |
| MR16 | GX10 | O | U | 20 | 2.28 | | 85101 | CMH20MR16/830/SP | C156/M156 | 12 | 9,000 | 12,000 | 1,000 | | 3000K | 81 | 5 | | |

## CMH20MR16/830/SP

- CMH20 — Identifies as CMH® lamp.
- MR16 — Identifies the lamp's wattage
- 830 — Identifies the bulb shape
- SP — Additional Information
- 830 — Color temp. and CRI

Lamp Contains Mercury.
Manage in Accord with Disposal Laws.
See **www.lamprecycle.org** or **1-800-327-0097**

## Multi-Vapor® Metal Halide Lamps

| Bulb Shape | Base Type | LET | OP | Watts | MOL (In) | LCL (In) | Order Code | Description | ANSI Ballast Type | Carton Qty[1] | Rated Life (hrs*) | Initial Lumens | Mean Lumens | Color Temp. | CRI | Warning Notice | Type B LED Replacement Order Code | Type B LED Replacement Description |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **50 Watts - Enclosed Rated** | | | | | | | | | | | | | | | | | | |
| BD17 | E26 | E | U | 50 | 5.43 | 3.43 | 10361 | MXR50/U/MED | M110 | 6 | 10,000 | 3,200 | 2,100 | 3700K | 60 | 1, 3 | 27729 | LED21ED17/740 |
| **70 Watts - Enclosed Rated** | | | | | | | | | | | | | | | | | | |
| BD17 | E26 | E | U | 70 | 5.43 | 3.43 | 22158 | MXR70/U/MED | M98 | 6 | 12,000 | 5,500 | 3,500 | 3500K | 55 | 1, 3 | 27729 | LED21ED17/740 |
| BD17 | E26 | E | U | 70 | 5.43 | 3.43 | 12590 | MVR70/U/MED | M98 | 6 | 12000 | 5,500 | 3,000 | 4000K | 65 | 1, 3 | 27729 | LED21ED17/740 |
| **70 Watts - Open Rated** | | | | | | | | | | | | | | | | | | |
| ED17 | E26 | O | U | 70 | 5.43 | 3.43 | 12377 | MXR70/U/MED/O | M98 | 6 | 15,000 | 5,500 | 3,500 | 3200K | 70 | 1, 3 | 93303384 | LED/LC/ED17/7SC |
| **100 Watts - Enclosed Rated** | | | | | | | | | | | | | | | | | | |
| BD17 | E26 | E | U | 100 | 5.43 | 3.43 | 18680 | MXR100/U/MED | M90 | 6 | 15,000 | 9,000 | 6,200 | 3200K | 65 | 1, 3 | 93112114 | LED35ED17/730 |
| BD17 | E26 | E | U | 100 | 5.43 | 3.43 | 12652 | MVR100/U/MED | M90 | 6 | 15,000 | 9,500 | 5,800 | 4000K | 70 | 1, 3 | 27602 | LED35ED17/740 |
| **100 Watts - Open Rated** | | | | | | | | | | | | | | | | | | |
| ED17 | E26 | O | U | 100 | 5.43 | 3.43 | 12381 | MXR100/U/MED/O | M90 | 6 | 15,000 | 9,000 | 6,200 | 3200K | 70 | 1, 3 | 93112114 | LED35ED17/730 |
| **150 Watts - Enclosed Rated** | | | | | | | | | | | | | | | | | | |
| BD17 | E26 | E | U | 150 | 5.43 | 3.43 | 12598 | MVR150/U/MED | M102 | 6 | 15,000 | 14,000 | 10,500 | 4300K | 65 | 1, 3 | 93303384 | LED/LC/ED17/7SC |
| **150 Watts - Open Rated** | | | | | | | | | | | | | | | | | | |
| ED17 | E26 | O | U | 150 | 5.43 | 3.43 | 45683 | MXR150/U/MED/O | M102 | 6 | 15,000 | 12,500 | 8,600 | 3500K | 70 | 1, 3 | 93303384 | LED/LC/ED17/7SC |
| **175 Watts - Enclosed Rated** | | | | | | | | | | | | | | | | | | |
| BD17 | E26 | E | U | 175 | 5.75 | 3.43 | 18902 | MVR175/U/MED | M57 | 6 | 6,000H/ 10,000V | 11,700H/ 14,000V | 7,400H/ 8,800V | 4000K | 60 | 1, 2 | 93148082 | LED45ED17/740 |
| ED28 | E39 | E | U | 175 | 8.25 | 5.00 | 47760 | MVR175/U | M57 | 12 | 6,000H/ 10,000V | 11,700H/ 13,600V | 7,900H/ 8,800V | 4000K | 55 | 1, 2 | 22679 | LED50ED23.5/740 |
| ED28 | E39 | E | U | 175 | 8.25 | 5.00 | 47761 | MVR175/C/U | M57 | 12 | 6,000H/ 10,000V | 11,900H/ 12,900V | 7,900H/ 8,400V | 3900K | 55 | 1, 2 | 22679 | LED50ED23.5/740 |
| **250 Watts - Enclosed Rated** | | | | | | | | | | | | | | | | | | |
| ED28 | E39 | E | U | 250 | 8.25 | 5.00 | 42729 | MVR250/U | M58 | 12 | 6,000H/ 10,000V | 19,100H/ 20,800V | 12,400H/ 13,500V | 4200K | 60 | 1, 2 | 22635 | LED80ED23.5/740 |
| **250 Watts - Enclosed Rated, PulseArc** | | | | | | | | | | | | | | | | | | |
| ED28 | E39 | E | U | 250 | 8.25 | 5.00 | 78665 | MVR250/U/PA | M138/M153 | 12 | 12,000H/ 15,000V | 18,600H/ 22,400V | 12,000H/ 14,000V | 3900K | 60 | 1, 3 | 22635 | LED80ED23.5/740 |
| **320 Watts - Enclosed Rated, PulseArc** | | | | | | | | | | | | | | | | | | |
| ED28 | E39 | E | VBU | 320 | 8.25 | 5.00 | 27501 | MVR320/VBU/HO/PA | M132/M154 | 12 | 20,000 | 31,000 | 18,000 | 4000K | 60 | 1, 3 | 22622 | LED115ED28/740 |
| **320 Watts - Open Rated** | | | | | | | | | | | | | | | | | | |
| ED28 | EX39 | O | VBU | 320 | 8.25 | 5.00 | 19609 | MPR320/C/PA/ED28 | M132/M154 | 12 | 20,000 | 30,600 | 22,500 | 3700K | 70 | 1, 3 | 22622 | LED115ED28/740 |
| **400 Watts - Enclosed Rated** | | | | | | | | | | | | | | | | | | |
| ED28 | E39 | E | U | 400 | 8.25 | 5.00 | 18904 | MVR400/U/ED28 | M59 | 12 | 15,000H/ 20,000V | 33,100H/ 38,000V | 22,100H/ 23,500V | 4000K | 60 | 1, 2 | 22611 | LED150ED28/740 |
| **400 Watts - Enclosed Rated, PulseArc** | | | | | | | | | | | | | | | | | | |
| ED37 | E39 | E | U | 400 | 11.50 | 7.00 | 78666 | MVR400/U/PA | M135/M155 | 6 | 15,000H/ 20,000V | 31,200H/ 39,400V | 18,000H/ 22,000V | 4000K | 60 | 1, 3 | 22611 | LED150ED28/740 |
| ED28 | E39 | E | VBU | 400 | 8.25 | 5.00 | 46271 | MVR400/VBUED28PA | M135/M155 | 12 | 20,000 | 44,000 | 28,500 | 4000K | 65 | 1, 3 | 22611 | LED150ED28/740 |
| ED28 | E39 | E | HOR | 400 | 8.25 | 5.00 | 72885 | MVR400/HOR/ED28/PA | M135/M155 | 12 | 20,000 | 38,000 | 21,400 | 4100K | 65 | 1, 3 | 22611 | LED150ED28/740 |
| **400 Watts - Open Rated** | | | | | | | | | | | | | | | | | | |
| ED37 | EX39 | O | VBU | 400 | 11.50 | 7.00 | 46273 | MPR400/VBU/XHOPA | M135/M155 | 6 | 20,000 | 42,000 | 29,500 | 4000K | 65 | 1, 3 | 22611 | LED150ED28/740 |
| ED37 | EX39 | O | VBU | 400 | 11.50 | 7.00 | 18708 | MPR400/VBU/HO/O | M59 | 6 | 20,000 | 40,000 | 36,000 | 3400K | 65 | 1, 2 | 93311586 | LED/LC/ED37/740 |
| **1000 Watts - Enclosed Rated** | | | | | | | | | | | | | | | | | | |
| BT37 | E39 | E | U | 1000 | 11.50 | 7.00 | 18205 | MVR1000/U/BT37 | M47 | 6 | 9,000H/ 12,000V | 105,000H/ 115,000V | 82,000H/ 90,000V | 3700K | 65 | 1, 3 | 93311586 | LED/LC/ED37/740 |
| **1000 Watts - Open Rated** | | | | | | | | | | | | | | | | | | |
| BT56 | EX39 | O | VBU | 1000 | 15.37 | 9.50 | 41433 | MPR1000/VBU/HO/O | M47 | 6 | 12,000 | 110,000 | 88,500 | 3500K | 65 | 1, 3 | 93096445 | LED450BT56/740 |
| **1500 Watts - Enclosed Rated** | | | | | | | | | | | | | | | | | | |
| BT56 | E39 | E | U | 1500 | 15.37 | 9.50 | 47326 | MVR1500/U/SPORTS | M48 | 6 | 3,000 | 162,000H/ 170,000V | 137,000H/ 153,000V | 4000K | 65 | 1, 3 | 93303389 | LED470BT56/740 |

[1] Minimum order quantity = Carton Qty
Please note Current lamps are not for sale for use in Yukon Territory in Canada

## Constant Color CMH® Metal Halide Lamps

| Bulb Shape | Base Type | LET | OP | Watts | MOL (In) | LCL (In) | Order Code | Description | ANSI Ballast Type | Carton Qty[1] | CBCP | Rated Life (hrs*) | Initial Lumens | Mean Lumens | Color Temp. | CRI | Warning Notice | LED Replacement Order Code | LED Replacement Description |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **CMH® MR16/MR17** | | | | | | | | | | | | | | | | | | | |
| MR16 | GX10 | O | U | 20 | 2.28 | | 85101 | CMH20MR16/830/SP | C156/M156 | 12 | 9,000 | 12,000 | 1,000 | | 3000K | 81 | 4 | | |
| | GX10 | O | U | 20 | 2.28 | | 85110 | CMH20MR16/830/FL | C156/M156 | 12 | 2,900 | 12,000 | 1,000 | | 3000K | 81 | 4 | | |
| | GX10 | O | U | 39 | 2.28 | | 71489 | CMH39MR16/930/FL | C130/M130 | 12 | 5,500 | 10,000 | 2,200 | | 3000K | 90 | 4 | | |
| **CMH® PAR** | | | | | | | | | | | | | | | | | | | |
| PAR30L | E26 | O | U | 39 | 4.75 | | 42067 | CMH39PAR30L/FL25 | C130/M130 | 6 | 11,000 | 10,000 | 2,400 | | 3000K | 81 | 4 | 75091 | LED18P30LW83025 |
| **CMH® Single-Ended G12** | | | | | | | | | | | | | | | | | | | |
| T6 | G12 | E | U | 39 | 3.56 | 2.18 | 20153 | CMH39TUVCU830G12 | C130/M130 | 12 | | 15,000 | 3,400 | 2,300 | 3000K | 84 | 4 | | |
| | G12 | E | U | 70 | 3.56 | 2.18 | 20016 | CMH70TU/830/G12 | C139/M139 | 12 | | 15,000 | 6,200 | 4,700 | 3000K | 83 | 4 | | |
| **CMH® GU6.5** | | | | | | | | | | | | | | | | | | | |
| T4 | GU6.5 | E | U | 20 | 2.05 | 1.18 | 85086 | CMH20T/U830GU6.5 | C156/M156 | 12 | | 12,000 | 1,615 | 1,066 | 3000K | 81 | 4 | | |
| | GU6.5 | E | U | 39 | 2.05 | 1.18 | 71484 | CMH39T/U930GU6.5 | C130/M130 | 12 | | 10,000 | 3,400 | 2,300 | 3000K | 88 | 4 | | |
| **CMH® Mini's** | | | | | | | | | | | | | | | | | | | |
| T4.5 | G8.5 | E | U | 20 | 3.37 | 2.00 | 92696 | CMH20TCU830/G8.5 | C156/M156 | 12 | | 12,000 | 1,650 | 1,090 | 3000K | 81 | 4 | | |
| | G8.5 | E | U | 39 | 3.37 | 2.00 | 90352 | CMH39TCU830/G8.5 | C130/M130 | 12 | | 16,500 | 3,400 | 2,300 | 3000K | 84 | 4 | | |
| | G8.5 | E | U | 70 | 3.37 | 2.00 | 92585 | CMH70TCU830G8.5 | C139/M139 | 12 | | 15,000 | 6,200 | 4,400 | 3000K | 83 | 4 | | |

## High Pressure Sodium Lamps

| Bulb Shape | Base Type | LET | OP | Watts | MOL (In) | LCL (In) | Order Code | Description | ANSI Ballast Type | Carton Qty[1] | Rated Life (hrs*) | Initial Lumens | Mean Lumens | Color Temp. | CRI | Warning Notice | Type B LED Replacement Order Code | Type B LED Replacement Description |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **70-1000 Watts** | | | | | | | | | | | | | | | | | | |
| B17 | E26 | O | U | 70 | 5.43 | 3.43 | 11339 | LU70/MED/ECO | S62 | 6 | 24,000+ | 6,400 | 5,450 | 1900K | 22 | 5 | 93112114 | LED35ED17/730 |
| ED23.5 | E39 | O | U | 70 | 7.75 | 5.00 | 85368 | LU70/H/ECO | S62 | 12 | 24,000+ | 6,400 | 5,450 | 1900K | 22 | 5 | 93303384 | LED/LC/ED17/7SC |
| B17 | E26 | O | U | 100 | 5.50 | 3.43 | 13250 | LU100/MED/ECO | S54 | 6 | 24,000+ | 9,500 | 8,550 | 2000K | 22 | 5 | 93303384 | LED/LC/ED17/7SC |
| ED23.5 | E39 | O | U | 100 | 7.75 | 5.00 | 85369 | LU100/H/ECO | S54 | 12 | 24,000+ | 9,500 | 8,550 | 2000K | 22 | 5 | 93312106 | LED/LC/ED23.5/7SC |
| B17 | E26 | O | U | 150 | 5.75 | 3.50 | 13252 | LU150/MED/ECO | S55 | 6 | 24,000+ | 16,000 | 14,400 | 2000K | 22 | 5 | 93303384 | LED/LC/ED17/7SC |
| ED23.5 | E39 | O | U | 150 | 7.75 | 5.00 | 85371 | LU150/55/H/ECO | S55 | 12 | 24,000+ | 16,000 | 14,400 | 2000K | 22 | 5 | 93312106 | LED/LC/ED23.5/7SC |
| ED18 | E39 | O | U | 200 | 9.75 | 5.75 | 85372 | LU200/H/ECO | S66 | 12 | 24,000+ | 22,000 | 19,800 | 2100K | 22 | 5 | 93320018 | LED120ED18/730/277-480 |
| | E39 | O | U | 250 | 9.75 | 5.75 | 85377 | LU250/H/ECO | S50 | 12 | 24,000+ | 28,000 | 25,200 | 2100K | 22 | 5 | 93320018 | LED120ED18/730/277-480 |
| | E39 | O | U | 400 | 9.75 | 5.75 | 85379 | LU400/H/ECO | S51 | 12 | 24,000+ | 51,000 | 45,000 | 2100K | 22 | 5 | 93312096 | LED180ED18/730 |
| E25 | E39 | O | U | 1000 | 15.06 | 8.75 | 44058 | LU1000/ECO | S52 | 6 | 24000+ | 130,000 | 117,000 | 2100K | 22 | 6 | | |

[1] Minimum order quantity = Carton Qty
Please note Current lamps are not for sale for use in Yukon Territory in Canada

1 WARNING **NOTICE NO. 1:**

## ⚠ WARNING

**Risk of electric shock**
- Turn power off before inspection, installation, or removal
- Do not use where directly exposed to water or outdoors without an enclosed fixture

**Risk of fire**
- Keep combustible materials away from lamp
- Use in fixture rated for this product

**A damaged lamp emits UV radiation which may cause eye/skin injury**
- Turn power off if glass bulb is broken. Remove and dispose of lamp.

Unexpected lamp rupture may cause injury, fire, or property damage
- Turn lamp off at least once for 15 minutes per week.

FAILURE TO COMPLY INCREASES THE RISK OF RUPTURE.
- Do not use beyond rated life. Beyond rated life, light output diminishes while energy consumption and risk of lamp rupture increases.
- Do not use lamp if outer glass is scratched or broken
- Do not use where directly exposed to water or outdoors without an enclosed fixture
- Lamps with E-rated ANSI codes must be operated in enclosed fixtures -- See Instructions
- Do not store flammable materials near/below lamp in open fixture
- Use only properly rated ballast
- Do not exceed rated voltage
- Do not turn on lamp until fully installed
- Operate lamp only in specified position
- If used on a dimming system, see instructions.

## INSTRUCTIONS

**LAMP OPERATING CHARACTERISTICS**
This is a discharge lamp and requires some time to restart and come to full brightness after a power interruption.

**RELAMP FIXTURES AT OR BEFORE THE END OF RATED LIFE.**
Beyond rated life, light output diminishes while energy consumption and risk of lamp rupture increases.

**SPECIFIED OPERATING POSITIONS**
**VBU - Base up ± 15˚** **VBD - Base down ± 15˚**
**HOR - Horizontal ± 15˚** **HOR/PA - Horizontal ± 75˚**
**U - Universal**

Match ANSI code of lamp to code on ballast or luminaire. Lamps are rated for either open or enclosed fixtures.

Note that lamps with S-rated ANSI codes operated in vertical position only (Base Up or Base Down), ± 15 degrees, can be used in an open fixture.

Use in luminaire which comply with UL1598 or IEC 60598. When used, fixture lens/diffuser material must be able to contain fragments of hot quartz or glass (up to 1100˚C).

Electrically insulate any metal to bulb support in luminaire to avoid decomposition of glass.

For total load, add auxiliary watts to lamp watts.

Not for use with lampholders that have stainless steel center contacts to avoid lamp or lampholder damage due to arcing. (360-1000W only)

**FOR USE ON DIMMING SYSTEMS**
Contact your local Current sales representative

## ⚠ CAUTION

**Risk of burn**
- Allow lamp to cool before handling
- Do not turn on lamp until fully installed

**Lamp may shatter and cause injury if broken**
- Wear safety glasses and gloves when handling lamp
- Do not use lamp if outer glass is scratched or broken
- Dispose of lamp in a closed container
- Do not use excessive force when installing lamp
- **CAUTION**: Do not stare at light source. May be harmful to the eyes. Not applicable to diffuse coated bulbs.

## Hg LAMP CONTAINS MERCURY

Manage in Accord with Disposal Laws.
See **www.lamprecycle.org** or **1-800-327-0097**

***R*** **WARNING:** This lamp can cause serious skin burn and eye inflammation from shortwave ultraviolet radiation if outer envelope of the lamp is broken or punctured. Do not use where people will remain for more than a few minutes unless adequate shielding or other safety precautions are used. Lamps that will automatically extinguish when the outer envelope is broken or punctured are commercially available. This lamp certified to comply with FDA radiation performance standards, 21 CFR Subchapter J. USA: 21 CFR 1040.30 Canada: C.R.C., c. 1370

2 WARNING **NOTICE NO. 2:** Lamp contains Radioactive Material Thorium

3 WARNING **NOTICE NO. 3:** Lamp contains Radioactive Materials Thorium and Kr-85

## 4 WARNING **NOTICE NO. 4:**

### ⚠ WARNING

**Risk of electric shock**
- Turn power off before inspection, installation, or removal
- Do not use where directly exposed to water or outdoors without an enclosed fixture

**Risk of fire**
- Keep combustible materials away from lamp
- Use in fixture rated for this product
- Use fused or thermally protected ballast - see instructions

**Unexpected lamp rupture may cause injury, fire, or property damage**
- Do not exceed rated voltage
- Do not use where directly exposed to water or outdoors without an enclosed fixture
- Do not use lamp if outer glass is scratched or broken
- Use only properly rated ballast
- Do not store flammable materials near/below lamp
- Do not use beyond rated life
- Do not turn on lamp until fully installed

### ⚠ CAUTION

**Risk of burn**
- Allow lamp to cool before handling
- Do not turn on lamp until fully installed

**Lamp may shatter and cause injury if broken**
- Wear safety glasses and gloves when handling lamp
- Do not use lamp if outer glass is scratched or broken
- Dispose of lamp in a closed container
- Do not use excessive force when installing lamp

### INSTRUCTIONS

**LAMP OPERATING CHARACTERISTICS**
This is a discharge lamp and requires some time to restart and come to full brightness after a power interruption.

For total load, add auxiliary watts to lamp watts

Relamp fixtures at or before the end of rated life. Beyond rated life, light output diminishes while energy consumption increases.

If power supply dips or is interrupted, lamps may extinguish and not restart. Turn off power supply for 10-15 minutes and allow lamp to fully cool. Lamps will restart when power is restored

Use on ballasts or systems that are either resistant to or will shut off in event of rectification

Lamp may be operated in any position.

UV Control is a quartz material that effectively cuts UVB and UVC radiation.

All MR16 and 20W PAR use only on electronic ballast.

Lamps designated as CMH70/PAR30 do not require thermally protected ballasts

### Hg LAMP CONTAINS MERCURY

Manage in Accord with Disposal Laws.
See **www.lamprecycle.org** or **1-800-327-0097**

This product is in conformity with performance standards for high intensity mercury vapor lamps products under 21 CFR 1040, except with respect to those characteristics authorized by Variance Number FDA-2021-V-0995 effective September 27, 2021.

**Arc tube fill gas contains Radioactive Material Kr-85**

## 5 WARNING **NOTICE NO. 5:**

### ⚠ WARNING

**Risk of electric shock**
- Turn power off before inspection, installation, or removal
- Do not use where directly exposed to water or outdoors without an enclosed fixture

**Risk of fire**
- Keep combustible materials away from lamp
- Use in fixture rated for this product

**Contains sodium – chemical burn risk**
- Avoid skin contact with broken pieces

**Unexpected lamp rupture may cause injury, fire, or property damage**
- Do not exceed rated voltage
- Do not use where directly exposed to water or outdoors without an enclosed fixture
- Do not use lamp if outer glass is scratched or broken
- Use only properly rated ballast
- Do not store flammable materials near/below lamp
- Do not turn on lamp until fully installed

### ⚠ CAUTION

**Risk of burn**
- Allow lamp to cool before handling
- Do not turn on lamp until fully installed

**Lamp may shatter and cause injury if broken**
- Wear safety glasses and gloves when handling lamp
- Do not use lamp if outer glass is scratched or broken
- Dispose of lamp in a closed container
- Do not use excessive force when installing lamp

### INSTRUCTIONS

**LAMP OPERATING CHARACTERISTICS**
This is a discharge lamp and requires some time to restart and come to full brightness after a power interruption.

HPS lamps may be operated in any burn position.

Match ANSI code of lamp to code on ballast or luminaire.

Use in luminaire which comply with UL1598 or IEC 60598.

Electrically insulate any metal to bulb support in luminaire to avoid decomposition of glass.

For total load, add auxiliary watts to lamp watts.

Not for use with lampholders that have stainless steel center contacts to avoid lamp or lampholder damage due to arcing. (400W only)

**FOR USE ON DIMMING SYSTEMS**
Contact your local Current sales representative

### Hg LAMP CONTAINS MERCURY

Manage in Accord with Disposal Laws.
See **www.lamprecycle.org** or **1-800-327-0097**

## 6 WARNING **NOTICE NO. 6:**

### ⚠ WARNING

**Risk of electric shock**
- Turn power off before inspection, installation, or removal
- Do not use where directly exposed to water or outdoors without an enclosed fixture

**Risk of fire**
- Keep combustible materials away from lamp
- Use in fixture rated for this product - see instructions

**Contains sodium – chemical burn risk**
- Avoid skin contact with broken pieces

**Unexpected lamp rupture may cause injury, fire, or property damage**
- Do not exceed rated voltage
- Do not use where directly exposed to water or outdoors without an enclosed fixture
- Do not use lamp if outer glass is scratched or broken
- Use only properly rated ballast
- Do not store flammable materials near/below lamp
- Do not turn on lamp until fully installed

### ⚠ CAUTION

**Risk of burn**
- Allow lamp to cool before handling
- Do not turn on lamp until fully installed

**Lamp may shatter and cause injury if broken**
- Wear safety glasses and gloves when handling lamp
- Do not use lamp if outer glass is scratched or broken
- Dispose of lamp in a closed container
- Do not use excessive force when installing lamp

### INSTRUCTIONS

**LAMP OPERATING CHARACTERISTICS**
This is a discharge lamp and requires some time to restart and come to full brightness after a power interruption.

Match ANSI code of lamp to code on ballast or luminaire. Or use suitable ballast and ignitor that complies with IEC 60923 and IEC 60927.

Use in luminaire which comply with UL1598 or IEC 60598.

Fixtures must have a specially designed mogul base lamp holder and must support the end of the lamp.

In vertical base up applications with no vibration and/or shock, a tempered glass enclosed fixture may be used in place of the lamp end support.

Electrically insulate any metal to bulb support in luminaire to avoid decomposition of glass.

For total load, add auxiliary watts to lamp watts.

Not for use with lampholders that have stainless steel center contacts to avoid lamp or lampholder damage due to arcing.


**FOR USE ON DIMMING SYSTEMS**
Contact your local Current sales representative

### Hg LAMP CONTAINS MERCURY

Manage in Accord with Disposal Laws.
See **www.lamprecycle.org** or **1-800-327-0097**

**Compact Fluorescent lighting** offers high light output and long life for all your commercial plug-in applications.

## **Reference Guide** | Bulb Identification





**NOMINAL LENGTH:**
Overall length including base or pins.


**Note:** Lamp drawings are not drawn to scale. Be sure to check size and dimension information when identifying each lamp.


To convert inches to millimeters, multiply the dimension (in inches) by 25.4 (i.e. 1.5" x 25.4 = 38.1 mm).


## **Lamp Drawings** (not drawn to scale)





## **Base Identification** (not drawn to scale)







## Catalog Logic:

The following terms and descriptions can help you when checking Compact Fluorescent lamp specifications and when ordering products. Within each product line, lamps are divided into families and listed by base and wattage.

**Base:** The type of base

**Watts:** Energy used (as defined by FTC Lamp Label Rules). To estimate energy consumption (kWh), multiply watts x hours of use and divide by 1000.

**Nominal Length (in):** Lamp length including base and/or pins.

**Order Code:** Use the order code when ordering to ensure that you receive the exact product you require.

**Description:** Lamp Model Description

**Carton Quantity:** Number of lamps packed in a carton

**Rated Life (hours):** Life (as defined by FTC Lamp Label Rules) is rated life in hours.

**Initial Lumens:** Lamp light output after the initial 100 hours of operation.


**Means Lumens:** Lamp light output at 40% of rated lamp life or 8K hours for lamps exceeding 20K hours life.

**Color Temperature – Kelvins (K):** A measure of the visual "warmth" or "coolness" of the light from the lamp. The higher the value, the whiter or "cooler" the light appears.

**Color Rendering Index (CRI or R):** An indication of the ability of the lamp to render object colors in a normal natural way. The higher the number (0-100), the better the color appearance

**LED Replacement:** Current offers a wide range of LED replacement lamps. The LED lamp models are provided as general guidance. Often, there will be more than one LED Lamp that may be used to replace a Traditional lamp. For Traditional lamps that operated off a ballast, the ballast bypass (UL Type B) LED option is given unless otherwise noted. The application should be considered when selecting an LED replacement lamp. Sometimes, Traditional lamps do not have a suitable LED replacement due to special application considerations, such as very high heat. Contact Current for additional guidance if the appropriate LED solution is unclear.

| | | | | | | | | | | | LED Replacement | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Base Type | Watts | Nominal Length (in.) | Order Code | Description | Car-ton Qty | Rated Life (hrs.) | Initial Lumens | Mean Lumens | Color Temp. | CRI | Order Code | Description |
| 2-Pin Low Wattage Biax® | | | | | | | | | | | | |
| GX23 | 13 | 7.0 | 97573 | F13BX/827/ECO | 100 | 10,000 | 825 | 710 | 2700K | 82 | 91404 | LED5GX23/827 (Type A) |




Lamp Contains Mercury.
Manage in Accord with Disposal Laws.
See **www.lamprecycle.org** or **1-800-327-0097**

****Fluorescent Phase-Out Regulations****: Several US states have enacted legislation that prohibit/will prohibit the sale of Linear and Compact Fluorescent Lamps within their state. For more information including effective dates, please visit www.LED.com/lamplegislation

## Plug-In Lamps


| Base Type | Watts | Nominal Length (in.) | Order Code | Description | Carton Qty[1] | Rated Life (hrs.) | Initial Lumens | Mean Lumens | Color Temp. | CRI | Type B LED Replacement Order Code | Type B LED Replacement Description |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **2-Pin Low Wattage Biax®** | | | | | | | | | | | | |
| GX23 | 13 | 7.0 | 97573 | F13BX/827/ECO | 10 | 10,000 | 825 | 710 | 2700K | 82 | 93312495 | LED5BGX23/827 |
| GX23 | 13 | 7.0 | 97569 | F13BX/835/ECO | 10 | 10,000 | 825 | 710 | 3500K | 82 | 93312507 | LED5BGX23/835 |
| GX23 | 13 | 7.0 | 97571 | F13BX/841/ECO | 10 | 10,000 | 825 | 710 | 4100K | 82 | 93312513 | LED5BGX23/840 |
| **4-Pin High Lumen Biax®** | | | | | | | | | | | | |
| 2G11 | 18 | 9.0 | 16053 | F18BX/SPX35 10PK | 10 | 10,000 | 1,200 | 1,080 | 3500K | 82 | 93318810 | LED9B2G11/8SC |
| 2G11 | 18 | 9.0 | 16940 | F18BX/SPX41 10PK | 10 | 10,000 | 1,200 | 1,080 | 4100K | 82 | 93318810 | LED9B2G11/8SC |
| 2G11 | 39 | 16.5 | 28393 | F39BXSPX35RS10PK | 10 | 12,000 | 2,850 | 2,565 | 3500K | 82 | 93318822 | LED16B2G11/8SC |
| 2G11 | 39 | 16.5 | 28458 | F39BXSPX41RS10PK | 10 | 12,000 | 2,850 | 2,565 | 4100K | 82 | 93318822 | LED16B2G11/8SC |
| 2G11 | 40 | 22.5 | 16953 | F4030BXSPX30 10P | 10 | 20,000 | 3,150 | 2,840 | 3000K | 82 | 93318828 | LED17B2G11/8SC |
| 2G11 | 40 | 22.5 | 16648 | F40/30BX/SPX35 | 10 | 20,000 | 3,150 | 2,840 | 3500K | 82 | 93318828 | LED17B2G11/8SC |
| 2G11 | 40 | 22.5 | 16954 | F40/30BX/SPX41 | 10 | 20,000 | 3,150 | 2,840 | 4100K | 82 | 93318828 | LED17B2G11/8SC |
| 2G11 | 25 | 21.5 | 75400 | F40/25BX835/IS/WM | 10 | 20,000 | 2,600 | 2,400 | 3500K | 82 | 93318828 | LED17B2G11/8SC |
| 2G11 | 55 | 20.7 | 31952 | F55BX/835 | 25 | 20,000 | 4,800 | 4,080 | 3500K | 82 | | |
| 2G11 | 55 | 20.7 | 31953 | F55BX/840 | 25 | 20,000 | 4,800 | 4,080 | 4100K | 82 | | |
| **2-Pin Double Biax®** | | | | | | | | | | | | |
| GX23-2 | 13 | 4.7 | 97586 | F13DBX23/827/ECO | 10 | 12,000 | 810 | 685 | 2700K | 82 | 93312531 | LED8BGX23-2-O/827 |
| GX23-2 | 13 | 4.7 | 97588 | F13DBX23/835/ECO | 10 | 12,000 | 810 | 685 | 3500K | 82 | 93312543 | LED8BGX23-2-O/835 |
| GX23-2 | 13 | 4.7 | 97589 | F13DBX23/841/ECO | 10 | 12,000 | 810 | 685 | 4100K | 82 | 93312549 | LED8BGX23-2-O/840 |
| G24d-2 | 18 | 6.1 | 97577 | F18DBX/827/ECO | 10 | 12,000 | 1,250 | 980 | 2700K | 82 | Vertical: 93300088<br>Horizontal: 93300087 | LED11BG24-V/8SC/120-347-4PK<br>LED11BG24-H/8SC/120-347-4PK |
| G24d-2 | 18 | 6.1 | 97579 | F18DBX/835/ECO | 10 | 12,000 | 1,250 | 980 | 3500K | 82 | Vertical: 93300088<br>Horizontal: 93300087 | LED11BG24-V/8SC/120-347-4PK<br>LED11BG24-H/8SC/120-347-4PK |
| G24d-2 | 18 | 6.1 | 97580 | F18DBX/841/ECO | 10 | 12,000 | 1,250 | 980 | 4100K | 82 | Vertical: 93300088<br>Horizontal: 93300087 | LED11BG24-V/8SC/120-347-4PK<br>LED11BG24-H/8SC/120-347-4PK |
| G24d-3 | 26 | 6.7 | 97606 | F26DBX/827/ECO | 10 | 12,000 | 1,710 | 1,460 | 2700K | 82 | Vertical: 93300088<br>Horizontal: 93300087 | LED11BG24-V/8SC/120-347-4PK<br>LED11BG24-H/8SC/120-347-4PK |
| G24d-3 | 26 | 6.7 | 97608 | F26DBX/835/ECO | 10 | 12,000 | 1,710 | 1,460 | 3500K | 82 | Vertical: 93300088<br>Horizontal: 93300087 | LED11BG24-V/8SC/120-347-4PK<br>LED11BG24-H/8SC/120-347-4PK |
| G24d-3 | 26 | 6.7 | 97609 | F26DBX/841/ECO | 10 | 12,000 | 1,710 | 1,460 | 4100K | 82 | Vertical: 93300088<br>Horizontal: 93300087 | LED11BG24-V/8SC/120-347-4PK<br>LED11BG24-H/8SC/120-347-4PK |
| **4-Pin Double Biax®** | | | | | | | | | | | | |
| G24q-1 | 13 | 5.0 | 97594 | F13DBX/827/ECO4P | 10 | 17,000 | 900 | 755 | 2700K | 82 | 93300068 | LED8BG24-O/827-4PK |
| G24q-1 | 13 | 5.0 | 97595 | F13DBX/830/ECO4P | 10 | 17,000 | 900 | 755 | 3000K | 82 | 93300069 | LED8BG24-O/830-4PK |
| G24q-1 | 13 | 5.0 | 97596 | F13DBX/835/ECO4P | 10 | 17,000 | 900 | 755 | 3500K | 82 | 93300080 | LED8BG24-O/835-4PK |
| G24q-1 | 13 | 5.0 | 97597 | F13DBX/841/ECO4P | 10 | 17,000 | 900 | 755 | 4100K | 82 | 93300081 | LED8BG24-O/840-4PK |
| G24q-2 | 18 | 5.8 | 97598 | F18DBX/827/ECO4P | 10 | 17,000 | 1,250 | 970 | 2700K | 82 | 93300082 | LED10BG24-O/827-4PK |
| G24q-2 | 18 | 5.8 | 97599 | F18DBX/830/ECO4P | 10 | 17,000 | 1,250 | 970 | 3000K | 82 | 93300083 | LED10BG24-O/830-4PK |
| G24q-2 | 18 | 5.8 | 97600 | F18DBX/835/ECO4P | 10 | 17,000 | 1,250 | 970 | 3500K | 82 | 93300084 | LED10BG24-O/835-4PK |
| G24q-2 | 18 | 5.8 | 97601 | F18DBX/841/ECO4P | 10 | 17,000 | 1,250 | 970 | 4100K | 82 | 93300086 | LED10BG24-O/840-4PK |
| G24q-3 | 26 | 6.4 | 97610 | F26DBX/827/ECO4P | 10 | 17,000 | 1,800 | 1,530 | 2700K | 82 | Vertical: 93300088<br>Horizontal: 93300087 | LED11BG24-V/8SC/120-347-4PK<br>LED11BG24-H/8SC/120-347-4PK |
| G24q-3 | 26 | 6.4 | 97611 | F26DBX/830/ECO4P | 10 | 17,000 | 1,800 | 1,530 | 3000K | 82 | Vertical: 93300088<br>Horizontal: 93300087 | LED11BG24-V/8SC/120-347-4PK<br>LED11BG24-H/8SC/120-347-4PK |
| G24q-3 | 26 | 6.4 | 97612 | F26DBX/835/ECO4P | 10 | 17,000 | 1,800 | 1,530 | 3500K | 82 | Vertical: 93300088<br>Horizontal: 93300087 | LED11BG24-V/8SC/120-347-4PK<br>LED11BG24-H/8SC/120-347-4PK |
| G24q-3 | 26 | 6.4 | 97613 | F26DBX/841/ECO4P | 10 | 17,000 | 1,800 | 1,530 | 4100K | 82 | Vertical: 93300088<br>Horizontal: 93300087 | LED11BG24-V/8SC/120-347-4PK<br>LED11BG24-H/8SC/120-347-4PK |
| **4-Pin Triple Biax®** | | | | | | | | | | | | |
| GX24q-3 | 26 | 5.2 | 97614 | F26TBX/827/A/ECO | 10 | 17,000 | 1,800 | 1,530 | 2700K | 82 | Vertical: 93300088<br>Horizontal: 93300087 | LED11BG24-V/8SC/120-347-4PK<br>LED11BG24-H/8SC/120-347-4PK |
| GX24q-3 | 26 | 5.2 | 97615 | F26TBX/830/A/ECO | 10 | 17,000 | 1,800 | 1,530 | 3000K | 82 | Vertical: 93300088<br>Horizontal: 93300087 | LED11BG24-V/8SC/120-347-4PK<br>LED11BG24-H/8SC/120-347-4PK |
| GX24q-3 | 26 | 5.2 | 97616 | F26TBX/835/A/ECO | 10 | 17,000 | 1,800 | 1,530 | 3500K | 82 | Vertical: 93300088<br>Horizontal: 93300087 | LED11BG24-V/8SC/120-347-4PK<br>LED11BG24-H/8SC/120-347-4PK |
| GX24q-3 | 26 | 5.2 | 97617 | F26TBX/841/A/ECO | 10 | 17,000 | 1,800 | 1,530 | 4100K | 82 | Vertical: 93300088<br>Horizontal: 93300087 | LED11BG24-V/8SC/120-347-4PK<br>LED11BG24-H/8SC/120-347-4PK |
| GX24q-3 | 32 | 5.5 | 97629 | F32TBX/827/A/ECO | 10 | 17,000 | 2,400 | 2,040 | 2700K | 82 | Vertical: 93312489<br>Horizontal: 93312525 | LED18BG24-V/8SC/120-347<br>LED18BG24-H/8SC/120-347 |
| GX24q-3 | 32 | 5.5 | 97630 | F32TBX/830/A/ECO | 10 | 17,000 | 2,400 | 2,040 | 3000K | 82 | Vertical: 93312489<br>Horizontal: 93312525 | LED18BG24-V/8SC/120-347<br>LED18BG24-H/8SC/120-347 |
| GX24q-3 | 32 | 5.5 | 97631 | F32TBX/835/A/ECO | 10 | 17,000 | 2,400 | 2,040 | 3500K | 82 | Vertical: 93312489<br>Horizontal: 93312525 | LED18BG24-V/8SC/120-347<br>LED18BG24-H/8SC/120-347 |
| GX24q-3 | 32 | 5.5 | 97632 | F32TBX/841/A/ECO | 10 | 17,000 | 2,400 | 2,040 | 4100K | 82 | Vertical: 93312489<br>Horizontal: 93312525 | LED18BG24-V/8SC/120-347<br>LED18BG24-H/8SC/120-347 |
| GX24q-4 | 42 | 6.4 | 97633 | F42TBX/827/A/ECO | 10 | 17,000 | 3,200 | 2,690 | 2700K | 82 | Vertical: 93312489<br>Horizontal: 93312525 | LED18BG24-V/8SC/120-347<br>LED18BG24-H/8SC/120-347 |
| GX24q-4 | 42 | 6.4 | 97634 | F42TBX/830/A/ECO | 10 | 17,000 | 3,200 | 2,690 | 3000K | 82 | Vertical: 93312489<br>Horizontal: 93312525 | LED18BG24-V/8SC/120-347<br>LED18BG24-H/8SC/120-347 |
| GX24q-4 | 42 | 6.4 | 97635 | F42TBX/835/A/ECO | 10 | 17,000 | 3,200 | 2,690 | 3500K | 82 | Vertical: 93312489<br>Horizontal: 93312525 | LED18BG24-V/8SC/120-347<br>LED18BG24-H/8SC/120-347 |
| GX24q-4 | 42 | 6.4 | 97636 | F42TBX/841/A/ECO | 10 | 17,000 | 3,200 | 2,690 | 4100K | 82 | Vertical: 93312489<br>Horizontal: 93312525 | LED18BG24-V/8SC/120-347<br>LED18BG24-H/8SC/120-347 |

[1] Minimum order quantity = Carton Qty

Please note Current lamps are not for sale for use in Yukon Territory in Canada

**Halogen Lighting** offers unmatched quality of white light in compact sizes.


## **Reference Guide** | Bulb Identification






**DIA. in.:** Diameter of bulb at widest point.
**MOL in.:** Maximum Overall Length including base or pins.
**LCL in.:** Distance between the center of the filament and the Light Center Length reference plane.
**Note:** Lamp drawings are not drawn to scale. Be sure to check size and dimension information when identifying each lamp.


To convert inches to millimeters, multiply the dimension (in inches) by 25.4 (i.e. 1.5" x 25.4 = 38.1 mm).


## **Filament** Identification


C-8
CC-8


C-2V
CC-2V


C-6
CC-6


C-8
CC-8


C-6
Oval

## **Base Identification** (not drawn to scale)



2-Pin
(Round)
GX5.3



Can DC Bay


2-Pin
GY6.35


Recessed
Single Contact
R7s


Screw
Terminals


4" Leads


1" Ribbon
Leads


6" Flex
Leads


2-Pin
GU4


2-Pin
GU5.3


2-Pin
G4


Turn & Lock
GU7


GU10


G8



G9



2-Pin Pf



Min Screw
E10



DC Bay
BA15d



Min Cand
E11



Med Screw
E26


Mog Screw
E39


Mogul BiPost
G38


Ext. Mog
End Pr
GX16d


Mog End
Pr
GX16d


Med
Skirted
E26/50x39

## Catalog Logic:

The following terms and descriptions can help you when checking Halogen lamp specifications and when ordering products. Within each product line, lamps are divided into families and listed by wattage.

**Bulb Shape:**
followed by its size (the maximum diameter of the bulb expressed in eighths of an inch).

**Watts:**
Energy used (as defined by FTC Lamp Label Rules). To estimate energy consumption (kWh), multiply watts x hours of use and divide by 1000.

**Base:**
The type of base

**Order Code:**
Use the order code when ordering to ensure that you receive the exact product you require.

**Description:**
Lamp Model Description

**Volts:**
Lamp data is based on operation at rated voltage

**Carton Quantity:**
Number of lamps packed in a carton

**Filament Design:**
Filaments are designated by a letter combination in which C is coiled wire filament, CC is a coiled wire that is itself wound into a larger coil and SR is straight ribbon filament. Numbers represent the type of filament-support arrangement.

**MOL (in):**
Maximum Overall Length in inches

**LCL (in):**
Distance between the center of the filament and the Light Center Length reference plane, in inches.

**Rated Life (hours):**
Life (as defined by FTC Lamp Label Rules) is rated life in hours.

**Initial Lumens:**
Lamp light output after the initial 100 hours of operation.

**Color Temperature – Kelvins (K):**
A measure of the visual "warmth" or "coolness" of the light from the lamp. The higher the value, the whiter or "cooler" the light appears.

**CBCP (Center beam Candlepower:**
For reflector-type lamps, Center Beam Candlepower is the intensity (candelas) at the center of maximum intensity of the beam. Used only for ConstantColor® CMH® Metal Halide Lamps

**Additional Information:**
Typical application and/or other important information.

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty | Filament Design | MOL (In) | LCL (In) | Rated Life (hrs*) | Lumens Initial | Color Temp. | CBCP | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Standard MR16** | | | | | | | | | | | | | | |
| PAR36 | Scrw Term | 35 | 19877 | 35PAR36/H/FL30 | 12 | 12 | C-6 | 2.75 | | 4,000 | 250 | 3050K | 900 | Floodlight |

**35PAR36/H/FL30**

- 35 — Identifies as lamp's wattage
- PAR36 — Identifies the lamp shape and the bulb diameter in eighths of inches
- H — Identifies the lamp type (Halogen)
- FL — Identifies beam angle type (Flood or Spot), code may also include base type or packaging information
- 30 — Beam Angle (30 = 30 degrees)

## Specialty Lamps


| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[1] | Filament Design | MOL (In) | LCL (In) | Rated Life (hrs*) | Lumens Initial | Color Temp. | CBCP | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Compact PAR36** | | | | | | | | | | | | | | |
| PAR36 | Scrw Term | 35 | 19877 | 35PAR36/H/FL30 | 12 | 12 | C-6 | 2.75 | | 4,000 | 250 | 3050K | 900 | Floodlight |
| **Standard MR11** | | | | | | | | | | | | | | |
| MR11 | 2-Pin G4 | 20 | 30773 | Q20MR11/NFL30 | 12 | 10 | C-6 | 1.38 | | 3,500 | | 2900K | 600 | Soft White |
| **Halogen G9** | | | | | | | | | | | | | | |
| T4 | G9 | 25 | 16754 | Q25G9/CD | 120 | 5 | CC-8 | 1.77 | 1.26 | 3,000 | 240 | 6250K | | Carded |
| **Halogen Double Contact Bayonet (BA15d)** | | | | | | | | | | | | | | |
| T4 | BA15d | 100 | 15508 | Q100CL/DC | 120 | 6 | CC-8 | 2.44 | 1.38 | 2,000 | 1,600 | 2950K | | Clear |
| | BA15d | 150 | 43693 | Q150CL/DC | 120 | 6 | CC-8 | 2.50 | 1.38 | 2,000 | 2,800 | 2950K | | Clear |
| | BA15d | 250 | 43697 | Q250CL/DC | 120 | 6 | CC-8 | 3.00 | 1.63 | 2,000 | 5,000 | 2950K | | Clear |
| **Halogen Recessed Single Contact (R7s)** | | | | | | | | | | | | | | |
| T3 | R7s | 100 | 22489 | Q100T3/CL/CD 5PK | 210 | 60 | C-8 | 3.13 | 1.25 | 1,500 | 1,650 | 2950K | | Clear, Horizontal, Carded |
| | R7s | 150 | 19378 | Q150T3/CL/CD 5PK | 120 | 60 | C-8 | 3.13 | 1.25 | 1,500 | 2,400 | 2950K | | Clear, Horizontal, Carded |
| T2.5 | R7s | 300 | 43703 | Q300T3/CL-6PK | 120 | 144 | C-8 | 4.69 | 2.25 | 2,000 | 5,950 | 2950K | | Clear, Horizontal |
| | R7s | 500 | 23731 | Q500T3/CL | 120 | 12 | C-8 | 4.69 | 2.25 | 2,000 | 11,100 | 3000K | | Clear, Horizontal |
| | R7s | 500 | 23733 | Q500T3/CL | 130/120 | 12 | C-8 | 4.69 | 2.25 | 2,000 | 10,550 | 3000K | | Clear, Horizontal |

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[1] | Filament Design | MOL (In) | LCL (In) | Rated Life (hrs*) | Lumens Initial | Color Temp. | Additional Information |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Halogen Miniature Candelabra Screw (E11)** | | | | | | | | | | | | | |
| T4 | Mini-Cand | 100 | 15507 | Q100CL/MC | 120 | 6 | CC-8 | 2.81 | 1.38 | 2,000 | 1,600 | 2950K | Clear |
| | Mini-Cand | 150 | 43694 | Q150CL/MC | 120 | 6 | CC-8 | 3.00 | 1.38 | 2,000 | 2,800 | 2950K | Clear |
| | Mini-Cand | 250 | 43699 | Q250CL/MC | 120 | 6 | CC-8 | 3.16 | 1.63 | 2,000 | 5,000 | 2950K | Clear |
| | Mini-Cand | 250 | 43700 | Q250CL/MC | 130/120 | 6 | CC-8 | 3.16 | 1.63 | 2,000 | 5,000 | 2950K | Clear |

[1] Minimum order quantity = Carton Qty
Please note Current lamps are not for sale for use in Yukon Territory in Canada

**Incandescent Lighting** is the familiar, dependable light source you've known for decades.

## **Reference Guide** | Bulb Identification




**DIA:** Diameter of bulb at widest point.


**MOL:** Maximum Overall Length including base or pins.

**LCL:** Distance between the center of the arc tube and the Light Center Length reference plane.

**Note:** Lamp drawings are not drawn to scale. Be sure to check size and dimension information when identifying each lamp.


To convert inches to millimeters, multiply the dimension (in inches) by 25.4 (i.e. 1.5" x 25.4 = 38.1 mm).

## **Filament** Identification



C-9 | C-6, CC-6 | C-17 | C-22 | C-13 | C-13D | C-8, CC-8 | C-8, CC-8 | C-5 | C-7A | C-2V, CC-2V

## **Base Identification** (not drawn to scale)




Cand Screw E12 | Intermediate E17 | 3 Contact Med E26 | Med Screw E26 | Mog Screw E39 | 3 Contact Mogul E39D | Mog Pf P40s

Med Skirt E26/50x39 | Can DC Bay | Can SC Bay B15 | 2-Lug Sleeve B22d | 3-Lug Sleeve B22-3 | Med Pf P28s | Mogul BiPost G38

Screw Terminal | Disc Base | Single Contact Pf | Med BiPost | Med Side Pr | Ext. Mog End PR GX16d | Mog End PR GX16d

## Lamp Drawings (not drawn to scale)



## Catalog Logic:

The following terms and descriptions can help you when checking Incandescent lamp specifications and when ordering products. Within this product line, lamps are listed by wattage.

**Bulb Shape:** followed by its size (the maximum diameter of the bulb expressed in eighths of an inch).

**Watts:** Energy used (as defined by FTC Lamp Label Rules). To estimate energy consumption (kWh), multiply watts x hours of use and divide by 1000.

**Base:** The type of base

**Order Code:** Use the order code when ordering to ensure that you receive the exact product you require.

**Description:** Lamp Model Description

**Carton Quantity:** Number of lamps packed in a carton

**Volts:** Lamp data is based on operation at rated voltage

**Filament Design:** Filaments are designated by a letter combination in which C is coiled wire filament, CC is a coiled wire that is itself wound into a larger coil and SR is straight ribbon filament. Numbers represent the type of filament-support arrangement.

**MOL (in):** Maximum Overall Length in inches

**Rated Life (hours):** Life (as defined by FTC Lamp Label Rules) is rated life in hours.

**Color Temperature – Kelvins (K):** A measure of the visual "warmth" or "coolness" of the light from the lamp. The higher the value, the winter or "cooler" the light appears.


**Initial Lumens:** Lamp light output after the initial 100 hours of operation.

**CBCP (Center beam Candlepower):** For reflector-type lamps, Center Beam Candlepower is the intensity (candelas) at the center of maximum intensity of the beam. Used only for ConstantColor® CMH® Metal Halide Lamps

**Additional Information:** Typical application and/or other important information.

**LED Replacement:** Current offers a wide range of LED replacement lamps. The LED lamp models are provided as general guidance. Often, there will be more than one LED Lamp that may be used to replace a Traditional lamp. For Traditional lamps that operated off a ballast, the ballast bypass (UL Type B) LED option is given unless otherwise noted. The application should be considered when selecting an LED replacement lamp. Sometimes, Traditional lamps do not have a suitable LED replacement due to special application considerations, such as very high heat. Contact Current for additional guidance if the appropriate LED solution is unclear.

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty | Filament Design | MOL (In) | LCL (In) | Rated Life (hrs*) | Lumens Initial | Color Temp | CBCP | Additional Information | LED Replacement Order Code | LED Replacement Description |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **3-8 Watts** | | | | | | | | | | | | | | | | |
| S6 | Cand | 3 | 11098 | 3S6/5 24PK | 130 | 24 | C-7A | 1.87 | 1.37 | 3,000 | 11 | | | Clear-Indicator | | |



## Incandescent Lamps

| Bulb Shape | Base Type | Watts | Order Code | Description | Volts | Carton Qty[1] | Filament Design | MOL (In) | LCL (In) | Rated Life (hrs*) | Lumens Initial | Color Temp | CBCP | Additional Information | LED Replacement Order Code | LED Replacement Description |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **3-8 Watts** | | | | | | | | | | | | | | | | |
| S6 | Cand | 3 | 11098 | 3S6/5 24PK | 130 | 24 | C-7A | 1.87 | 1.37 | 3,000 | 11 | | | Clear-Indicator | | |
| | Cand | 6 | 11374 | 6S6 155 | 155 | 240 | C-7A | 1.87 | 1.37 | 1,500 | 38 | | | Clear-Indicator | | |
| T4.5 | Cand | 6 | 11764 | 6T41/2/1 | 130 | 100 | C-7A | 1.87 | 1.31 | 1,500 | 42 | | | Clear-Indicator | | |
| **15 Watts** | | | | | | | | | | | | | | | | |
| A15 | Med | 15 | 97491 | 15A/W-2PK | 120 | 24 | C-9 | 3.50 | 2.37 | 2,500 | 110 | | | Soft-White | 93142810 | LED4DFA15-W-2PK |
| S11 | DC Bay | 15 | 13188 | 15S11/3DC | 75 | 120 | C-9 | 2.37 | 1.25 | 1,000 | 138 | | | Clear-Train | | |
| T6 | Cand | 15 | 13402 | 15T6 | 145 | 60 | C-7A | 3.06 | 1.56 | 1,500 | 102 | | | Clear-Exit | | |
| T7 | Cand | 15 | 13494 | 15T7C | 120 | 120 | C-7A | 2.25 | 1.50 | 3,000 | 108 | | | Clear-Appliance | | |
| **18 Watts** | | | | | | | | | | | | | | | | |
| S11 | BA15s | 18 | 13655 | 18S11/1SC | 10 | 120 | CC-6 | 2.37 | 1.25 | 2,000 | 200 | | | Clear-Railway | | |
| **20 Watts** | | | | | | | | | | | | | | | | |
| T6.5 | DC Bay | 20 | 34241 | 20T61/2DC/F | 120 | 60 | C-8 | 5.56 | | 5,000 | 90 | | | Frost-Exit Light | | |
| T6.5 | Inter | 20 | 34272 | 20T61/2/F | 120 | 60 | C-8 | 5.50 | | 7,000 | 90 | | | Frost-Exit Light | | |
| **25 Watts** | | | | | | | | | | | | | | | | |
| T7 | DC Bay | 25 | 14741 | 25T7DC | 120 | 60 | C-7A | 2.25 | 1.31 | 1,000 | 195 | | | Clear-Appliance | | |
| T7 | Inter | 25 | 14791 | 25T7N | 120 | 60 | C-7A | 2.25 | 1.56 | 1,000 | 195 | | | Clear-Appliance | | |
| T10 | Med | 25 | 14880 | 25T10 24PK | 120 | 192 | C-8 | 5.60 | | 1,000 | 250 | | | Clear-Display Light | | |
| B10 | Med | 25 | 22756 | 25BM CD2 | 120 | 60 | C-7A | 4.62 | | 1,500 | 170 | 2500K | | Clear, Blunt Tip | 93142811 | LED4DFBM-C-2PK |
| CA10 | Cand | 25 | 40045 | 25CAC/L | 120 | 120 | CC-2V | 4.12 | | 4,000 | 210 | 2500K | | Clear, Bent Tip | 93142792 | LED3DFCAC-C-2PK |
| **40 Watts** | | | | | | | | | | | | | | | | |
| A15 | Med | 40 | 15206 | 40A15 CARD 12PK | 120 | 60 | C-9 | 3.50 | 2.37 | 1,500 | 415 | 2600K | | Clear-Oven Light | 93142809 | LED4DFA15-C-2PK |
| **50 Watts** | | | | | | | | | | | | | | | | |
| A19 | Med | 50 | 16201 | 50A19/RS/SH | 75 | 120 | C-9 | 3.87 | 2.50 | 1,000 | 500 | | | Train/Rough Service | | |
| **200 Watts** | | | | | | | | | | | | | | | | |
| A21 | Med | 200 | 16069 | 200A/CL-1 12PK | 120 | 12 | CC-8 | 5.37 | 4.06 | 750 | 3,780 | 2900K | | Crystal | 93309226 | LED23A21/827 |
| PAR56 | Scrw Term | 200 | 20122 | 200PAR | 30 | 12 | CC-8 | 4.50 | | 350 | | | 230,000 | Locomotive | | |
| **250 Watts** | | | | | | | | | | | | | | | | |
| R40 | Med | 250 | 37770 | 250R40/1 6PK | 120 | 30 | C-9 | 6.56 | | 5,000 | 2,200 | | | Heat Lamp | | |
| **300 Watts** | | | | | | | | | | | | | | | | |
| PS25 | Med | 300/266 | 73788 | 300M/130V-PK6 | 130/120 | 6 | CC-8 | 6.93 | 4.92 | 750/1,950 | 6,120/4,650 | | | Clear | 93303384 | LED/LC/ED17/7SC |
| PS35 | Mog Screw | 300 | 21025 | 300 | 130 | 24 | C-9 | 9.37 | 7.00 | 1,000 | 5,820 | | | Clear | 93303384 | LED/LC/ED17/7SC |
| | Mog Screw | 300 | 21079 | 300/IF | 130 | 24 | C-9 | 9.37 | 7.00 | 1,000 | 5,820 | | | Inside Frost | 93303384 | LED/LC/ED17/7SC |
| | Mog Screw | 300 | 20849 | 300PAR56/WFL | 120 | 12 | CC-13 | 5 | | 2,000 | 3,840 | 2750K | 11,000 | Wide Flood | | |
| **350 Watts** | | | | | | | | | | | | | | | | |
| PAR56 | Scrw Term | 350 | 19866 | 350PAR56/SP | 75 | 12 | CC-8 | 4.50 | | 500 | 6,200 | | | Locomotive | | |
| **375 Watts** | | | | | | | | | | | | | | | | |
| R40 | Med Skirt | 375 | 21334 | 375R40/1 | 115 | 24 | C-9 | 7.50 | | 5,000 | 2,700 | | 1,170 | Infrared Reflector | | |

[1] Minimum order quantity = Carton Qty
Please note Current lamps are not for sale for use in Yukon Territory in Canada

# Ballasts



## Understanding **Fluorescent Ballasts**

GE introduced the first fluorescent ballast more than 70 years ago. Today, Current is providing high-frequency electronic GE Lamp ballasts for almost every fluorescent application.

### With our UltraMax® and UltraStart® ballasts, we are bringing you the future in ballast performance.

Current's UltraMax® instant-start and UltraStart® programmed start electronic ballasts transform the power of light into efficiency and savings from store shelves to the installation site. The foundation of the "Ultra" family of ballasts starts with its high efficiency ratings. High efficiency ballasts are a minimum of 90% efficiency with some ballasts nearly 95% efficient which means the ballast only consumes 5-10% of the total system power. These high efficiency ballasts exceed minimum high efficiency standards as established by almost all energy advocate groups, utility rebate programs and the NEMA Premium® ballast program. The ballasts are marked with the Ultra brand as well as the NEMA Premium® ballast mark. These ballasts have multi-voltage control (MVC), which automatically adjusts to handle voltage from 120V through 277V. That cuts the ballast models you need to stock from 40 down to 13, which can dramatically reduce inventory carrying costs. UltraMax® ballasts have ArcGuard Protection, too, with a UL Type CC Anti-Arc Rating. Plus, they're ultra-lamp-friendly, with a low lamp current crest factor of 1.4 for optimal lamp performance. Both UltraMax® and UltraStart® have anti-striation control for better light quality with no lamp striations (spiraling). And the small, low-profile design of these ballasts makes retrofits effortless at the job site. Also unique to our programmed start UltraStart® ballasts is parallel lamp operation which means that if one lamp fails the others remain on and quick starting times of less than 700 milliseconds which is necessary in avoiding delays with automatic sensors.

### Fluorescent Ballast Types

#### *Electronic Instant Start*

The most common fluorescent ballast is the instant start and is used typically in long 3 to 10-hour lamp cycle applications. These ballasts are energy efficient and can deliver 20% to 40% energy savings when installed with energy-efficient lamps in building retrofits. These ballasts deliver >550 open circuit volts when starting lamps and operate lamps at high frequencies which offers flicker-free operation and better lamp efficiencies. The ballasts are significantly quieter than conventional magnetic ballasts and are backed by Current Lighting's system 5-year ballast limited warranty and extended lamp warranties.

**UltraMax® Professional Series**
A family of high-efficiency T8 instant-start electronic linear fluorescent ballasts designed to optimize T8 lamps for optimal system energy savings. UltraMax® ballasts have a low lamp current crest factor and virtually "read" and adapt to incoming voltage from 108V to 305V. Other features include UL Type CC Anti-Arc Rating and anti-striation control to eliminate lamp striations and spiraling. These ballasts are offered in ballast factors: low wattage (.77), normal light (.87), normal-high (N+) (1.0) and high (>1.15).

**UltraMax® General Series**
Offered in dedicated or multi-volt (120-277V), these high performance T8 instant-start ballasts also meet minimum efficiency requirements as established with the NEMA Premium® ballast program. These ballasts are offered in ballast factors: low wattage (.77), normal light (.87) and high (>1.15).



## *Programmed Instant Start*

Programmed Start electronic ballasts have a lamp starting method that preheats lamp filaments before applying an open circuit voltage (OCV) to start the lamp. Use Programmed Start ballasts to ensure long lamp life when turning lamps on and off more than five times in a day or in conjunction with any automatic light control or sensor. This type of starting circuit keeps lamp-end blackening to a minimum and improves lamp life performance, especially in applications where the lamps are frequently switched on and off.

### UltraStart®

UltraStart® is a family of high-efficiency Programmed Start electronic linear fluorescent ballasts that also exceed NEMA Premium® ballast efficiency requirements but are designed to optimize T8 lamps in frequently switched applications. Instant start ballasts provide 7,000-13,000 starts before 50% lamp failure. UltraStart® provides greater than 100,000 starts before 50% lamp failure. UltraStart® ballasts provide the same energy savings and convenience of instant start ballasts but with the longer lamp life offered a programmed start ballast. These ballasts are offered in ballast factors: programmed start x-low wattage (XL) (.60), low wattage (.71), normal light (.87) and high (>1.15).



## *Ballast Date Codes*

### Date Code

Electronic ballast manufacturing date codes are located on the upper right-hand corner of the label. The code lists the month, year and day of manufacture. A typical code is C16-073, where the month is listed as A (January), B (February), C (March) as in this code followed by the year 16 (2016) and the date of manufacture 073 (the 73rd day of 2016).

### Ballast Life

Electronic ballasts are designed and manufactured to an average life expectancy of 60,000 hours of operation at maximum rated case temperatures. As a rule of thumb, ballast life is doubled for every 10C reduction in ballast case temperature. However there are other variables such as transients, voltage sags and swells, ambient temperature, etc., which affect ballast life as well.

### Instant Start vs. Rapid Start Sockets

When using programmed start or dimming ballasts in fixtures, sockets must be 2-pin rapid start type. Fixtures with T8 instant start ballasts must use jumpered rapid start sockets or shunted lamp holders (internal to the lamp holder) that bridge the lamp bi-pins together into one contact on each side of the lamp. If retrofitting from a instant start ballast fixture with shunted sockets to a dimming or programmed start ballast, rapid start type sockets must be used to properly start lamps and maintain rated lamp life.

# 73190 – GE232MAXP-H/ULTRA

## UltraMax® P-Series Instant Start Multi-Voltage High-Efficiency

2 or 1 – F32T8 120 to 277 "H" 1.18 BF UltraMax® P

- T8 Instant Start Ballasts For F17 (2ft), F25 (3ft), F32 (4ft), F40 (5ft) Lamps
- Energy-saving high-efficiency instant-start electronic ballast (>90%)
- Multi-voltage technology handles voltage from 120 to 277V
- UL Type CC Rating provides protection against arcing in electrical devices
- Anti-striation control for better light quality
- UL 55°C Ambient Temperature rating
- Cold temperature -22°F Minimum Starting Temperature

| General Characteristics | |
|---|---|
| Ballast Type | Electronic – High-Efficiency Multivolt Instant Start |
| Starting Method | Instant Start |
| Lamp Wiring | Parallel |
| Line Voltage Regulation(+/-) | 10% |
| Ambient Temperature (MAX) | 55°C (131°F) |
| Case Temperature (MAX) | 90°C (194°F) |
| Ballast Factor | High |
| Power Factor Correction | Active |
| Sound Rating | A (20-24 decibels) |
| Enclosure Type | Metal |
| Additional Info | Anti-striation control, Auto-restart, Inherently Thermally Protected, UL Class P |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 50 Hz/60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 9.5 in (241 mm) |
| Width (W) | 1.3 in (33 mm) |
| Height (H) | 1.0 in (25.4 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 8.9 in (226 mm) |
| Mount Width (X or F) | 0.87 in (22 mm) |
| Mount Slots (MS) | 0.3 in (8 mm) |
| Weight | 0.7 lbs |
| Exit Type | Side |
| Remote Mounting Distance to Lamp (F32T8) | 18 ft |
| Remote Mounting Wire Gauge | 18 AWG |
| **Lead Lengths** | |
| Black | 25 in (635 mm) |
| White | 25 in (635 mm) |
| Blue | 31 in (787 mm) |
| Red | 37 in (940 mm) |

**Specifications and lamp wattage**

| Lamp | # of Lamps | Line Volts (V) | System Watts (W) | Nom. Line Current (A) | System Ballast Factor | Ballast Efficacy Factor | Power Factor % (>=) | Crest Factor (<=) | THD% (<=) | Min Starting Temp (°F/°C) |
|---|---|---|---|---|---|---|---|---|---|---|
| F32T8 | 2 | 120 | 74 | 0.62 | 1.19 | 1.61 | 99 | 1.5 | 10 | -22/-30 |
| | 2 | 277 | 73 | 0.26 | 1.19 | 1.63 | 98 | 1.5 | 10 | -22/-30 |
| | 1 | 120 | 47 | 0.40 | 1.38 | 2.94 | 99 | 1.5 | 10 | -22/-30 |
| | 1 | 277 | 46 | 0.18 | 1.38 | 3.00 | 96 | 1.5 | 20 | -22/-30 |
| F32T8/WM | 2 | 120 | 70 | 0.59 | 1.16 | 1.66 | 99 | 1.5 | 10 | -22/-30 |
| | 2 | 277 | 69 | 0.26 | 1.16 | 1.68 | 98 | 1.5 | 10 | -22/-30 |
| | 1 | 120 | 43 | 0.37 | 1.37 | 3.19 | 99 | 1.5 | 10 | -22/-30 |
| | 1 | 277 | 43 | 0.17 | 1.37 | 3.19 | 95 | 1.5 | 15 | -22/-30 |
| F28T8 | 2 | 120 | 65 | 0.55 | 1.14 | 1.75 | 99 | 1.5 | 10 | -22/-30 |
| | 2 | 277 | 64 | 0.24 | 1.14 | 1.78 | 97 | 1.5 | 10 | -22/-30 |
| | 1 | 120 | 40 | 0.34 | 1.34 | 3.35 | 99 | 1.5 | 10 | -22/-30 |
| | 1 | 277 | 41 | 0.16 | 1.34 | 3.27 | 94 | 1.5 | 20 | -22/-30 |
| F32T8/25W | 2 | 120 | 60 | 0.51 | 1.16 | 1.93 | 99 | 1.5 | 10 | -22/-30 |
| | 2 | 277 | 60 | 0.22 | 1.16 | 1.93 | 97 | 1.5 | 15 | -22/-30 |
| | 1 | 120 | 38 | 0.32 | 1.37 | 3.60 | 99 | 1.5 | 15 | -22/-30 |
| | 1 | 277 | 38 | 0.15 | 1.37 | 3.60 | 94 | 1.5 | 20 | -22/-30 |
| F25T8 | 2 | 120 | 62 | 0.52 | 1.17 | 1.87 | 99 | 1.5 | 10 | -22/-30 |
| | 2 | 277 | 61 | 0.22 | 1.17 | 1.90 | 97 | 1.5 | 15 | -22/-30 |
| | 1 | 120 | 38 | 0.32 | 1.37 | 3.61 | 99 | 1.5 | 15 | -22/-30 |
| | 1 | 277 | 38 | 0.15 | 1.37 | 3.61 | 94 | 1.5 | 20 | -22/-30 |
| F17T8 | 2 | 120 | 41 | 0.36 | 1.02 | 2.85 | 99 | 1.5 | 10 | -22/-30 |
| | 2 | 277 | 41 | 0.17 | 1.02 | 2.85 | 95 | 1.5 | 20 | -22/-30 |
| | 1 | 120 | 26 | 0.23 | 1.21 | 5.27 | 99 | 1.5 | 15 | -22/-30 |
| | 1 | 277 | 27 | 0.12 | 1.21 | 5.07 | 90 | 1.5 | 20 | -22/-30 |
| FE15T8 | 2 | 120 | 32 | 0.29 | 1.02 | 3.19 | 99 | 1.5 | 15 | -22/-30 |
| | 2 | 277 | 33 | 0.14 | 1.02 | 3.09 | 93 | 1.5 | 20 | -22/-30 |
| | 1 | 120 | 23 | 0.19 | 1.21 | 5.26 | 98 | 1.5 | 15 | -22/-30 |
| | 1 | 277 | 22 | 0.10 | 1.21 | 5.50 | 87 | 1.5 | 20 | -22/-30 |
| F40T8 | 1 | 120 | 56 | 0.46 | .66 | 1.18 | 99 | 1.5 | 10 | -22/-30 |
| | 1 | 277 | 55 | 0.21 | .66 | 1.20 | 94 | 1.5 | 15 | -22/-30 |
| F25T12 | 2 | 120 | 64 | 0.54 | 1.11 | 1.73 | 99 | 1.5 | 10 | 0/-18 |
| | 2 | 277 | 63 | 0.24 | 1.11 | 1.76 | 97 | 1.5 | 10 | 0/-18 |
| | 1 | 120 | 40 | 0.35 | 1.36 | 3.40 | 99 | 1.5 | 10 | 0/-18 |
| | 1 | 277 | 40 | 0.16 | 1.36 | 3.40 | 94 | 1.5 | 15 | 0/-18 |

## Safety and Performance

UL LISTED · UL Class P · UL Type 1 Outdoor · UL Type CC · UL Type HL · FCC – CLASS A Non-Consumer

# 72266 – GE232MAXP-N/ULTRA

## UltraMax® P-Series Instant Start Multi-Voltage High-Efficiency

2 or 1 – F32T8 120 to 277 "N" 87 BF UltraMax® P

- T8 Instant Start Ballasts For F17 (2ft), F25 (3ft), F32 (4ft), F40 (5ft) Lamps
- Energy-saving high-efficiency instant-start electronic ballast (>90%)
- Multi-voltage technology handles voltage from 120 to 277V
- UL Type CC Rating provides protection against arcing in electrical devices
- Anti-striation control for better light quality
- UL 55°C Ambient Temperature rating
- Cold temperature -22°F Minimum Starting Temperature

| General Characteristics | |
|---|---|
| Ballast Type | Electronic – High-Efficiency Multivolt Instant Start |
| Starting Method | Instant Start |
| Lamp Wiring | Parallel |
| Line Voltage Regulation(+/-) | 10% |
| Ambient Temperature (MAX) | 55°C (131°F) |
| Case Temperature (MAX) | 70°C (158°F) |
| Ballast Factor | Normal |
| Power Factor Correction | Active |
| Sound Rating | A (20-24 decibels) |
| Enclosure Type | Metal |
| Additional Info | Anti-striation control, Auto-restart, Inherently Thermally Protected, UL Class P |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 50 Hz/60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 9.5 in (241 mm) |
| Width (W) | 1.3 in (33 mm) |
| Height (H) | 1.0 in (25.4 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 8.9 in (226 mm) |
| Mount Width (X or F) | 0.87 in (22 mm) |
| Mount Slots (MS) | 0.3 in (8 mm) |
| Weight | 0.7 lbs |
| Exit Type | Side |
| Remote Mounting Distance to Lamp (F32T8) | 18 ft |
| Remote Mounting Wire Gauge | 18 AWG |
| **Lead Lengths** | |
| Black | 25 in (635 mm) |
| White | 25 in (635 mm) |
| Blue | 31 in (787 mm) |
| Red | 37 in (940 mm) |

**Specifications and lamp wattage**

| Lamp | # of Lamps | Line Volts (V) | System Watts (W) | Nom. Line Current (A) | System Ballast Factor | Ballast Efficacy Factor | Power Factor % (>=) | Crest Factor (<=) | THD% (<=) | Min Starting Temp (°F/°C) |
|---|---|---|---|---|---|---|---|---|---|---|
| F32T8 | 2 | 120 | 54 | 0.47 | .88 | 1.63 | 99 | 1.5 | 10 | -22/-30 |
| | 2 | 277 | 53 | 0.20 | .88 | 1.66 | 98 | 1.5 | 10 | -22/-30 |
| | 1 | 120 | 31 | 0.26 | 1.08 | 3.48 | 99 | 1.5 | 10 | -22/-30 |
| | 1 | 277 | 31 | 0.12 | 1.08 | 3.48 | 96 | 1.5 | 10 | -22/-30 |
| F32T8/WM | 2 | 120 | 52 | 0.44 | .87 | 1.67 | 99 | 1.5 | 10 | -22/-30 |
| | 2 | 277 | 51 | 0.19 | .87 | 1.71 | 98 | 1.5 | 10 | -22/-30 |
| | 1 | 120 | 29 | 0.25 | 1.07 | 3.69 | 99 | 1.5 | 10 | -22/-30 |
| | 1 | 277 | 29 | 0.12 | 1.07 | 3.69 | 96 | 1.5 | 10 | -22/-30 |
| F28T8 | 2 | 120 | 48 | 0.40 | .85 | 1.77 | 99 | 1.5 | 10 | -22/-30 |
| | 2 | 277 | 47 | 0.17 | .85 | 1.81 | 98 | 1.5 | 10 | -22/-30 |
| | 1 | 120 | 27 | 0.24 | 1.05 | 3.89 | 99 | 1.5 | 10 | -22/-30 |
| | 1 | 277 | 27 | 0.11 | 1.05 | 3.89 | 95 | 1.5 | 10 | -22/-30 |
| F32T8/25W | 2 | 120 | 44 | 0.37 | .87 | 1.98 | 99 | 1.5 | 10 | -22/-30 |
| | 2 | 277 | 43 | 0.16 | .87 | 2.02 | 98 | 1.5 | 10 | -22/-30 |
| | 1 | 120 | 25 | 0.23 | .87 | 3.48 | 99 | 1.5 | 10 | -22/-30 |
| | 1 | 277 | 25 | 0.10 | .87 | 3.48 | 94 | 1.5 | 10 | -22/-30 |
| F25T8 | 2 | 120 | 44 | 0.38 | .87 | 1.98 | 99 | 1.5 | 10 | -22/-30 |
| | 2 | 277 | 44 | 0.16 | .87 | 1.98 | 98 | 1.5 | 10 | -22/-30 |
| | 1 | 120 | 26 | 0.23 | 1.09 | 4.19 | 99 | 1.5 | 10 | -22/-30 |
| | 1 | 277 | 26 | 0.11 | 1.09 | 4.19 | 94 | 1.5 | 10 | -22/-30 |
| F17T8 | 2 | 120 | 31 | 0.27 | .88 | 2.84 | 99 | 1.5 | 10 | -22/-30 |
| | 2 | 277 | 31 | 0.12 | .88 | 2.84 | 96 | 1.5 | 10 | -22/-30 |
| | 1 | 120 | 19 | 0.17 | 1.09 | 5.74 | 99 | 1.5 | 10 | -22/-30 |
| | 1 | 277 | 19 | 0.08 | 1.09 | 5.74 | 90 | 1.5 | 20 | -22/-30 |
| FE15T8 | 2 | 120 | 25 | 0.21 | .91 | 3.64 | 99 | 1.5 | 10 | -22/-30 |
| | 2 | 277 | 25 | 0.10 | .91 | 3.64 | 93 | 1.5 | 15 | -22/-30 |
| | 1 | 120 | 16 | 0.14 | .91 | 5.69 | 98 | 1.5 | 10 | -22/-30 |
| | 1 | 277 | 16 | 0.07 | .91 | 5.69 | 88 | 1.5 | 15 | -22/-30 |
| F25T12 | 2 | 120 | 46 | 0.39 | .93 | 2.02 | 99 | 1.5 | 10 | 0/-18 |
| | 2 | 277 | 46 | 0.17 | .93 | 2.02 | 98 | 1.5 | 10 | 0/-18 |
| | 1 | 120 | 27 | 0.24 | .93 | 3.44 | 99 | 1.5 | 10 | 0/-18 |
| | 1 | 277 | 27 | 0.11 | .93 | 3.44 | 95 | 1.5 | 10 | 0/-18 |

## Safety and Performance

UL Class P · UL Type 1 Outdoor · UL Type CC · UL Type HL · FCC – CLASS A Non-Consumer

# 72262 – GE232MAXP-L/ULTRA

## UltraMax® P-Series Instant Start Multi-Voltage High-Efficiency

2 or 1 – F32T8 120 to 277 "L" .77 BF UltraMax® P

- T8 Instant Start Ballasts For F17 (2ft), F25 (3ft), F32 (4ft), F40 (5ft) Lamps
- Energy-saving high-efficiency instant-start electronic ballast (>90%)
- Multi-voltage technology handles voltage from 120 to 277V
- UL Type CC Rating provides protection against arcing in electrical devices
- Anti-striation control for better light quality
- UL 55°C Ambient Temperature rating
- Cold temperature -22°F Minimum Starting Temperature

| General Characteristics | |
|---|---|
| Ballast Type | Electronic – High-Efficiency Multivolt Instant Start |
| Starting Method | Instant Start |
| Lamp Wiring | Parallel |
| Line Voltage Regulation(+/-) | 10% |
| Ambient Temperature (MAX) | 55°C (131°F) |
| Case Temperature (MAX) | 70°C (158°F) |
| Ballast Factor | Low |
| Power Factor Correction | Active |
| Sound Rating | A (20-24 decibels) |
| Enclosure Type | Metal |
| Additional Info | Anti-striation control, Auto-restart, Inherently Thermally Protected, UL Class P |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 50 Hz/60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 9.5 in (241 mm) |
| Width (W) | 1.3 in (33 mm) |
| Height (H) | 1.0 in (25.4 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 8.9 in (226 mm) |
| Mount Width (X or F) | 0.87 in (22 mm) |
| Mount Slots (MS) | 0.3 in (8 mm) |
| Weight | 0.7 lbs |
| Exit Type | Side |
| Remote Mounting Distance to Lamp (F32T8) | 18 ft |
| Remote Mounting Wire Gauge | 18 AWG |
| **Lead Lengths** | |
| Black | 25 in (635 mm) |
| White | 25 in (635 mm) |
| Blue | 31 in (787 mm) |
| Red | 37 in (940 mm) |

**Specifications and lamp wattage**

| Lamp | # of Lamps | Line Volts (V) | System Watts (W) | Nom. Line Current (A) | System Ballast Factor | Ballast Efficacy Factor | Power Factor % (>=) | Crest Factor (<=) | THD% (<=) | Min Starting Temp (°F/°C) |
|---|---|---|---|---|---|---|---|---|---|---|
| F32T8 | 2 | 120 | 48 | 0.42 | .78 | 1.63 | 99 | 1.5 | 10 | -22/-30 |
| | 2 | 277 | 48 | 0.19 | .78 | 1.63 | 98 | 1.5 | 10 | -22/-30 |
| | 1 | 120 | 30 | 0.24 | .96 | 3.20 | 99 | 1.5 | 10 | -22/-30 |
| | 1 | 277 | 30 | 0.11 | .96 | 3.20 | 95 | 1.5 | 10 | -22/-30 |
| F32T8/WM | 2 | 120 | 46 | 0.39 | .77 | 1.67 | 99 | 1.5 | 10 | -22/-30 |
| | 2 | 277 | 46 | 0.17 | .77 | 1.67 | 98 | 1.5 | 10 | -22/-30 |
| | 1 | 120 | 28 | 0.22 | .77 | 2.75 | 99 | 1.5 | 10 | -22/-30 |
| | 1 | 277 | 28 | 0.11 | .77 | 2.75 | 94 | 1.5 | 10 | -22/-30 |
| F28T8 | 2 | 120 | 43 | 0.36 | .77 | 1.79 | 99 | 1.5 | 10 | -22/-30 |
| | 2 | 277 | 42 | 0.16 | .77 | 1.83 | 97 | 1.5 | 10 | -22/-30 |
| | 1 | 120 | 26 | 0.21 | .77 | 2.96 | 99 | 1.5 | 10 | -22/-30 |
| | 1 | 277 | 26 | 0.10 | .77 | 2.96 | 94 | 1.5 | 10 | -22/-30 |
| F32T8/25W | 2 | 120 | 39 | 0.33 | .78 | 2.00 | 99 | 1.5 | 10 | -22/-30 |
| | 2 | 277 | 39 | 0.15 | .78 | 2.00 | 96 | 1.5 | 10 | -22/-30 |
| | 1 | 120 | 22 | 0.18 | .78 | 3.55 | 98 | 1.5 | 10 | -22/-30 |
| | 1 | 277 | 22 | 0.09 | .78 | 3.55 | 93 | 1.5 | 10 | -22/-30 |
| F25T8 | 2 | 120 | 40 | 0.34 | .78 | 1.95 | 99 | 1.5 | 10 | -22/-30 |
| | 2 | 277 | 40 | 0.15 | .78 | 1.95 | 96 | 1.5 | 10 | -22/-30 |
| | 1 | 120 | 23 | 0.21 | .96 | 4.17 | 99 | 1.5 | 10 | -22/-30 |
| | 1 | 277 | 24 | 0.10 | .96 | 4.00 | 93 | 1.5 | 15 | -22/-30 |
| F17T8 | 2 | 120 | 28 | 0.24 | .79 | 2.82 | 99 | 1.5 | 10 | -22/-30 |
| | 2 | 277 | 29 | 0.11 | .79 | 2.72 | 94 | 1.5 | 10 | -22/-30 |
| | 1 | 120 | 17 | 0.18 | .98 | 5.76 | 99 | 1.5 | 10 | -22/-30 |
| | 1 | 277 | 18 | 0.08 | .98 | 5.44 | 90 | 1.5 | 10 | -22/-30 |
| FE15T8 | 2 | 120 | 23 | 0.20 | .78 | 3.39 | 99 | 1.5 | 10 | -22/-30 |
| | 2 | 277 | 23 | 0.10 | .78 | 3.39 | 91 | 1.5 | 15 | -22/-30 |
| | 1 | 120 | 14 | 0.13 | .78 | 5.57 | 99 | 1.5 | 10 | -22/-30 |
| | 1 | 277 | 15 | 0.07 | .78 | 5.20 | 87 | 1.5 | 10 | -22/-30 |
| F25T12 | 2 | 120 | 42 | 0.35 | .80 | 1.90 | 99 | 1.5 | 10 | 0/-18 |
| | 2 | 277 | 41 | 0.15 | .80 | 1.95 | 97 | 1.5 | 10 | 0/-18 |
| | 1 | 120 | 24 | 0.21 | .80 | 3.33 | 99 | 1.5 | 10 | 0/-18 |
| | 1 | 277 | 24 | 0.10 | .80 | 3.33 | 95 | 1.5 | 10 | 0/-18 |

## Safety and Performance

c UL us LISTED · UL Class P · UL Type 1 Outdoor · UL Type CC · UL Type HL · FCC – CLASS A Non-Consumer

# 71723 – GE432MAXP-H/ULTRA

## UltraMax® P-Series Instant Start Multi-Voltage High-Efficiency

4 or 3 – F32T8 120 to 277 "H" 1.18 BF UltraMax® P

- T8 Instant Start Ballasts For F17 (2ft), F25 (3ft), F32 (4ft), F40 (5ft) Lamps
- Energy-saving high-efficiency instant-start electronic ballast (>90%)
- Multi-voltage technology handles voltage from 120 to 277V
- UL Type CC Rating provides protection against arcing in electrical devices
- Anti-striation control for better light quality
- UL 55°C Ambient Temperature rating
- Cold temperature -22°F Minimum Starting Temperature

| General Characteristics | |
|---|---|
| Ballast Type | Electronic – High-Efficiency Multivolt Instant Start |
| Starting Method | Instant Start |
| Lamp Wiring | Parallel |
| Line Voltage Regulation(+/-) | 10% |
| Ambient Temperature (MAX) | 55°C (131°F) |
| Case Temperature (MAX) | 90°C (194°F) |
| Ballast Factor | High |
| Power Factor Correction | Active |
| Sound Rating | A (20-24 decibels) |
| Enclosure Type | Metal |
| Additional Info | Anti-striation control, Auto-restart, Inherently Thermally Protected, UL Class P |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 50 Hz/60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 9.5 in (241 mm) |
| Width (W) | 1.7 in (43 mm) |
| Height (H) | 1.18 in (30 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 8.9 in (226 mm) |
| Mount Width (X or F) | 1.05 in (27 mm) |
| Mount Slots (MS) | 0.3 in (8 mm) |
| Weight | 1.4 lbs |
| Exit Type | Side |
| Remote Mounting Distance to Lamp (F32T8) | 18 ft |
| Remote Mounting Wire Gauge | 18 AWG |
| **Lead Lengths** | |
| Black | 25 in (635 mm) |
| White | 25 in (635 mm) |
| Blue | 31 in (787 mm) |
| Red | 39 in (991 mm) |

**Specifications and lamp wattage**

| Lamp | # of Lamps | Line Volts (V) | System Watts (W) | Nom. Line Current (A) | System Ballast Factor | Ballast Efficacy Factor | Power Factor % (>=) | Crest Factor (<=) | THD% (<=) | Min Starting Temp (°F/°C) |
|---|---|---|---|---|---|---|---|---|---|---|
| F32T8 | 4 | 120 | 148 | 1.30 | 1.18 | .80 | 99 | 1.4 | 10 | -22/-30 |
| | 4 | 277 | 146 | 0.55 | 1.18 | .81 | 98 | 1.4 | 10 | -22/-30 |
| | 3 | 120 | 119 | 1.07 | 1.28 | 1.08 | 99 | 1.4 | 10 | -22/-30 |
| | 3 | 277 | 117 | 0.46 | 1.28 | 1.09 | 97 | 1.4 | 15 | -22/-30 |
| F32T8/WM | 4 | 120 | 139 | 1.21 | 1.18 | .85 | 99 | 1.4 | 10 | 50/10 |
| | 4 | 277 | 136 | 0.51 | 1.18 | .87 | 97 | 1.4 | 10 | 50/10 |
| | 3 | 120 | 113 | 0.99 | 1.25 | 1.11 | 99 | 1.4 | 10 | 50/10 |
| | 3 | 277 | 112 | 0.41 | 1.25 | 1.12 | 97 | 1.4 | 16 | 50/10 |
| F28T8 | 4 | 120 | 127 | 1.10 | 1.18 | .93 | 99 | 1.4 | 10 | 50/10 |
| | 4 | 277 | 125 | 0.48 | 1.18 | .94 | 98 | 1.4 | 10 | 50/10 |
| | 3 | 120 | 105 | 0.91 | 1.24 | 1.18 | 99 | 1.4 | 10 | 50/10 |
| | 3 | 277 | 102 | 0.40 | 1.24 | 1.22 | 97 | 1.4 | 16 | 50/10 |
| F32T8/25W | 4 | 120 | 120 | 1.06 | 1.18 | .98 | 99 | 1.4 | 10 | 60/16 |
| | 4 | 277 | 116 | 0.45 | 1.18 | 1.02 | 98 | 1.4 | 10 | 60/16 |
| | 3 | 120 | 99 | 0.88 | 1.24 | 1.25 | 99 | 1.4 | 10 | 60/16 |
| | 3 | 277 | 95 | 0.38 | 1.24 | 1.31 | 97 | 1.4 | 10 | 60/16 |
| F25T8 | 4 | 120 | 119 | 0.45 | 1.16 | .97 | 97 | 1.4 | 10 | -22/-30 |
| | 4 | 277 | 121 | 1.06 | 1.16 | .96 | 99 | 1.4 | 10 | -22/-30 |
| | 3 | 120 | 101 | 0.87 | 1.27 | 1.26 | 99 | 1.4 | 10 | -22/-30 |
| | 3 | 277 | 100 | 0.38 | 1.27 | 1.27 | 96 | 1.4 | 17 | -22/-30 |
| F17T8 | 4 | 120 | 79 | 0.62 | 1.16 | 1.47 | 99 | 1.4 | 10 | -22/-30 |
| | 4 | 277 | 78 | 0.31 | 1.16 | 1.49 | 96 | 1.4 | 10 | -22/-30 |
| | 3 | 120 | 62 | 0.57 | 1.25 | 2.02 | 99 | 1.4 | 10 | -22/-30 |
| | 3 | 277 | 62 | 0.27 | 1.25 | 2.02 | 95 | 1.4 | 21 | -22/-30 |
| FE15T8 | 4 | 120 | 62 | 0.54 | 1.03 | 1.66 | 99 | 1.4 | 10 | 0/-18 |
| | 4 | 277 | 62 | 0.26 | 1.03 | 1.66 | 95 | 1.4 | 20 | 0/-18 |
| | 3 | 120 | 51 | 0.45 | 1.12 | 2.20 | 99 | 1.4 | 10 | 0/-18 |
| | 3 | 277 | 52 | 0.22 | 1.12 | 2.15 | 92 | 1.4 | 20 | 0/-18 |
| F40T8 | 3 | 120 | 146 | 1.27 | 1.22 | .84 | 99 | 1.4 | 10 | -22/-30 |
| | 3 | 277 | 142 | 0.54 | 1.22 | .86 | 97 | 1.4 | 14 | -22/-30 |
| F25T12 | 4 | 120 | 125 | 1.10 | 1.11 | .89 | 99 | 1.4 | 10 | 0/-18 |
| | 4 | 277 | 122 | 0.47 | 1.11 | .91 | 97 | 1.4 | 14 | 0/-18 |
| | 3 | 120 | 101 | 0.90 | 1.22 | 1.21 | 99 | 1.4 | 10 | 0/-18 |
| | 3 | 277 | 100 | 0.39 | 1.22 | 1.22 | 97 | 1.4 | 17 | 0/-18 |

Safety and Performance UL Class P UL Type 1 Outdoor UL Type CC UL Type HL FCC – CLASS A Non-Consumer

# 78627 – GE432MAXP-N/ULTRA

## UltraMax® P-Series Instant Start Multi-Voltage High-Efficiency

4 or 3 – F32T8 120 to 277 "N" .87 BF UltraMax® P

- T8 Instant Start Ballasts For F17 (2ft), F25 (3ft), F32 (4ft), F40 (5ft) Lamps
- Energy-saving high-efficiency instant-start electronic ballast (>90%)
- Multi-voltage technology handles voltage from 120 to 277V
- UL Type CC Rating provides protection against arcing in electrical devices
- Anti-striation control for better light quality
- UL 55°C Ambient Temperature rating
- Cold temperature -22°F Minimum Starting Temperature

| General Characteristics | |
|---|---|
| Ballast Type | Electronic – High-Efficiency Multivolt Instant Start |
| Starting Method | Instant Start |
| Lamp Wiring | Parallel |
| Line Voltage Regulation(+/-) | 10% |
| Ambient Temperature (MAX) | 55°C (131°F) |
| Case Temperature (MAX) | 70°C (158°F) |
| Ballast Factor | Normal |
| Power Factor Correction | Active |
| Sound Rating | A (20-24 decibels) |
| Enclosure Type | Metal |
| Additional Info | Anti-striation control, Auto-restart, Inherently Thermally Protected, UL Class P |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 50 Hz/60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 9.5 in (241 mm) |
| Width (W) | 1.3 in (33 mm) |
| Height (H) | 1.0 in (25.4 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 8.9 in (226 mm) |
| Mount Width (X or F) | 0.87 in (22 mm) |
| Mount Slots (MS) | 0.3 in (8 mm) |
| Weight | 0.9 lbs |
| Exit Type | Side |
| Remote Mounting Distance to Lamp (F32T8) | 18 ft |
| Remote Mounting Wire Gauge | 18 AWG |
| **Lead Lengths** | |
| Black | 25 in (635 mm) |
| White | 25 in (635 mm) |
| Red & Blue | 31 in (787 mm) |
| Yellow | 39 in (991 mm) |

**Specifications and lamp wattage**

| Lamp | # of Lamps | Line Volts (V) | System Watts (W) | Nom. Line Current (A) | System Ballast Factor | Ballast Efficacy Factor | Power Factor % (>=) | Crest Factor (<=) | THD% (<=) | Min Starting Temp (°F/°C) |
|---|---|---|---|---|---|---|---|---|---|---|
| F32T8 | 4 | 120 | 110 | 0.93 | .88 | .80 | 99 | 1.5 | 10 | -22/-30 |
| | 4 | 277 | 108 | 0.4 | .88 | .81 | 98 | 1.5 | 10 | -22/-30 |
| | 3 | 120 | 92 | 0.78 | .96 | 1.04 | 99 | 1.5 | 10 | -22/-30 |
| | 3 | 277 | 91 | 0.34 | .96 | 1.05 | 98 | 1.5 | 10 | -22/-30 |
| F32T8/WM | 4 | 120 | 103 | 0.87 | .88 | .85 | 99 | 1.5 | 10 | -22/-30 |
| | 4 | 277 | 101 | 0.37 | .88 | .87 | 98 | 1.5 | 10 | -22/-30 |
| | 3 | 120 | 85 | 0.73 | .97 | 1.14 | 99 | 1.5 | 10 | -22/-30 |
| | 3 | 277 | 84 | 0.31 | .97 | 1.15 | 98 | 1.5 | 10 | -22/-30 |
| F28T8 | 4 | 120 | 94 | 0.80 | .84 | .89 | 99 | 1.5 | 10 | -22/-30 |
| | 4 | 277 | 92 | 0.34 | .84 | .91 | 98 | 1.5 | 10 | -22/-30 |
| | 3 | 120 | 77 | 0.66 | .93 | 1.21 | 99 | 1.5 | 10 | -22/-30 |
| | 3 | 277 | 76 | 0.29 | .93 | 1.22 | 98 | 1.5 | 10 | -22/-30 |
| F32T8/25W | 4 | 120 | 87 | 0.73 | .87 | 1.00 | 99 | 1.5 | 10 | -22/-30 |
| | 4 | 277 | 87 | 0.32 | .87 | 1.00 | 98 | 1.5 | 10 | -22/-30 |
| | 3 | 120 | 72 | 0.60 | .89 | 1.24 | 99 | 1.5 | 10 | -22/-30 |
| | 3 | 277 | 71 | 0.26 | .89 | 1.25 | 97 | 1.5 | 10 | -22/-30 |
| F25T8 | 4 | 120 | 89 | 0.74 | .86 | .97 | 99 | 1.5 | 10 | -22/-30 |
| | 4 | 277 | 88 | 0.32 | .86 | .98 | 98 | 1.5 | 10 | -22/-30 |
| | 3 | 120 | 74 | 0.62 | .97 | 1.31 | 99 | 1.5 | 10 | -22/-30 |
| | 3 | 277 | 73 | 0.27 | .97 | 1.33 | 97 | 1.5 | 10 | -22/-30 |
| F17T8 | 4 | 120 | 61 | 0.53 | .89 | 1.46 | 99 | 1.5 | 10 | -22/-30 |
| | 4 | 277 | 61 | 0.23 | .89 | 1.46 | 97 | 1.5 | 10 | -22/-30 |
| | 3 | 120 | 51 | 0.44 | .99 | 1.94 | 99 | 1.5 | 10 | -22/-30 |
| | 3 | 277 | 51 | 0.20 | .99 | 1.94 | 96 | 1.5 | 10 | -22/-30 |
| FE15T8 | 4 | 120 | 48 | 0.42 | .77 | 1.60 | 99 | 1.5 | 10 | -22/-30 |
| | 4 | 277 | 48 | 0.19 | .77 | 1.60 | 96 | 1.5 | 10 | -22/-30 |
| | 3 | 120 | 41 | 0.35 | .85 | 2.07 | 99 | 1.5 | 10 | -22/-30 |
| | 3 | 277 | 40 | 0.17 | .85 | 2.13 | 94 | 1.5 | 10 | -22/-30 |
| F25T12 | 4 | 120 | 91 | 0.78 | .79 | .87 | 99 | 1.5 | 10 | 0/-18 |
| | 4 | 277 | 90 | 0.33 | .79 | .88 | 98 | 1.5 | 10 | 0/-18 |
| | 3 | 120 | 76 | 0.65 | .87 | 1.14 | 99 | 1.5 | 10 | 0/-18 |
| | 3 | 277 | 75 | 0.28 | .87 | 1.16 | 98 | 1.5 | 10 | 0/-18 |

## Safety and Performance

c UL us LISTED · UL Class P · UL Type 1 Outdoor · UL Type CC · UL Type HL · FCC – CLASS A Non-Consumer

# 78625 – GE432MAXP-L/ULTRA

## UltraMax® P-Series Instant Start Multi-Voltage High-Efficiency

4 or 3 – F32T8 120 to 277 "L" .77 BF UltraMax® P

- T8 Instant Start Ballasts For F17 (2ft), F25 (3ft), F32 (4ft), F40 (5ft) Lamps
- Energy-saving high-efficiency instant-start electronic ballast (>90%)
- Multi-voltage technology handles voltage from 120 to 277V
- UL Type CC Rating provides protection against arcing in electrical devices
- Anti-striation control for better light quality
- UL 55°C Ambient Temperature rating
- Cold temperature -22°F Minimum Starting Temperature

| General Characteristics | |
|---|---|
| Ballast Type | Electronic – High-Efficiency Multivolt Instant Start |
| Starting Method | Instant Start |
| Lamp Wiring | Parallel |
| Line Voltage Regulation(+/-) | 10% |
| Ambient Temperature (MAX) | 55°C (131°F) |
| Case Temperature (MAX) | 70°C (158°F) |
| Ballast Factor | Low |
| Power Factor Correction | Active |
| Sound Rating | A (20-24 decibels) |
| Enclosure Type | Metal |
| Additional Info | Anti-striation control, Auto-restart, Inherently Thermally Protected, UL Class P |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 50 Hz/60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 9.5 in (241 mm) |
| Width (W) | 1.3 in (33 mm) |
| Height (H) | 1.0 in (25.4 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 8.9 in (226 mm) |
| Mount Width (X or F) | 0.87 in (22 mm) |
| Mount Slots (MS) | 0.3 in (8 mm) |
| Weight | 0.9 lbs |
| Exit Type | Side |
| Remote Mounting Distance to Lamp (F32T8) | 18 ft |
| Remote Mounting Wire Gauge | 18 AWG |
| **Lead Lengths** | |
| Black | 25 in (635 mm) |
| White | 25 in (635 mm) |
| Red & Blue | 31 in (787 mm) |
| Yellow | 39 in (991 mm) |

**Specifications and lamp wattage**

| Lamp | # of Lamps | Line Volts (V) | System Watts (W) | Nom. Line Current (A) | System Ballast Factor | Ballast Efficacy Factor | Power Factor % (>=) | Crest Factor (<=) | THD% (<=) | Min Starting Temp (°F/°C) |
|---|---|---|---|---|---|---|---|---|---|---|
| F32T8 | 4 | 120 | 98 | 0.82 | .78 | .80 | 99 | 1.5 | 10 | -22/-30 |
| | 4 | 277 | 96 | 0.35 | .78 | .81 | 98 | 1.5 | 10 | -22/-30 |
| | 3 | 120 | 84 | 0.72 | .88 | 1.05 | 99 | 1.5 | 10 | -22/-30 |
| | 3 | 277 | 83 | 0.31 | .88 | 1.06 | 98 | 1.5 | 10 | -22/-30 |
| F32T8/WM | 4 | 120 | 92 | 0.79 | .76 | .83 | 99 | 1.5 | 10 | -22/-30 |
| | 4 | 277 | 91 | 0.34 | .76 | .84 | 98 | 1.5 | 10 | -22/-30 |
| | 3 | 120 | 77 | 0.66 | .83 | 1.08 | 99 | 1.5 | 10 | -22/-30 |
| | 3 | 277 | 76 | 0.28 | .83 | 1.09 | 97 | 1.5 | 10 | -22/-30 |
| F28T8 | 4 | 120 | 85 | 0.72 | .75 | .88 | 99 | 1.5 | 10 | -22/-30 |
| | 4 | 277 | 84 | 0.31 | .75 | .89 | 98 | 1.5 | 10 | -22/-30 |
| | 3 | 120 | 68 | 0.59 | .81 | 1.19 | 99 | 1.5 | 10 | -22/-30 |
| | 3 | 277 | 67 | 0.26 | .81 | 1.21 | 97 | 1.5 | 10 | -22/-30 |
| F32T8/25W | 4 | 120 | 78 | 0.66 | .77 | .99 | 99 | 1.5 | 10 | -22/-30 |
| | 4 | 277 | 77 | 0.29 | .77 | 1.00 | 98 | 1.5 | 10 | -22/-30 |
| | 3 | 120 | 62 | 0.52 | .81 | 1.31 | 99 | 1.5 | 10 | -22/-30 |
| | 3 | 277 | 61 | 0.22 | .81 | 1.33 | 97 | 1.5 | 10 | -22/-30 |
| F25T8 | 4 | 120 | 80 | 0.67 | .76 | .95 | 99 | 1.5 | 10 | -22/-30 |
| | 4 | 277 | 79 | 0.29 | .76 | .96 | 98 | 1.5 | 10 | -22/-30 |
| | 3 | 120 | 66 | 0.55 | .84 | 1.27 | 99 | 1.5 | 10 | -22/-30 |
| | 3 | 277 | 65 | 0.25 | .84 | 1.29 | 97 | 1.5 | 15 | -22/-30 |
| F17T8 | 4 | 120 | 56 | 0.47 | .79 | 1.41 | 99 | 1.5 | 10 | -22/-30 |
| | 4 | 277 | 56 | 0.21 | .79 | 1.41 | 96 | 1.5 | 10 | -22/-30 |
| | 3 | 120 | 47 | 0.40 | .86 | 1.83 | 99 | 1.5 | 10 | -22/-30 |
| | 3 | 277 | 47 | 0.18 | .86 | 1.83 | 95 | 1.5 | 15 | -22/-30 |
| FE15T8 | 4 | 120 | 44 | 0.38 | .76 | 1.73 | 99 | 1.5 | 10 | -22/-30 |
| | 4 | 277 | 44 | 0.18 | .76 | 1.73 | 95 | 1.5 | 10 | -22/-30 |
| | 3 | 120 | 36 | 0.32 | .76 | 2.11 | 99 | 1.5 | 10 | -22/-30 |
| | 3 | 277 | 37 | 0.15 | .76 | 2.05 | 93 | 1.5 | 15 | -22/-30 |
| F25T12 | 4 | 120 | 81 | 0.69 | .76 | .94 | 99 | 1.5 | 10 | 0/-18 |
| | 4 | 277 | 81 | 0.30 | .76 | .94 | 98 | 1.5 | 10 | 0/-18 |
| | 3 | 120 | 68 | 0.58 | .76 | 1.12 | 99 | 1.5 | 10 | 0/-18 |
| | 3 | 277 | 67 | 0.25 | .76 | 1.13 | 97 | 1.5 | 10 | 0/-18 |

## Safety and Performance

UL Class P · UL Type 1 Outdoor · UL Type CC · UL Type HL · FCC – CLASS A Non-Consumer

## 49767 – GE259MAXP-N/ULTRA

### UltraMax® P-Series Instant Start Multi-Voltage High-Efficiency

2 or 1 – F96T8 120 to 277 "N" .87 BF UltraMax® P

- T8 Instant Start Ballasts For 46-59W 4ft-8ft Slimline Lamps
- Energy-saving high-efficiency instant-start electronic ballast (>90%)
- Multi-voltage technology handles voltage from 120 to 277V
- Anti-striation control for better light quality
- Cold temperature 0°F Minimum Starting Temperature

| General Characteristics | |
|---|---|
| Ballast Type | Electronic – High-Efficiency Multivolt Instant Start |
| Starting Method | Instant Start |
| Lamp Wiring | Parallel |
| Line Voltage Regulation(+/-) | 10% |
| Ambient Temperature (MAX) | 40°C (104°F) |
| Case Temperature (MAX) | 70°C (158°F) |
| Ballast Factor | Normal |
| Power Factor Correction | Active |
| Sound Rating | A (20-24 decibels) |
| Enclosure Type | Metal |
| Additional Info | Anti-striation control, Auto-restart, Inherently Thermally Protected, UL Class P |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 50 Hz/60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 9.5 in (241 mm) |
| Width (W) | 1.3 in (33 mm) |
| Height (H) | 1.18 in (30 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 8.9 in (226 mm) |
| Mount Width (X or F) | 0.87 in (22 mm) |
| Mount Slots (MS) | 0.3 in (8 mm) |
| Weight | 1.4 lbs |
| Exit Type | Side |
| Remote Mounting Distance to Lamp (F32T8) | 18 ft |
| Remote Mounting Wire Gauge | 18 AWG |
| **Lead Lengths** | |
| Black | 22 in (559 mm) |
| White | 22 in (559 mm) |
| Blue | 46 in (1168 mm) |
| Red | 78 in (1981 mm) |

**Specifications and lamp wattage**

| Lamp | # of Lamps | Line Volts (V) | System Watts (W) | Nom. Line Current (A) | System Ballast Factor | Ballast Efficacy Factor | Power Factor % (>=) | Crest Factor (<=) | THD% (<=) | Min Starting Temp (°F/°C) |
|---|---|---|---|---|---|---|---|---|---|---|
| F96T8 | 2 | 120 | 107 | 0.91 | .87 | .81 | 99 | 1.7 | 10 | 0/-18 |
| | 2 | 277 | 105 | 0.4 | .87 | .83 | 98 | 1.7 | 15 | 0/-18 |
| | 1 | 120 | 62 | 0.53 | .87 | 1.40 | 99 | 1.7 | 10 | 0/-18 |
| | 1 | 277 | 62 | 0.24 | .87 | 1.40 | 97 | 1.7 | 20 | 0/-18 |
| F96T8/WM | 2 | 120 | 102 | 0.87 | .87 | .85 | 99 | 1.7 | 10 | 50/10 |
| | 2 | 277 | 100 | 0.38 | .87 | .87 | 98 | 1.7 | 15 | 50/10 |
| | 1 | 120 | 59 | 0.5 | .87 | 1.47 | 99 | 1.7 | 10 | 50/10 |
| | 1 | 277 | 59 | 0.23 | .87 | 1.47 | 97 | 1.7 | 20 | 50/10 |
| F96T8/WMP | 2 | 120 | 85 | 0.78 | .89 | 1.05 | 99 | 1.7 | 10 | 50/10 |
| | 2 | 277 | 84 | 0.32 | .89 | 1.06 | 98 | 1.7 | 15 | 50/10 |
| | 1 | 120 | 59 | 0.5 | .87 | 1.47 | 99 | 1.7 | 10 | 50/10 |
| | 1 | 277 | 59 | 0.23 | .87 | 1.47 | 97 | 1.7 | 20 | 50/10 |
| F72T8 | 2 | 120 | 79 | 0.72 | .89 | 1.13 | 99 | 1.7 | 10 | 0/-18 |
| | 2 | 277 | 78 | 0.29 | .89 | 1.14 | 98 | 1.7 | 13 | 0/-18 |
| | 1 | 120 | 44 | 0.39 | .87 | 1.98 | 99 | 1.7 | 10 | 0/-18 |
| | 1 | 277 | 44 | 0.17 | .87 | 1.98 | 96 | 1.7 | 20 | 0/-18 |

Safety and Performance c UL us LISTED UL Class P UL Type 1 Outdoor UL Type HL FCC – CLASS A Non-Consumer

# 74109 – GE232MAXP347-H

## UltraMax® P-Series
## 347V High-Efficiency

2 or 1 – F32T8 347V "H" 1.18 BF UltraMax® P

- T8 Instant Start Ballasts
- Energy-saving high-efficiency instant-start electronic ballast (>90%)
- Instant start ballast for long lamp starting cycles and low initial cost
- Anti-striation control for better light quality
- Cold temperature -22°F Minimum Starting Temperature
- Parallel lamp operation means system maintenance is easier to manage

| General Characteristics | |
|---|---|
| Ballast Type | Electronic – High-Efficiency Instant Start |
| Starting Method | Instant Start |
| Lamp Wiring | Parallel |
| Line Voltage Regulation(+/-) | 10% |
| Ambient Temperature (MAX) | 40°C (104°F) |
| Case Temperature (MAX) | 70°C (158°F) |
| Ballast Factor | High |
| Power Factor Correction | Active |
| Sound Rating | A (20-24 decibels) |
| Enclosure Type | Metal |
| Additional Info | Anti-striation control, Auto-restart, Inherently Thermally Protected, UL Class P |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 9.5 in (241 mm) |
| Width (W) | 1.3 in (33 mm) |
| Height (H) | 1.18 in (30 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 8.9 in (226 mm) |
| Mount Width (X or F) | 0.87 in (22 mm) |
| Mount Slots (MS) | 0.3 in (8 mm) |
| Weight | 1.04 lbs |
| Exit Type | Side |
| Remote Mounting Distance to Lamp (F32T8) | 18 ft |
| Remote Mounting Wire Gauge | 18 AWG |
| **Lead Lengths** | |
| Black | 25 in (635 mm) |
| White | 25 in (635 mm) |
| Blue | 31 in (787 mm) |
| Red | 45 in (1143 mm) |

**Specifications and lamp wattage**

| Lamp | # of Lamps | Line Volts (V) | System Watts (W) | Nom. Line Current (A) | System Ballast Factor | Ballast Efficacy Factor | Power Factor % (>=) | Crest Factor (<=) | THD% (<=) | Min Starting Temp (°F/°C) |
|---|---|---|---|---|---|---|---|---|---|---|
| F32T8 | 2 | 347 | 70 | 0.20 | 1.18 | 1.69 | 99 | 1.7 | 10 | -22/-30 |
| | 1 | 347 | 44 | 0.13 | 1.32 | 3.00 | 99 | 1.7 | 10 | -22/-30 |
| F32T8/WM | 2 | 347 | 67 | 0.19 | 1.15 | 1.72 | 99 | 1.7 | 10 | 60/16 |
| | 1 | 347 | 42 | 0.12 | 1.29 | 3.07 | 99 | 1.7 | 10 | 60/16 |
| F28T8 | 2 | 347 | 63 | 0.12 | 1.30 | 2.06 | 99 | 1.7 | 17 | 60/16 |
| | 1 | 347 | 39 | 0.18 | 1.30 | 3.33 | 99 | 1.7 | 17 | 60/16 |
| F32T8/25W | 2 | 347 | 56 | 0.16 | 1.12 | 2.00 | 99 | 1.7 | 10 | 60/16 |
| F25T8 | 2 | 347 | 55 | 0.16 | 1.16 | 2.11 | 99 | 1.7 | 10 | -22/-30 |
| | 1 | 347 | 36 | 0.11 | 1.32 | 3.67 | 99 | 1.7 | 30 | -22/-30 |
| F25T8/WM | 2 | 347 | 47 | 0.14 | 1.16 | 2.47 | 98 | 1.7 | 10 | 60/16 |
| F17TB | 2 | 347 | 37 | 0.11 | 1.10 | 2.97 | 97 | 1.7 | 12 | -22/-30 |
| | 1 | 347 | 23 | 0.08 | 1.25 | 5.43 | 87 | 1.7 | 52 | -22/-30 |
| F17T8/WM | 2 | 347 | 31 | 0.10 | 1.10 | 3.55 | 97 | 1.7 | 12 | 60/16 |
| FE15T8 | 2 | 347 | 30 | 0.09 | 1.00 | 3.33 | 94 | 1.7 | 30 | -22/-30 |
| | 1 | 347 | 19 | 0.07 | 1.15 | 6.05 | 82 | 1.7 | 55 | -22/-30 |
| F17T8/WM | 2 | 347 | 53 | 0.16 | 1.24 | 2.34 | 99 | 1.7 | 10 | -22/-30 |
| FE15T8 | 2 | 347 | 61 | 0.18 | 1.23 | 2.02 | 99 | 1.7 | 10 | -22/-30 |
| | 1 | 347 | 39 | 0.12 | 1.45 | 3.72 | 95 | 1.7 | 20 | -22/-30 |

## Safety and Performance

c UL us LISTED · UL Class P · UL Type 1 Outdoor · UL Type HL · ICES-005 for EMI and RFI FCC – CLASS A Non-Consumer

ANSI - C82.11 - Cons 2002, ANSI - C62.41 - 1991

## 72275 – GE232MAX-G-N (Replaces GE-232-MV-N)

### UltraMax® G-Series Instant Start Multivolt 120V-277V

2 or 1 – F32T8 120 to 277 "N" .87 BF Multivolt UltraMax® G

- For F17 (2ft), F25 (3ft), F32 (4ft), F40 (5ft) Lamps
- High-performance electronic ballast for all general fluorescent applications
- Instant start electronic ballast for long lamp starting cycles and low initial cost
- Multi-voltage technology handles voltage from 120 to 277V
- Parallel lamp operation means system maintenance is easier to manage
- Anti-striation control for better light quality
- Cold temperature -22°F Minimum Starting Temperature

| General Characteristics | |
|---|---|
| Ballast Type | Electronic – Multivolt Instant Start |
| Starting Method | Instant Start |
| Lamp Wiring | Parallel |
| Line Voltage Regulation(+/-) | 10% |
| Ambient Temperature (MAX) | 40°C (104°F) |
| Case Temperature (MAX) | 70°C (158°F) |
| Ballast Factor | Normal |
| Power Factor Correction | Active |
| Sound Rating | A (20-24 decibels) |
| Enclosure Type | Metal |
| Additional Info | Anti-striation control, Auto-restart, Inherently Thermally Protected, UL Class P |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 50 Hz/60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 9.5 in (241 mm) |
| Width (W) | 1.3 in (33 mm) |
| Height (H) | 1.18 in (30 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 8.9 in (226 mm) |
| Mount Width (X or F) | 0.87 in (22 mm) |
| Mount Slots (MS) | 0.3 in (8 mm) |
| Weight | 1.06 lbs |
| Exit Type | Side |
| Remote Mounting Distance to Lamp (F32T8) | 18 ft |
| Remote Mounting Wire Gauge | 18 AWG |
| **Lead Lengths** | |
| Black | 25 in (635 mm) |
| White | 25 in (635 mm) |
| Blue | 31 in (787 mm) |
| Red | 45 in (1143 mm) |

**Specifications and lamp wattage**

| Lamp | # of Lamps | Line Volts (V) | System Watts (W) | Nom. Line Current (A) | System Ballast Factor | Ballast Efficacy Factor | Power Factor % (>=) | Crest Factor (<=) | THD% (<=) | Min Starting Temp (°F/°C) |
|---|---|---|---|---|---|---|---|---|---|---|
| F32T8 | 2 | 120 | 57 | 0.48 | .88 | 1.54 | 99 | 1.7 | 10 | -22/-30 |
| | 2 | 277 | 55 | 0.2 | .88 | 1.60 | 98 | 1.7 | 10 | -22/-30 |
| | 1 | 120 | 35 | 0.3 | 1.08 | 3.09 | 99 | 1.7 | 10 | -22/-30 |
| | 1 | 277 | 35 | 0.13 | 1.08 | 3.09 | 97 | 1.7 | 10 | -22/-30 |
| F32T8/WM | 2 | 120 | 53 | 0.44 | .86 | 1.62 | 99 | 1.7 | 10 | 60/16 |
| | 2 | 277 | 51 | 0.19 | .87 | 1.71 | 97 | 1.7 | 10 | 60/16 |
| | 1 | 120 | 33 | 0.28 | 1.05 | 3.18 | 99 | 1.7 | 10 | 60/16 |
| | 1 | 277 | 33 | 0.12 | 1.05 | 3.18 | 96 | 1.7 | 10 | 60/16 |
| F28T8 | 2 | 120 | 47 | 0.39 | .83 | 1.77 | 99 | 1.7 | 10 | 60/16 |
| | 2 | 277 | 47 | 0.17 | .83 | 1.77 | 97 | 1.7 | 10 | 60/16 |
| | 1 | 120 | 31 | 0.26 | 1.02 | 3.29 | 99 | 1.7 | 10 | 60/16 |
| | 1 | 277 | 31 | 0.11 | .02 | .06 | 95 | 1.7 | 10 | 60/16 |
| F32T8/25W | 2 | 120 | 43 | 0.36 | .83 | 1.93 | 99 | 1.7 | 10 | 60/16 |
| | 2 | 277 | 43 | 0.16 | .83 | 1.93 | 97 | 1.7 | 10 | 60/16 |
| | 1 | 120 | 28 | 0.24 | 1.02 | 3.64 | 99 | 1.7 | 10 | 60/16 |
| | 1 | 277 | 28 | 0.10 | 1.02 | 3.64 | 98 | 1.7 | 10 | 60/16 |
| F25T8 | 2 | 120 | 44 | 0.37 | .90 | 2.05 | 99 | 1.7 | 10 | -22/-30 |
| | 2 | 277 | 44 | 0.16 | .91 | 2.07 | 97 | 1.7 | 10 | -22/-30 |
| | 1 | 120 | 28 | 0.23 | 1.08 | 3.86 | 99 | 1.7 | 10 | -22/-30 |
| | 1 | 277 | 28 | 0.11 | 1.08 | 3.86 | 95 | 1.7 | 10 | -22/-30 |
| F17T8 | 2 | 120 | 31 | 0.26 | .88 | 2.84 | 99 | 1.7 | 10 | -22/-30 |
| | 2 | 277 | 31 | 0.12 | .88 | 2.84 | 95 | 1.7 | 10 | -22/-30 |
| | 1 | 120 | 20 | 0.17 | 1.05 | 5.25 | 99 | 1.7 | 10 | -22/-30 |
| | 1 | 277 | 21 | 0.08 | 1.05 | 5.00 | 92 | 1.7 | 14 | -22/-30 |
| F40T8 | 1 | 120 | 44 | 0.37 | 1.08 | 2.45 | 99 | 1.7 | 10 | 0/-18 |
| | 1 | 277 | 43 | 0.16 | 1.08 | 2.51 | 96 | 1.7 | 10 | 0/-18 |

## Safety and Performance

c UL us LISTED · UL Class P · UL Type 1 Outdoor · UL Type HL · FCC – CLASS A Non-Consumer

# 74463 – GE432MAX-G-N (Replaces GE432MV-N)

## UltraMax® G-Series T8
## Multivolt 120V-277V

4 or 3 – F32T8 120 to 277 "N" .87 BF Multivolt UltraMax® G

- For F17 (2ft), F25 (3ft), F32 (4ft), F40 (5ft) Lamps
- High-performance electronic ballast for all general fluorescent applications
- Instant start electronic ballast for long lamp starting cycles and low initial cost
- Multi-voltage technology handles voltage from 120 to 277V
- Parallel lamp operation means system maintenance is easier to manage
- Anti-striation control for better light quality
- Cold temperature -22°F Minimum Starting Temperature

| General Characteristics | |
|---|---|
| Ballast Type | Electronic – Multivolt Instant Start |
| Starting Method | Instant Start |
| Lamp Wiring | Parallel |
| Line Voltage Regulation(+/-) | 10% |
| Ambient Temperature (MAX) | 40°C (104°F) |
| Case Temperature (MAX) | 70°C (158°F) |
| Ballast Factor | Normal |
| Power Factor Correction | Active |
| Sound Rating | A (20-24 decibels) |
| Enclosure Type | Metal |
| Additional Info | Anti-striation control, Auto-restart, Inherently Thermally Protected, UL Class P |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 50 Hz/60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 9.5 in (241 mm) |
| Width (W) | 1.3 in (33 mm) |
| Height (H) | 1.18 in (30 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 8.9 in (226 mm) |
| Mount Width (X or F) | 0.87 in (22 mm) |
| Mount Slots (MS) | 0.3 in (8 mm) |
| Weight | 1.40 lbs |
| Exit Type | Side |
| Remote Mounting Distance to Lamp (F32T8) | 18 ft |
| Remote Mounting Wire Gauge | 18 AWG |
| **Lead Lengths** | |
| Black | 25 in (635 mm) |
| White | 25 in (635 mm) |
| Red & Blue | 31 in (787 mm) |
| Yellow | 47 in (1194 mm) |

**Specifications and lamp wattage**

| Lamp | # of Lamps | Line Volts (V) | System Watts (W) | Nom. Line Current (A) | System Ballast Factor | Ballast Efficacy Factor | Power Factor % (>=) | Crest Factor (<=) | THD% (<=) | Min Starting Temp (°F/°C) |
|---|---|---|---|---|---|---|---|---|---|---|
| F32T8 | 4 | 120 | 113 | 0.99 | .88 | .78 | 99 | 1.7 | 10 | -22/-30 |
| | 4 | 277 | 110 | 0.43 | .88 | .80 | 98 | 1.7 | 10 | -22/-30 |
| | 3 | 120 | 93 | 0.83 | .93 | 1.00 | 99 | 1.7 | 10 | -22/-30 |
| | 3 | 277 | 92 | 0.36 | .93 | 1.01 | 98 | 1.7 | 10 | -22/-30 |
| F32T8/WM | 4 | 120 | 103 | 0.90 | .83 | .81 | 99 | 1.7 | 10 | 60/16 |
| | 4 | 277 | 103 | 0.40 | .83 | .81 | 98 | 1.7 | 10 | 60/16 |
| | 3 | 120 | 87 | 0.77 | .91 | 1.05 | 99 | 1.7 | 10 | 60/16 |
| | 3 | 277 | 86 | 0.33 | .91 | 1.06 | 98 | 1.7 | 10 | 60/16 |
| F28T8 | 4 | 120 | 93 | 0.83 | .82 | .88 | 99 | 1.7 | 10 | 60/16 |
| | 4 | 277 | 92 | 0.36 | .82 | .89 | 98 | 1.7 | 10 | 60/16 |
| | 3 | 120 | 77 | 0.68 | .85 | 1.10 | 99 | 1.7 | 10 | 60/16 |
| | 3 | 277 | 77 | 0.30 | .85 | 1.10 | 98 | 1.7 | 10 | 60/16 |
| F32T8/25W | 4 | 120 | 88 | 0.74 | .80 | .91 | 99 | 1.7 | 10 | 60/16 |
| | 4 | 277 | 87 | 0.32 | .80 | .92 | 98 | 1.7 | 15 | 60/16 |
| | 3 | 120 | 73 | 0.61 | .85 | 1.16 | 99 | 1.7 | 10 | 60/16 |
| | 3 | 277 | 73 | 0.27 | .85 | 1.16 | 97 | 1.7 | 16 | 60/16 |
| F25T8 | 4 | 120 | 88 | 0.77 | .87 | .99 | 99 | 1.7 | 10 | -22/-30 |
| | 4 | 277 | 86 | 0.34 | .87 | 1.01 | 98 | 1.7 | 10 | -22/-30 |
| | 3 | 120 | 73 | 0.64 | .93 | 1.27 | 99 | 1.7 | 10 | -22/-30 |
| | 3 | 277 | 72 | 0.28 | .93 | 1.29 | 98 | 1.7 | 10 | -22/-30 |
| F17T8 | 4 | 120 | 60 | 0.53 | .87 | 1.45 | 99 | 1.7 | 10 | -22/-30 |
| | 4 | 277 | 60 | 0.23 | .87 | 1.45 | 97 | 1.7 | 10 | -22/-30 |
| | 3 | 120 | 51 | 0.45 | .91 | 1.78 | 99 | 1.7 | 10 | -22/-30 |
| | 3 | 277 | 51 | 0.20 | .91 | 1.78 | 97 | 1.7 | 10 | -22/-30 |
| F40T8 | 3 | 120 | 112 | 0.99 | | | 99 | 1.7 | 10 | 0/-18 |
| | 3 | 277 | 110 | 0.43 | | | 98 | 1.7 | 10 | 0/-18 |

## Safety and Performance

c UL us LISTED · UL Class P · UL Type 1 Outdoor · UL Type HL · FCC – CLASS A Non-Consumer

## 74103 – GE232MAX-G-347 (Replaces GE232-N-347)

UltraMax® G-Series

347V Instant Start High-Efficiency

2 or 1 – F32T8 347V "N" .87 BF UltraMax® G

- T8 Instant Start Ballasts
- High-performance electronic ballast for all general fluorescent applications
- Instant start ballast for long lamp starting cycles and low initial cost
- Light-weight, Slim Profile Mini Can Housing
- Parallel lamp operation means system maintenance is easier to manage
- Cold temperature 0°F Minimum Starting Temperature

| General Characteristics | |
|---|---|
| Ballast Type | Electronic – High-Efficiency Instant Start |
| Starting Method | Instant Start |
| Lamp Wiring | Parallel |
| Line Voltage Regulation(+/-) | 10% |
| Ambient Temperature (MAX) | 40°C (104°F) |
| Case Temperature (MAX) | 70°C (158°F) |
| Ballast Factor | Normal |
| Power Factor Correction | Active |
| Sound Rating | A (20-24 decibels) |
| Enclosure Type | Metal |
| Additional Info | Auto-restart, Inherently Thermally Protected, UL Class P |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 9.5 in (241 mm) |
| Width (W) | 1.3 in (33 mm) |
| Height (H) | 1.18 in (30 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 8.9 in (226 mm) |
| Mount Width (X or F) | 0.87 in (22 mm) |
| Mount Slots (MS) | 0.3 in (8 mm) |
| Weight | 1.15 bs |
| Exit Type | Side |
| Remote Mounting Distance to Lamp (F32T8) | 18 ft |
| Remote Mounting Wire Gauge | 18 AWG |
| **Lead Lengths** | |
| Black | 25 in (635 mm) |
| White | 25 in (635 mm) |
| Blue | 31 in (787 mm) |
| Red | 45 in (1143 mm) |

**Specifications and lamp wattage**

| Lamp | # of Lamps | Line Volts (V) | System Watts (W) | Nom. Line Current (A) | System Ballast Factor | Ballast Efficacy Factor | Power Factor % (>=) | Crest Factor (<=) | THD% (<=) | Min Starting Temp (°F/°C) |
|---|---|---|---|---|---|---|---|---|---|---|
| F32T8 | 2 | 347 | 55 | 0.16 | 0.87 | 1.58 | 99 | 1.7 | 10 | 0/-18 |
| | 1 | 347 | 34 | 0.11 | 1.03 | 3.03 | 97 | 1.7 | 10 | 0/-18 |
| F32T8/WM | 2 | 347 | 52 | 0.15 | 0.85 | 1.63 | 99 | 1.7 | 10 | 60/16 |
| | 1 | 347 | 32 | 0.09 | 1.01 | 3.16 | 97 | 1.7 | 10 | 60/16 |
| F28T8 | 2 | 347 | 48 | 0.14 | 0.84 | 1.75 | 99 | 1.7 | 10 | 60/16 |
| | 1 | 347 | 30 | 0.09 | 1.00 | 3.33 | 96 | 1.7 | 10 | 60/16 |
| F32T8/25W | 2 | 347 | 44 | 0.13 | 0.84 | 1.91 | 99 | 1.7 | 10 | 60/16 |
| F25T8 | 2 | 347 | 41 | 0.12 | 0.88 | 2.15 | 98 | 1.7 | 10 | 0/-18 |
| | 1 | 347 | 26 | 0.08 | 1.04 | 4.00 | 95 | 1.7 | 11 | 0/-18 |
| F25T8/WM | 2 | 347 | 35 | 0.11 | 0.88 | 2.51 | 98 | 1.7 | 10 | 60/16 |
| F17T8 | 2 | 347 | 29 | 0.09 | 0.83 | 2.86 | 96 | 1.7 | 10 | 0/-18 |
| | 1 | 347 | 19 | 0.07 | 0.99 | 5.21 | 84 | 1.7 | 50 | 0/-18 |
| F17T8/WM | 2 | 347 | 24 | 0.08 | 0.83 | 3.46 | 96 | 1.7 | 10 | 60/16 |
| FE15T8 | 2 | 347 | 24 | 0.08 | 0.76 | 3.17 | 90 | 1.7 | 30 | 0/-18 |
| | 1 | 347 | 16 | 0.06 | 0.89 | 5.56 | 78 | 1.7 | 66 | 0/-18 |
| F25T12 | 2 | 347 | 44 | 0.13 | 0.88 | 2.00 | 98 | 1.7 | 10 | 0/-18 |
| | 1 | 347 | 28 | 0.08 | 1.07 | 3.82 | 96 | 1.7 | 10 | 0/-18 |

## Safety and Performance

c UL us LISTED · UL Class P · UL Type 1 Outdoor · UL Type HL · ICES-005 for EMI and RFI · FCC – CLASS A Non-Consumer

ANSI - C82.11 - Cons 2002, ANSI - C62.41 - 1991

## 74107 – GE432MAX-G-347 (Replaces GE432-N-347)

UltraMax® G-Series

347V Instant Start High-Efficiency

4 or 3 – F32T8 347V "N" .87 BF UltraMax® G

- T8 Instant Start Ballasts
- High-performance electronic ballast for all general fluorescent applications
- Instant start ballast for long lamp starting cycles and low initial cost
- Light-weight, Slim Profile Mini Can Housing
- Parallel lamp operation means system maintenance is easier to manage
- Cold temperature 0°F Minimum Starting Temperature

| General Characteristics | |
|---|---|
| Ballast Type | Electronic – High-Efficiency Instant Start |
| Starting Method | Instant Start |
| Lamp Wiring | Parallel |
| Line Voltage Regulation(+/-) | 10% |
| Ambient Temperature (MAX) | 40°C (104°F) |
| Case Temperature (MAX) | 70°C (158°F) |
| Ballast Factor | Normal |
| Power Factor Correction | Active |
| Sound Rating | A (20-24 decibels) |
| Enclosure Type | Metal |
| Additional Info | Auto-restart, Inherently Thermally Protected, UL Class P |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 9.5 in (241 mm) |
| Width (W) | 1.3 in (33 mm) |
| Height (H) | 1.18 in (30 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 8.9 in (226 mm) |
| Mount Width (X or F) | 0.87 in (22 mm) |
| Mount Slots (MS) | 0.3 in (8 mm) |
| Weight | 1.15 lbs |
| Exit Type | Side |
| Remote Mounting Distance to Lamp (F32T8) | 18 ft |
| Remote Mounting Wire Gauge | 18 AWG |
| **Lead Lengths** | |
| Black | 25 in (635 mm) |
| White | 25 in (635 mm) |
| Blue | 31 in (787 mm) |
| Red | 47 in (1194 mm) |

**Specifications and lamp wattage**

| Lamp | # of Lamps | Line Volts (V) | System Watts (W) | Nom. Line Current (A) | System Ballast Factor | Ballast Efficacy Factor | Power Factor % (>=) | Crest Factor (<=) | THD% (<=) | Min Starting Temp (°F/°C) |
|---|---|---|---|---|---|---|---|---|---|---|
| F32T8 | 4 | 347 | 109 | 0.30 | 0.88 | .81 | 99 | 1.7 | 10 | 0/-18 |
| | 3 | 347 | 87 | 0.25 | 0.95 | 1.09 | 99 | 1.7 | 10 | 0/-18 |
| F32T8/WM | 4 | 347 | 103 | 0.29 | 0.86 | .83 | 99 | 1.7 | 10 | 60/16 |
| | 3 | 347 | 83 | 0.24 | 0.94 | 1.13 | 99 | 1.7 | 10 | 60/16 |
| F28T8 | 4 | 347 | 96 | 0.27 | 0.84 | .88 | 99 | 1.7 | 10 | 60/16 |
| | 3 | 347 | 76 | 0.22 | 0.92 | 1.21 | 99 | 1.7 | 10 | 60/16 |
| F32T8/25W | 4 | 347 | 87 | 0.25 | 0.84 | .97 | 99 | 1.7 | 10 | 60/16 |
| F25T8 | 4 | 347 | 83 | 0.24 | 0.88 | 1.06 | 99 | 1.7 | 10 | 0/-18 |
| | 3 | 347 | 68 | 0.20 | 0.96 | 1.41 | 99 | 1.7 | 11 | 0/-18 |
| F25T8/WM | 4 | 347 | 71 | 0.20 | 0.88 | 1.24 | 99 | 1.7 | 10 | 60/16 |
| F17T8 | 4 | 347 | 52 | 0.17 | 0.84 | 1.62 | 99 | 1.7 | 10 | 0/-18 |
| | 3 | 347 | 48 | 0.14 | 0.91 | 1.90 | 98 | 1.7 | 50 | 0/-18 |
| F17T8/WM | 4 | 347 | 44 | 0.13 | 0.84 | 1.91 | 99 | 1.7 | 10 | 60/16 |
| FE15T8 | 4 | 347 | 47 | 0.14 | 0.76 | 1.62 | 98 | 1.7 | 30 | 0/-18 |
| | 3 | 347 | 38 | 0.12 | 0.82 | 2.16 | 91 | 1.7 | 66 | 0/-18 |
| F25T12 | 4 | 347 | 87 | 0.25 | 0.89 | 1.02 | 99 | 1.7 | 10 | 0/-18 |
| | 3 | 347 | 72 | 0.21 | 0.97 | 1.35 | 99 | 1.7 | 10 | 0/-18 |

## Safety and Performance

c UL us LISTED · UL Class P · UL Type 1 Outdoor · UL Type HL · ICES-005 for EMI and RFI · FCC – CLASS A Non-Consumer

ANSI - C82.11 - Cons 2002, ANSI - C62.41 - 1991

# 96714 – GE232-MVPS-N

## UltraStart® T8
## Programmed Start

2 or 1 – F32T8 120 to 277 Normal Light .88 BF <10% THD UltraStart®

- For F17 (2ft), F25 (3ft), F32 (4ft) Lamps
- < 10% THD, > 99% power factor
- A new generation of ultra-efficient Programmed Start ballasts (> 90% efficiency)
- Anti-striation circuitry reduces striations with energy saving lamps
- Extends lamp life in frequently switched applications (> 100,000 on/off cycles)
- Multi-voltage technology handles voltage from 120 to 277V
- Light-weight, Slim Profile Mini Can Housing

| General Characteristics | |
|---|---|
| Ballast Type | Electronic – Programmed/ Rapid Start |
| Starting Method | Programmed Start |
| Lamp Wiring | Parallel |
| Line Voltage Regulation(+/-) | 10% |
| Ambient Temperature (MAX) | 104°C (40°F) |
| Case Temperature (MAX) | 70°C (158°F) |
| Ballast Factor | Normal |
| Power Factor Correction | Active |
| Sound Rating | A (20-24 decibels) |
| Additional Info | Anti-striation control, Inherently Thermally Protected, UL Class P, Universal voltage |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 50 Hz/Supply Current Frequency (MIN)/ 50 Hz/ 60 (MIN) |
| Supply Current Frequency (MIN) | 50 Hz/60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 9.5 in (241 mm) |
| Width (W) | 1.3 in (33 mm) |
| Height (H) | 1.1 in (28 mm) |
| Weight | 1.10 lbs |
| Exit Type | Side |
| Remote Mounting Distance to Lamp (F32T8) | 18 ft |
| Remote Mounting Wire Gauge | 18 AWG |
| **Lead Lengths** | **Lengths (± 1 in)** |
| Black | 25 in (635 mm) |
| Blue & Red | 33 in (838 mm) |
| White | 25 in (635 mm) |
| Yellow | 47 in (1194 mm) |

**Specifications and lamp wattage**

| Lamp | # of Lamps | Line Volts (V) | System Watts (W) | Nom. Line Current (A) | System Ballast Factor | Ballast Efficacy Factor | Power Factor % (>=) | Crest Factor (<=) | THD% (<=) | Min Starting Temp (°F/°C) |
|---|---|---|---|---|---|---|---|---|---|---|
| F96T8 | 2 | 120 | 59 | 0.48A | 0.89 | 1.50 | 99 | 1.7 | 10 | 0/-18 |
| | 2 | 277 | 58 | 0.21A | 0.89 | 1.53 | 96 | 1.7 | 10 | 0/-18 |
| | 1 | 120 | 37 | 0.30A | 1.05 | 2.83 | 98 | 1.7 | 10 | 0/-18 |
| | 1 | 277 | 37 | 0.14A | 1.05 | 2.83 | 93 | 1.7 | 10 | 0/-18 |
| F96T8/WM | 2 | 120 | 55 | 0.45A | 0.88 | 1.60 | 99 | 1.7 | 10 | 50/10 |
| | 2 | 277 | 54 | 0.20A | 0.88 | 1.62 | 96 | 1.7 | 10 | 50/10 |
| | 1 | 120 | 34 | 0.28A | 1.02 | 3.00 | 98 | 1.7 | 10 | 50/10 |
| | 1 | 277 | 34 | 0.13A | 1.02 | 3.00 | 93 | 1.7 | 10 | 50/10 |
| F96T8/WMP | 2 | 120 | 51 | 0.42A | 0.86 | 1.68 | 99 | 1.7 | 10 | 50/10 |
| | 2 | 277 | 50 | 0.18A | 0.86 | 1.72 | 95 | 1.7 | 10 | 50/10 |
| | 1 | 120 | 32 | 0.26A | 1.00 | 3.12 | 98 | 1.7 | 10 | 50/10 |
| | 1 | 277 | 32 | 0.12A | 1.00 | 3.12 | 92 | 1.7 | 10 | 50/10 |

## Safety and Performance

c UL us LISTED · UL Listed · UL Class P · ANSI – C62.41 · UL Type 1 Outdoor · UL Type HL · FCC – CLASS A Non-Consumer

## 68993 – GE228MVPS-MC (replaces 99655)

UltraStart® Programmed Start
T5 High-Efficiency
2 or 1 – F14-F28T5HE, 120 – 277 UltraStart PRS Normal Light - .95 BF A Can

- For F14 (2ft), F21 (3ft), F28 (4ft), F35 (5ft) HE T5 Lamps*
- High Efficiency T5 ballast with Continuous Cathode Cutout Technology
- Lower Maintenance Costs with Parallel Lamp Operation
- Fast Starting Time <700ms
- Multi-Voltage technology means a single ballast handles voltage from 108V to 305V
- Auto-Restart withstands temporary losses in power without the need to cycle power

| General Characteristics | |
|---|---|
| Ballast Type | Electronic – Programmed / Rapid Start |
| Starting Method | Programmed Start |
| Lamp Wiring | Parallel |
| Line Voltage Regulation(+/-) | 10% |
| Ambient Temperature (MAX) | 131°F (55°C) |
| Case Temperature (MAX) | 70°C (158°F) |
| Ballast Factor | Normal |
| Power Factor Correction | Active |
| Sound Rating | A (20-24 decibels) |
| Additional Info | Auto-restart, End-of-Life Protection (EOL), Thermally protected, Universal voltage, Anti-striation control |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 50 Hz/60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 9.5 in (241 mm) |
| Width (W) | 1.3 in (33 mm) |
| Height (H) | 1.0 in (25.4 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 8.9 in (226 mm) |
| Mount Slots (MS) | 0.3 in (8 mm) |
| Weight | 1.0 lbs |
| Exit Type | Side |
| Remote Mounting Distance to Lamp | 8 ft |
| Remote Mounting Wire Gauge | 18 AWG |
| **Lead Lengths** | **Length (± 1 in)** |
| White & Black | 20 in (508 mm) |
| Blue & Red | 26 in (660 mm) |
| Yellow | 37 in (940 mm) |

**Specifications and lamp wattage**

| Lamp | # of Lamps | Line Volts (V) | System Watts (W) | Nom. Line Current (A) | System Ballast Factor | Ballast Efficacy Factor | Power Factor % (>=) | Crest Factor (<=) | THD% (<=) | Min Starting Temp (°F/°C) |
|---|---|---|---|---|---|---|---|---|---|---|
| F28T5HE | 2 | 277 | 60 | 0.22 | .96 | 1.60 | 99 | 1.4 | 6 | 0/-18 |
| | 1 | 277 | 41 | 0.16 | 1.21 | 2.95 | 97 | 1.4 | 9 | 0/-18 |
| | 2 | 120 | 62 | 0.53 | .96 | 1.55 | 99 | 1.4 | 7 | 0/-18 |
| | 1 | 120 | 41 | 0.35 | 1.21 | 2.95 | 99 | 1.4 | 8 | 0/-18 |
| F28T5HL | 2 | 277 | 60 | 0.23 | .96 | 1.60 | 98 | 1.4 | 6 | 32/0 |
| | 1 | 277 | 41 | 0.15 | 1.21 | 2.95 | 97 | 1.4 | 10 | 32/0 |
| | 2 | 120 | 62 | 0.52 | .96 | 1.55 | 99 | 1.4 | 7 | 32/0 |
| | 1 | 120 | 41 | 0.35 | 1.21 | 2.95 | 99 | 1.4 | 8 | 32/0 |
| F28T5WM | 2 | 277 | 58 | 0.22 | .98 | 1.69 | 98 | 1.4 | 6 | 32/0 |
| | 2 | 120 | 59 | 0.50 | .98 | 1.66 | 99 | 1.4 | 7 | 32/0 |
| F21T5HE | 2 | 277 | 50 | 0.18 | 1.04 | 2.08 | 98 | 1.4 | 7 | 32/0 |
| | 2 | 120 | 51 | 0.43 | 1.04 | 2.04 | 99 | 1.4 | 8 | 32/0 |
| F14T5HE | 2 | 277 | 37 | 0.14 | 1.10 | 2.97 | 97 | 1.4 | 10 | 32/0 |
| | 2 | 120 | 37 | 0.32 | 1.10 | 2.97 | 99 | 1.4 | 9 | 32/0 |
| F14T5WM | 2 | 277 | 36 | 0.13 | 1.10 | 3.06 | 97 | 1.4 | 11 | 32/0 |
| | 2 | 120 | 36 | 0.30 | 1.10 | 3.06 | 99 | 1.4 | 9 | 32/0 |

## Safety and Performance

UL Type CC, UL Type 1 Outdoor, UL Listed, UL Type HL, FCC – CLASS A Non-Consumer, UL Class P, cUL Listed, Meets ANSI Standard C62.41-1991, Meets ANSI Standard C82.11- cons 2002, No PCB's

# 67562 – GE254MVPS90-A

## UltraStart® Programmed Start
## T5 High Output

2 or 1 – F54T5HO 120 to 277V UltraStart® PRS High Temp A Can

- For T5 HO Lamps*
- High Efficiency T5 ballast with Continuous Cathode Cutout Technology
- Lower Maintenance Costs with Parallel Lamp Operation
- Fast Starting Time <700ms
- Multi-Voltage technology means a single ballast handles voltage from 108V to 305V
- Auto-Restart withstands temporary losses in power without the need to cycle power

| General Characteristics | |
|---|---|
| Ballast Type | Electronic – Programmed / Rapid Start |
| Starting Method | Programmed Start |
| Lamp Wiring | Parallel |
| Line Voltage Regulation(+/-) | 10% |
| Ambient Temperature (MAX) | 131°F (55°C) |
| Case Temperature (MAX) | 90°C (194°F) |
| Ballast Factor | Normal |
| Power Factor Correction | Active |
| Sound Rating | A (20-24 decibels) |
| Additional Info | Auto-restart, End-of-Life Protection (EOL), Thermally protected, Universal voltage, Anti-striation control |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 50 Hz/60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 9.5 in (241 mm) |
| Width (W) | 1.3 in (33.0 mm) |
| Height (H) | 1.0 in (25.4 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 8.9 in (226 mm) |
| Mount Slots (MS) | 0.25 in (6 mm) |
| Weight | 1.10 lbs |
| Exit Type | Side |
| Remote Mounting Distance to Lamp | 12 ft |
| Remote Mounting Wire Gauge | 18 AWG |
| **Lead Lengths** | **Length (± 1 in)** |
| White & Black | 25 in (635 mm) |
| Blue & Red | 34 in (864 mm) |
| Yellow | 45 in (1143 mm) |

**Specifications and lamp wattage**

| Lamp | # of Lamps | Line Volts (V) | System Watts (W) | Nom. Line Current (A) | System Ballast Factor | Ballast Efficacy Factor | Power Factor % (>=) | Crest Factor (<=) | THD% (<=) | Min Starting Temp (°F/°C) |
|---|---|---|---|---|---|---|---|---|---|---|
| F54T5HO | 2 | 120 | 117 | 0.98 | 1.00 | .85 | 1.00 | 1.4 | 4.4 | -20/-29 |
| | 2 | 277 | 114 | 0.41 | 1.10 | .96 | 99 | 1.4 | 5.4 | -20/-29 |
| | 1 | 120 | 63 | 0.53 | 1.00 | 1.59 | 1.00 | 1.4 | 6.4 | -20/-29 |
| | 1 | 277 | 62 | 0.23 | 1.10 | 1.77 | 97 | 1.4 | 6.6 | -20/-29 |
| F54T5WM | 2 | 120 | 109 | 0.90 | 1.00 | .92 | 1.00 | 1.4 | 4.6 | 0/-18 |
| | 2 | 277 | 107 | 0.40 | 1.12 | 1.05 | 99 | 1.4 | 5.2 | 0/-18 |
| | 1 | 120 | 61 | 0.51 | 1.00 | 1.64 | 1.00 | 1.4 | 6.7 | 0/-18 |
| | 1 | 277 | 60 | 0.22 | 1.12 | 1.87 | 97 | 1.4 | 7.7 | 0/-18 |
| F54T5/47W | 2 | 120 | 105 | 0.88 | 1.00 | .95 | 1.00 | 1.4 | 4.8 | -20/-29 |
| | 2 | 277 | 104 | 0.40 | 1.10 | 1.06 | 99 | 1.4 | 5.3 | -20/-29 |
| | 1 | 120 | 58 | 0.48 | 1.00 | 1.72 | 1.00 | 1.4 | 6.9 | -20/-29 |
| | 1 | 277 | 57 | 0.22 | 1.10 | 1.93 | 96 | 1.4 | 8.0 | -20/-29 |
| F58T8 | 2 | 120 | 110 | 0.90 | .95 | .86 | 1.00 | 1.4 | 4.7 | -20/-29 |
| | 2 | 277 | 107 | 0.39 | .95 | .89 | 99 | 1.4 | 5.4 | -20/-29 |
| | 1 | 120 | 59 | 0.49 | 1.08 | 1.83 | 1.00 | 1.4 | 6.6 | -20/-29 |
| | 1 | 277 | 59 | 0.22 | 1.08 | 1.83 | 96 | 1.4 | 7.3 | -20/-29 |
| FT55W/4P | 2 | 120 | 116 | 0.97 | .86 | .74 | 1.00 | 1.4 | 4.9 | 0/-18 |
| | 2 | 277 | 112 | 0.41 | .86 | .77 | 99 | 1.4 | 5.4 | 0/-18 |
| | 1 | 120 | 61 | 0.51 | 1.03 | 1.69 | 1.00 | 1.4 | 6.8 | 0/-18 |
| | 1 | 277 | 60 | 0.23 | 1.03 | 1.72 | 97 | 1.4 | 8.0 | 0/-18 |
| FT50W/4P | 2 | 120 | 118 | 1.00 | 1.05 | .89 | 1.00 | 1.4 | 4.6 | 0/-18 |
| | 2 | 277 | 116 | 0.43 | 1.06 | .91 | 99 | 1.4 | 5.2 | 0/-18 |
| | 1 | 120 | 64 | 0.53 | 1.18 | 1.84 | 1.00 | 1.4 | 6.6 | 0/-18 |
| | 1 | 277 | 63 | 0.24 | 1.18 | 1.87 | 97 | 1.4 | 7.4 | 0/-18 |

## Safety and Performance

UL Type 1 Outdoor · UL Type CC · UL Listed · Meets ANSI Standard C62.41-1991 · UL Class P · Meets ANSI Standard C82.11- cons 2002

FCC – CLASS A Non-Consumer · High Temperature Rated: Suitable for high temperature applications 80°C max case temp 5 yr warranty.

# 67566 – GE454MVPS90-F (replaces 77114)

## UltraStart® Programmed Start
## T5 High Output

4-1 – F54T5HO 120 to 277V UltraStart PS F Can

- For T5 HO Lamps*
- High Efficiency T5 ballast with Continuous Cathode Cutout Technology
- Lower Maintenance Costs with Parallel Lamp Operation
- Fast Starting Time <700ms
- Multi-Voltage technology means a single ballast handles voltage from 108V to 305V
- Auto-Restart withstands temporary losses in power without the need to cycle power
- Anti-Striation Control for better light quality, with no striations
- 90°C case rating/UL Approved 55C Ambient Rating
- Individual lamp End of Lamp Life protection - only one lamp shuts down at end of life
- Cold temperature -20°F Minimum Starting Temperature

| General Characteristics | |
|---|---|
| Ballast Type | Electronic – Programmed / Rapid Start |
| Starting Method | Programmed Start |
| Lamp Wiring | Parallel |
| Line Voltage Regulation(+/-) | 10% |
| Ambient Temperature (MAX) | 55°C (131°F) |
| Case Temperature (MAX) | 90°C (194°F) |
| Ballast Factor | Normal |
| Power Factor Correction | Active |
| Sound Rating | A (20-24 decibels) |
| Enclosure Type | Metal |
| Additional Info | Auto-restart, End-of-Life Protection (EOL), Thermally protected |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 50 Hz/60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 16.75 in (425 mm) |
| Width (W) | 1.8 in (46 mm) |
| Height (H) | 1.2 in (30.5 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 16.7 in (424 mm) |
| Weight | 3.0 lbs |
| Exit Type | Side |
| Remote Mounting Distance to Lamp | 8 ft |
| Remote Mounting Wire Gauge | 18 AWG |
| **Lead Lengths** | **Length (± 1 in)** |
| Black | 25 in (635 mm) |
| White | 25 in (635 mm) |

**Specifications and lamp wattage**

| Lamp | # of Lamps | Line Volts (V) | System Watts (W) | Nom. Line Current (A) | System Ballast Factor | Ballast Efficacy Factor | Power Factor % (>=) | Crest Factor (<=) | THD% (<=) | Min Starting Temp (°F/°C) |
|---|---|---|---|---|---|---|---|---|---|---|
| FT55W/4P | 4 | 120 | 206 | 1.73 | .86 | .42 | 99 | 1.4 | 5 | 0/-18 |
| | 4 | 277 | 203 | 0.75 | .86 | .42 | 97 | 1.4 | 8 | 0/-18 |
| | 3 | 120 | 168 | 1.41 | .91 | .54 | 99 | 7.0 | 6 | 0/-18 |
| | 3 | 277 | 168 | 0.63 | .91 | .54 | 97 | 1.4 | 10 | 0/-18 |
| | 2 | 120 | 125 | 1.04 | | | 99 | 1.4 | 7 | 0/-18 |
| | 2 | 277 | 124 | 0.48 | | | 94 | 1.4 | 16 | 0/-18 |
| | 1 | 120 | 64 | 0.54 | | | 99 | 1.4 | 10 | 0/-18 |
| | 1 | 277 | 66 | 0.28 | | | 84 | 1.4 | 25 | 0/-18 |
| FT50W/4P | 4 | 120 | 222 | 1.86 | 1.06 | .48 | 99 | 1.4 | 5 | 0/-18 |
| | 4 | 277 | 218 | 0.81 | 1.06 | .49 | 98 | 1.4 | 8 | 0/-18 |
| | 3 | 120 | 187 | 1.56 | 1.11 | .59 | 99 | 1.4 | 6 | 0/-18 |
| | 3 | 277 | 184 | 0.68 | 1.11 | .60 | 97 | 1.4 | 9 | 0/-18 |
| | 2 | 120 | 130 | 1.09 | | | 99 | 1.4 | 7 | 0/-18 |
| | 2 | 277 | 130 | 0.50 | | | 95 | 1.4 | 15 | 0/-18 |
| | 1 | 120 | 72 | 0.60 | | | 99 | 1.4 | 10 | 0/-18 |
| | 1 | 277 | 73 | 0.31 | | | 85 | 1.4 | 26 | 0/-18 |
| F58T8 | 4 | 120 | 208 | 1.73 | .95 | .46 | 99 | 1.4 | 5 | -20/-29 |
| | 4 | 277 | 204 | 0.76 | .95 | .47 | 97 | 1.4 | 9 | -20/-29 |
| | 3 | 120 | 176 | 1.47 | .99 | .56 | 99 | 1.4 | 6 | -20/-29 |
| | 3 | 277 | 173 | 0.65 | .99 | .57 | 94 | 1.4 | 10 | -20/-29 |
| | 2 | 120 | 128 | 1.07 | | | 99 | 1.4 | 7 | -20/-29 |
| | 2 | 277 | 127 | 0.49 | | | 94 | 1.4 | 16 | -20/-29 |
| | 1 | 120 | 67 | 0.57 | | | 99 | 1.4 | 10 | -20/-29 |
| F54T5/WM | 1 | 277 | 68 | 0.29 | | | 85 | 1.4 | 25 | -20/-29 |
| | 4 | 120 | 214 | 1.79 | 1.00 | .47 | 99 | 1.4 | 5 | 0/-18 |
| | 4 | 277 | 210 | 0.78 | 1.00 | .48 | 98 | 1.4 | 8 | 0/-18 |
| | 3 | 120 | 181 | 1.51 | 1.01 | .56 | 99 | 1.4 | 6 | 0/-18 |
| | 3 | 277 | 178 | 0.66 | 1.01 | .57 | 97 | 1.4 | 9 | 0/-18 |
| | 2 | 120 | 130 | 1.09 | .96 | .74 | 99 | 1.4 | 7 | 0/-18 |
| | 2 | 277 | 135 | 0.51 | .96 | .71 | 95 | 1.4 | 15 | 0/-18 |
| | 1 | 120 | 69 | 0.58 | 1.12 | 1.62 | 99 | 1.4 | 10 | 0/-18 |
| F54T5/HO | 1 | 277 | 70 | 0.30 | 1.12 | 1.60 | 85 | 1.4 | 26 | 0/-18 |
| | 4 | 120 | 220 | 1.84 | 1.00 | .45 | 99 | 1.4 | 5 | -20/-29 |
| | 4 | 277 | 216 | 0.80 | 1.00 | .46 | 98 | 1.4 | 8 | -20/-29 |
| | 3 | 120 | 185 | 1.55 | 1.01 | .55 | 99 | 1.4 | 6 | -20/-29 |
| | 3 | 277 | 182 | 0.68 | 1.01 | .55 | 97 | 1.4 | 9 | -20/-29 |
| | 2 | 120 | 133 | 0.58 | .96 | .72 | 99 | 1.4 | 7 | -20/-29 |
| | 2 | 277 | 132 | 0.50 | .96 | .72 | 95 | 1.4 | 15 | -20/-29 |
| | 1 | 120 | 69 | 0.58 | 1.11 | 1.61 | 99 | 1.4 | 10 | -20/-29 |
| | 1 | 277 | 70 | 0.30 | 1.11 | 1.59 | 85 | 1.4 | 26 | -20/-29 |

## Safety and Performance

UL Type 1 Outdoor  UL Type HL  FCC – CLASS A Non-Consumer  ANSI-C62.41-1991

ANSI-C82.11-Cons 2002  UL Class P  UL Type CC  UL Listed  CSA

High Temperature Rated: Suitable for high temperature applications  70C max case temp 5 yr warranty or 90C max case temp 3 yr warranty

## 74119 – GETR480/277-250W

### Step Down Transformers

Non-Isolated Autotransformer 480 to 277V, <250 Watts (VA), A Can

- Precision-wound coils, ensuring even heat dissipation and the highest electrical integrity.
- Non-Isolated Autotransformer designed specifically for lighting applications to step down 480V to 277V
- For use with one or more electronic 277V or universal voltage ballasts within max total system power of autotransformer
- 480Vrms Input, 60Hz Only, 277Vrms Full Load Output or 347Vrms Input
- For loads with total system power <250VA
- Internal Auto Reset Thermal Protector Rated 100C
- For use on single phase or ground referred systems
- Five Year Limited Warranty
- 93% electrical efficiency

| General Characteristics | |
|---|---|
| Ballast Type | Magnetic - Core & Coil |
| Case Temperature (MAX) | 100°C (212°F) |
| Sound Rating | A (20-24 decibels) |
| Enclosure Type | Metal |
| Additional Info | Thermally protected |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 60 Hz |
| Supply Current Frequency (MIN) | 60 Hz |

| Specifications by lamp and wattage/Line Volts (V) |
|---|
| 480V to 277V |
| 347V to 200V |

| Dimensions | |
|---|---|
| Length (L) | 9.5 in (241 mm) |
| Width (W) | 1.7 in (43.2 mm) |
| Height (H) | 1.18 in (30 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 8.9 in (226 mm) |
| Mount Width (X or F) | 1.18 in (30 mm) |
| Mount Slots (MS) | 0.3 in (8 mm) |
| Exit Type | Side |
| Remote Mounting Wire Gauge | 14 AWG |
| **Lead Lengths** | **Length (± 1 in)** |
| Black | 14.0 in (356 mm) |
| Blue | 14.0 in (356 mm) |
| Red | 14.0 in (356 mm) |

### Safety and Performance

UL Type 1 Outdoor · UL Listed · UL Listed Autotransformer · cULus cUL

## 74120 – GETR480/277-375W

### Step Down Transformers

Non-Isolated Autotransformer 480 to 277V, <375 Watts (VA), F Can

- Precision-wound coils, ensuring even heat dissipation and the highest electrical integrity.
- Non-Isolated Autotransformer designed specifically for lighting applications to step down 480V to 277V
- For use with one or more electronic 277V or universal voltage ballasts within max total system power of autotransformer
- 480Vrms Input, 60Hz Only, 277Vrms Full Load Output or 347Vrms Input
- For loads with total system power <375VA
- Internal Auto Reset Thermal Protector Rated 100C
- For use on single phase or ground referred systems
- Five Year Limited Warranty
- 93% electrical efficiency

| General Characteristics | |
|---|---|
| Ballast Type | Magnetic - Core & Coil |
| Case Temperature (MAX) | 100°C (212°F) |
| Sound Rating | A (20-24 decibels) |
| Enclosure Type | Metal |
| Additional Info | Thermally protected |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 60 Hz |
| Supply Current Frequency (MIN) | 60 Hz |

| Specifications by lamp and wattage/Line Volts (V) |
|---|
| 480V to 277V |
| 347V to 200V |

| Dimensions | |
|---|---|
| Length (L) | 11.75 in (299 mm) |
| Width (W) | 1.7 in (43.2 mm) |
| Height (H) | 1.18 in (30 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 11.1 in (283 mm) |
| Mount Slots (MS) | 0.3 in (8 mm) |
| Exit Type | Side |
| Remote Mounting Wire Gauge | 14 AWG |
| **Lead Lengths** | **Length (± 1 in)** |
| Black | 14.0 in (356 mm) |
| Blue | 14.0 in (356 mm) |
| Red | 14.0 in (356 mm) |

### Safety and Performance

UL Type 1 Outdoor · UL Listed · cULus cUL

## 74472 – GE240PS-MV-N (replaces 24107)

ProLine®

T12 Multivolt 120V – 277V

2 or 1 – F40 or F34T12 Rapid Start 120 to 277 "N" BF ProLine® T12

- For F20 (2ft), F30 (3ft), F34/F40 (4ft) T12 Lamps
- High-performance electronic ballast for all general fluorescent applications
- Multi-voltage technology handles voltage from 120 to 277V
- Light weight, low-profile housing
- Parallel lamp operation means system maintenance is easier to manage

| General Characteristics | |
|---|---|
| Ballast Type | Electronic – Programmed / Rapid Start |
| Starting Method | Rapid Start |
| Lamp Wiring | Parallel |
| Line Voltage Regulation(+/-) | 10% |
| Ambient Temperature (MAX) | |
| Case Temperature (MAX) | 70°C (158°F) |
| Ballast Factor | Normal |
| Power Factor Correction | Active |
| Sound Rating | A (20-24 decibels) |
| Enclosure Type | Metal |
| Additional Info | Auto-restart, Thermally protected |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 9.5 in (241 mm) |
| Width (W) | 1.3 in (33 mm) |
| Height (H) | 1.2 in (30.5 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 8.9 in (226 mm) |
| Mount Width (X or F) | 1.1 in (28 mm) |
| Mount Slots (MS) | 0.3 in (8 mm) |
| Weight | 1.06 lbs |
| Exit Type | Side |
| Remote Mounting Distance to Lamp | 18 ft |
| Remote Mounting Wire Gauge | 18 AWG |
| **Lead Lengths** | **Length (± 1 in)** |
| Yellow | 48 in (1219 mm) |
| Blue | 33 in (838 mm) |
| Red | 33 in (838 mm) |
| Black | 25 in (635 mm) |
| White | 25 in (635 mm) |

**Specifications and lamp wattage**

| Lamp | # of Lamps | Line Volts (V) | System Watts (W) | Nom. Line Current (A) | System Ballast Factor | Ballast Efficacy Factor | Power Factor % (>=) | Crest Factor (<=) | THD% (<=) | Min Starting Temp (°F/°C) |
|---|---|---|---|---|---|---|---|---|---|---|
| F40T12 | 2 | 120 | 74 | 0.67 | .89 | 1.20 | 99 | 1.7 | 6 | 50/10 |
| | 2 | 277 | 73 | 0.30 | .89 | 1.22 | 97 | 1.7 | 10 | 50/10 |
| | 1 | 120 | 48 | 0.41 | | | 99 | 1.7 | 7 | 50/10 |
| | 1 | 277 | 48 | 0.19 | | | 95 | 1.7 | 10 | 50/10 |
| F40T10 | 2 | 120 | 75 | 0.63 | .88 | 1.17 | 99 | 1.7 | 7 | 50/10 |
| | 2 | 277 | 72 | 0.27 | .88 | 1.22 | 94 | 1.7 | 16 | 50/10 |
| | 1 | 120 | 42 | 0.35 | | | 99 | 1.7 | 10 | 50/10 |
| | 1 | 277 | 42 | 0.17 | | | 88 | 1.7 | 16 | 50/10 |
| F34T12 | 2 | 120 | 63 | 0.56 | .87 | 1.38 | 99 | 1.7 | 7 | 50/10 |
| | 2 | 277 | 62 | 0.26 | .87 | 1.40 | 96 | 1.7 | 10 | 50/10 |
| | 1 | 120 | 41 | 0.35 | | | 99 | 1.7 | 8 | 50/10 |
| | 1 | 277 | 41 | 0.17 | | | 94 | 1.7 | 11 | 50/10 |
| F30T12/WM | 2 | 120 | 50 | 0.42 | .95 | 1.90 | 99 | 1.7 | 9 | 50/10 |
| | 2 | 277 | 50 | 0.20 | .95 | 1.90 | 91 | 1.7 | 18 | 50/10 |
| | 1 | 120 | 30 | 0.26 | | | 99 | 1.7 | 12 | 50/10 |
| | 1 | 277 | 30 | 0.13 | | | 82 | 1.7 | 27 | 50/10 |
| F30T12 | 2 | 120 | 60 | 0.31 | .95 | 1.58 | 99 | 1.7 | 7 | 50/10 |
| | 2 | 277 | 58 | 0.22 | .95 | 1.64 | 96 | 1.7 | 10 | 50/10 |
| | 1 | 120 | 37 | 0.31 | | | 99 | 1.7 | 8 | 50/10 |
| | 1 | 277 | 37 | 0.16 | | | 94 | 1.7 | 11 | 50/10 |
| F20T12 | 2 | 120 | 46 | 0.39 | 1.00 | 2.17 | 99 | 1.7 | 8 | 50/10 |
| | 2 | 277 | 45 | 0.18 | 1.00 | 2.22 | 94 | 1.7 | 11 | 50/10 |
| | 1 | 120 | 28 | 0.24 | | | 99 | 1.7 | 9 | 50/10 |
| | 1 | 277 | 29 | 0.13 | | | 92 | 1.7 | 17 | 50/10 |

## Safety and Performance

UL Type 1 Outdoor · UL Type HL · UL Class P · NRCan · FCC Part 18 Class B at 120 volts · cUL Listed · UL Listed

## 74474 – GE-260IS-MV-N (replaces 24108)

ProLine®

T12 Multivolt 120V – 277V

2 or 1 – F96T12 Instant Start 120 to 277

- For T12 4ft – 8ft Slimline Lamps
- High-performance electronic ballast for all general fluorescent applications
- Instant start electronic ballast for long lamp starting cycles and low initial cost
- Multi-voltage technology handles voltage from 120 to 277V
- Light weight, low-profile housing
- Parallel lamp operation means system maintenance is easier to manage

| General Characteristics | |
|---|---|
| Ballast Type | Electronic – Multivolt Instant Start |
| Starting Method | Rapid Start |
| Lamp Wiring | Parallel |
| Line Voltage Regulation(+/-) | 10% |
| Ambient Temperature (MAX) | |
| Case Temperature (MAX) | 70°C (158°F) |
| Ballast Factor | Normal |
| Power Factor Correction | Active |
| Sound Rating | A (20-24 decibels) |
| Enclosure Type | Metal |
| Additional Info | Auto-restart, Thermally protected |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 50Hz/60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 9.5 in (241 mm) |
| Width (W) | 1.7 in (43 mm) |
| Height (H) | 1.2 in (30.5 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 8.9 in (226 mm) |
| Mount Width (X or F) | 1.1 in (28 mm) |
| Mount Slots (MS) | 0.3 in (8 mm) |
| Weight | 2.40 lbs |
| Exit Type | Side |
| Remote Mounting Distance to Lamp | 18 ft |
| Remote Mounting Wire Gauge | 18 AWG |
| **Lead Lengths** | **Length (± 1 in)** |
| Black | 25 in (635 mm) |
| White | 25 in (635 mm) |
| Red | 59 in (1499 mm) |
| Blue | 67 in (1702 mm) |

**Specifications and lamp wattage**

| Lamp | # of Lamps | Line Volts (V) | System Watts (W) | Nom. Line Current (A) | System Ballast Factor | Ballast Efficacy Factor | Power Factor % (>=) | Crest Factor (<=) | THD% (<=) | Min Starting Temp (°F/°C) |
|---|---|---|---|---|---|---|---|---|---|---|
| F96T12/WMP | 2 | 120 | 107 | 0.94 | .88 | .82 | 99 | 1.7 | 8 | 60/16 |
| | 2 | 277 | 106 | 0.40 | .88 | .83 | 96 | 1.7 | 10 | 60/16 |
| | 1 | 120 | 68 | 0.60 | 1.00 | 1.47 | 99 | 1.7 | 10 | 60/16 |
| | 1 | 277 | 68 | 0.27 | 1.00 | 1.47 | 95 | 1.7 | 12 | 60/16 |
| F96T12/WM | 2 | 120 | 112 | 0.98 | .90 | .80 | 99 | 1.7 | 8 | 60/16 |
| | 2 | 277 | 110 | 0.42 | .90 | .82 | 97 | 1.7 | 10 | 60/16 |
| | 1 | 120 | 72 | 0.63 | 1.00 | 1.39 | 99 | 1.7 | 10 | 60/16 |
| | 1 | 277 | 71 | 0.28 | 1.00 | 1.41 | 95 | 1.7 | 12 | 60/16 |
| F96T12 | 2 | 120 | 141 | 1.24 | .90 | .64 | 99 | 1.7 | 8 | 0/-18 |
| | 2 | 277 | 138 | 0.53 | .90 | .65 | 98 | 1.7 | 10 | 0/-18 |
| | 1 | 120 | 90 | 0.79 | 1.02 | 1.13 | 99 | 1.7 | 10 | 0/-18 |
| | 1 | 277 | 89 | 0.34 | 1.02 | 1.15 | 96 | 1.7 | 12 | 0/-18 |
| F84T12 | 2 | 120 | 125 | 1.10 | .90 | .72 | 99 | 1.7 | 8 | 0/-18 |
| | 2 | 277 | 123 | 0.47 | .90 | .73 | 97 | 1.7 | 10 | 0/-18 |
| | 1 | 120 | 80 | 0.70 | 1.04 | 1.30 | 99 | 1.7 | 10 | 0/-18 |
| | 1 | 277 | 79 | 0.30 | 1.04 | 1.32 | 96 | 1.7 | 12 | 0/-18 |
| F72T12 | 2 | 120 | 107 | 0.94 | .90 | .84 | 99 | 1.7 | 8 | 0/-18 |
| | 2 | 277 | 106 | 0.40 | .90 | .85 | 97 | 1.7 | 10 | 0/-18 |
| | 1 | 120 | 69 | 0.60 | 1.08 | 1.51 | 99 | 1.7 | 10 | 0/-18 |
| | 1 | 277 | 69 | 0.27 | 1.08 | 1.51 | 95 | 1.7 | 12 | 0/-18 |
| F64T12 | 2 | 120 | 97 | 0.86 | .90 | .93 | 99 | 1.7 | 8 | 0/-18 |
| | 2 | 277 | 96 | 0.37 | .90 | .94 | 97 | 1.7 | 10 | 0/-18 |
| | 1 | 120 | 63 | 0.55 | 1.08 | 1.71 | 99 | 1.7 | 10 | 0/-18 |
| | 1 | 277 | 63 | 0.25 | 1.08 | 1.71 | 95 | 1.7 | 12 | 0/-18 |
| F60T12 | 2 | 120 | 92 | 0.81 | .90 | .98 | 99 | 1.7 | 8 | 0/-18 |
| | 2 | 277 | 91 | 0.35 | .90 | .99 | 96 | 1.7 | 10 | 0/-18 |
| | 1 | 120 | 60 | 0.53 | 1.08 | 1.80 | 99 | 1.7 | 10 | 0/-18 |
| | 1 | 277 | 60 | 0.28 | 1.08 | 1.80 | 94 | 1.7 | 12 | 0/-18 |
| F48T12 | 2 | 120 | 73 | 0.65 | .90 | 1.23 | 99 | 1.7 | 8 | 0/-18 |
| | 2 | 277 | 73 | 0.29 | .90 | 1.23 | 95 | 1.7 | 10 | 0/-18 |
| | 1 | 120 | 49 | 0.43 | 1.10 | 2.24 | 99 | 1.7 | 10 | 0/-18 |
| | 1 | 277 | 48 | 0.20 | 1.10 | 2.29 | 89 | 1.7 | 12 | 0/-18 |

## Safety and Performance

UL Type 1 Outdoor · NRCan · UL Type HL · FCC – CLASS A Non-Consumer · UL Class P · cUL Listed · UL Listed

# 35727 – GE296HO-MVPS-N

ProLine® T12 High Output
T12 Multivolt 120V – 277V
2 or 1 – F96T12 HO RS 120 to 277 Multivolt ProLine®


| General Characteristics | |
|---|---|
| Ballast Type | Electronic – Programmed/ Rapid Start |
| Starting Method | Rapid Start |
| Lamp Wiring | Series |
| Line Voltage Regulation(+/-) | 10% |
| Ambient Temperature (MAX) | 105°F (41°C) |
| Case Temperature (MAX) | 75°C (167°F) |
| Ballast Factor | Normal |
| Power Factor Correction | Active |
| Sound Rating | A (20-24 decibels) |
| Additional Info | Auto-restart, Thermally protected |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 50Hz/60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 11.75 in (299 mm) |
| Width (W) | 2.15 in (55 mm) |
| Height (H) | 1.61 in (41 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 11.0 in (279 mm) |
| Mount Width (X or F) | 2.15 in (55 mm) |
| Mount Slots (MS) | |
| Weight | |
| Exit Type | Side |

**Specifications by lamp and wattage**

| Lamp | # of Lamps | Line Volts (V) | System Watts (W) | Nom. Line Current (A) | System Ballast Factor | Ballast Efficacy Factor | Power Factor % (>=) | Crest Factor (<=) | THD% (<=) | Min Starting Temp (°F/°C) |
|---|---|---|---|---|---|---|---|---|---|---|
| F96T12/HO/WM | 2 | 120 | 164 | 1.38 | .90 | .55 | 99 | 1.7 | 10 | 60/16 |
| | 2 | 277 | 164 | 0.62 | .90 | .55 | 99 | 1.7 | 10 | 60/16 |
| F96T12/HO | 2 | 120 | 196 | 1.65 | .90 | .47 | 99 | 1.7 | 10 | -20/-29 |
| | 2 | 277 | 196 | 0.73 | .90 | .46 | 97 | 1.7 | 10 | -20/-29 |
| | 1 | 120 | 104 | 0.88 | .92 | .88 | 99 | 1.7 | 15 | -20/-29 |
| | 1 | 277 | 104 | 0.42 | .92 | .88 | 95 | 1.7 | 15 | -20/-29 |
| F72T12/HO | 2 | 120 | 154 | 1.30 | .90 | .58 | 99 | 1.7 | 10 | -20/-29 |
| | 2 | 277 | 154 | 0.57 | .90 | .58 | 96 | 1.7 | 10 | -20/-29 |
| F70T8 | 2 | 120 | 120 | 1.17 | .90 | .75 | 99 | 1.7 | 10 | -20/-29 |
| | 2 | 277 | 119 | 0.52 | .90 | .76 | 97 | 1.7 | 10 | -20/-29 |
| F60T12/HO | 2 | 120 | 132 | 0.50 | .90 | .68 | 96 | 1.7 | 10 | -20/-29 |
| | 2 | 277 | 132 | 0.50 | .90 | .68 | 96 | 1.7 | 10 | -20/-29 |
| F48T12/HO | 2 | 120 | 112 | 0.95 | .90 | .80 | 99 | 1.7 | 15 | -20/-29 |
| | 2 | 277 | 113 | 0.43 | .90 | .80 | 95 | 1.7 | 15 | -20/-29 |




## Safety and Performance

cUL Listed UL Listed FCC Part 18 (Class A) Non Consumer

## Understanding **Compact Fluorescent Ballasts**

Compact fluorescent (CFL) ballasts provide energy saving alternatives to halogen, incandescent or HID light sources. Multi volt ProLine® CFL programmed start ballasts combine universal voltage (108-305V) technology with multi-lamp capability, dual entry color-coded connectors and ultra system reliability to create an industry leading CFL solution for commercial and residential applications.

UltraMax® and UltraStart® High Lumen Biax® ballasts with the High Lumen WattMiser® Biax® lamp provides the perfect solution for high efficiency and high lumen output in a small space.

### UltraMax® Instant Start Ballasts:

- For use in long burn cycles (>10 hr cycles) to maintain lamp life
- High efficiency (>90%) design
- Universal voltage (120-277V)
- Striation control circuitry
- Small compact housing

### UltraStart® Programmed Start Ballasts:

- For use in shorter burn cycles (<3 hr cycles) to extend lamp life
- High efficiency (>90%) cathode cutout design
- Universal voltage (120-277V)
- Striation control circuitry
- Small compact housing
- Parallel lamp operation
- <700ms fast starting time
- Ballasts available for both F40/30W and F40/25W lamps

### Multivolt ProLine®

Multivolt ProLine® CFL ballasts are offered in 3W configuration: 3-way mounting kits that allow you to have all three mounting options with one kit.

Multivolt ProLine® CFL ballasts come with a five-year ballast and one-year lamp limited warranty. These ballasts have a Consumer Class B EMI rating for residential applications, as well as a high power factor ballast design.

Use the Multivolt ProLine® CFL Multi-Lamp compatibility chart (page 17-3) to find the right ballast for your need.

### ProLine® CFL Date Code System

Date Code Format: 01 200801 = Week2008 = Year

UltraMax® and UltraStart® Biax® ballasts have the same date code system as all linear fluorescent ballasts.



## 63097 – GEC226-MVPS-3W

### ProLine® CFL Electronic Ballasts

2 – CFQ26W, FT24 or 1 – 24W CFTR32 120-277V ProLine® PS

- Multi-voltage technology means a single ballast handles voltage from 108V to 305V
- Programmed starting for extended lamp life
- End-of-Lamp-Life protection
- Color coded poke-in connectors simplifies wiring

| General Characteristics | |
|---|---|
| Ballast Type | Electronic – Program/ Rapid Start |
| Starting Method | Programmed Start |
| Lamp Wiring | Series |
| Line Voltage Regulation(+/-) | 10% |
| Ambient Temperature (MAX) | 104°F (40°C) |
| Case Temperature (MAX) | 75°C (167°F) |
| Ballast Factor | Normal |
| Power Factor Correction | Active |
| Sound Rating | A (20-24 decibels) |
| Additional Info | Auto restart, Thermally protected, Universal voltage |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 50Hz/60 Hz |

| Dimensions | |
|---|---|
| **Physical Parameters** | |
| Length (L) | 5.1 in (128 mm) |
| Width (W) | 2.4 in (60 mm) |
| Height (H) | 0.9 in (23 mm) |
| Weight | 0.419 lbs |
| Exit Type | Dual Entry |
| Remote Mounting Distance to Lamp | 9.8 ft (3 m) |
| Remote Mounting Wire Gauge | 18 AWG |

**Specifications by lamp and wattage**

| Lamp | # of Lamps | Line Volts (V) | System Watts (W) | Nom. Line Current (A) | System Ballast Factor | Ballast Efficacy Factor | Power Factor % (>=) | Crest Factor (<=) | THD% (<=) | Min Starting Temp (°F/°C) |
|---|---|---|---|---|---|---|---|---|---|---|
| CFQ26W/G24q | 2 | 120 | 56 | 0.47 | 1.02 | 1.82 | 99 | 1.7 | 10 | -20/-29 |
| | 2 | 277 | 54 | 0.20 | 1.02 | 1.89 | 97 | 1.7 | 11 | -20/-29 |
| | 1 | 120 | 30 | 0.25 | 1.04 | 3.47 | 99 | 1.7 | 10 | -20/-29 |
| | 1 | 277 | 30 | 0.12 | 1.04 | 3.47 | 93 | 1.7 | 13 | -20/-29 |
| CFTR26W/GX24q | 2 | 120 | 64 | 0.53 | .97 | 1.52 | 99 | 1.7 | 10 | -20/-29 |
| | 2 | 277 | 64 | 0.23 | .88 | 1.38 | 97 | 1.7 | 12 | -20/-29 |
| | 1 | 120 | 32 | 0.26 | 1.01 | 3.16 | 99 | 1.7 | 10 | -20/-29 |
| | 1 | 277 | 32 | 0.12 | 1.00 | 3.16 | 94 | 1.7 | 13 | -20/-29 |
| CFS21W/GR10q | 2 | 120 | 56 | 0.47 | 1.12 | 2.00 | 99 | 1.7 | 10 | -20/-29 |
| | 2 | 277 | 55 | 0.20 | 1.11 | 2.02 | 96 | 1.7 | 11 | -20/-29 |
| CFTR42W/GX24q | 1 | 120 | 51 | 0.42 | .92 | 1.80 | 99 | 1.7 | 10 | -20/-29 |
| | 1 | 277 | 50 | 0.18 | .92 | 1.84 | 97 | 1.7 | 12 | -20/-29 |
| CFTR32W/GX24q | 1 | 120 | 39 | 0.33 | 1.24 | 3.18 | 99 | 1.7 | 10 | -20/-29 |
| | 1 | 277 | 39 | 0.15 | 1.23 | 3.15 | 95 | 1.7 | 13 | -20/-29 |
| FC16T9 40W | 1 | 120 | 40 | 0.33 | .89 | 2.23 | 99 | 1.7 | 10 | -20/-29 |
| | 1 | 277 | 40 | 0.14 | .94 | 2.35 | 95 | 1.7 | 13 | -20/-29 |
| FT24W/2G11 | 1 | 120 | 27 | 0.23 | 1.04 | 3.85 | 99 | 1.7 | 10 | -20/-29 |
| | 1 | 277 | 27 | 0.11 | 1.10 | 4.07 | 91 | 1.7 | 14 | -20/-29 |
| FT36W/2G11 | 1 | 120 | 35 | 0.29 | .94 | 2.69 | 99 | 1.7 | 10 | -20/-29 |
| | 1 | 277 | 35 | 0.13 | .94 | 2.69 | 94 | 1.7 | 13 | -20/-29 |
| FT39W/2G11 | 1 | 120 | 33 | 0.27 | .97 | 2.94 | 99 | 1.7 | 10 | -20/-29 |
| | 1 | 277 | 33 | 0.12 | .98 | 2.97 | 94 | 1.7 | 14 | -20/-29 |

## 71436 – GEC340MAX-A

### High-Lumen Biax® UltraMax® Instant Start

3 – FT40W-25W/2G11 Biax - 120-277V UltraMax® Instant Start

- Multi-Voltage technology handles voltage from 120 to 277V
- Energy saving, high efficiency instant start electronic ballast (> 90%)
- Instant start electronic ballast for long lamp starting cycles and low initial cost
- Lamp End-of-Life Safety Shutdown Circuit with Re-Lamping Auto-reset

| General Characteristics | |
|---|---|
| Ballast Type | Electronic – High Efficiency Instant Start |
| Starting Method | Instant Start |
| Lamp Wiring | Parallel |
| Line Voltage Regulation(+/-) | 10% |
| Ambient Temperature (MAX) | 105°F (41°C) |
| Case Temperature (MAX) | 70°C (158°F) |
| Ballast Factor | Normal |
| Power Factor Correction | Active |
| Sound Rating | A (20-24 decibels) |
| Additional Info | End-of-Life Protection (EOL), Thermally protected |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 50Hz/60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 9.5 in (241 mm) |
| Width (W) | 1.7 in (43 mm) |
| Height (H) | 1.18 in (30 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 8.9 in (226 mm) |
| Mount Width (X or F) | 1.18 in (30 mm) |
| Mount Slots (MS) | 0.3 in (8 mm) |
| Weight | 1.40 lbs |
| Exit Type | Side |
| Remote Mounting Distance to Lamp | 12 ft |
| Remote Mounting Wire Gauge | 18 AWG |

**Specifications by lamp and wattage**

| Lamp | # of Lamps | Line Volts (V) | System Watts (W) | Nom. Line Current (A) | System Ballast Factor | Power Factor % (>=) | Crest Factor (<=) | THD% (<=) | Min Starting Temp (°F/°C) |
|---|---|---|---|---|---|---|---|---|---|
| FT40W/4P | 3 | 120 | 100 | 0.86 | .90 | 99 | 1.7 | 10 | 0/-18 |
| | 3 | 277 | 99 | 0.36 | .90 | 99 | 1.7 | 10 | 0/-18 |
| | 2 | 120 | 76 | 0.65 | .98 | 99 | 1.7 | 10 | 0/-18 |
| | 2 | 277 | 75 | 0.27 | .98 | 95 | 1.7 | 10 | 0/-18 |
| FT40W/28W/4P | 3 | 120 | 93 | 0.79 | 1.00 | 99 | 1.7 | 10 | 0/-18 |
| | 3 | 277 | 91 | 0.33 | 1.00 | 95 | 1.7 | 10 | 0/-18 |
| | 2 | 120 | 70 | 0.59 | 1.07 | 99 | 1.7 | 10 | 0/-18 |
| | 2 | 277 | 69 | 0.25 | 1.07 | 95 | 1.7 | 10 | 0/-18 |
| FT40W/25W/4P | 3 | 120 | 85 | 0.73 | 1.00 | 99 | 1.7 | 10 | 0/-18 |
| | 3 | 277 | 84 | 0.31 | 1.00 | 95 | 1.7 | 10 | 0/-18 |
| | 2 | 120 | 64 | 0.53 | 1.11 | 99 | 1.7 | 10 | 0/-18 |
| | 2 | 277 | 63 | 0.23 | 1.11 | 95 | 1.7 | 10 | 0/-18 |

## Safety and Performance

FCC Part 18 Class B | UL Class P | UL Type 1 Outdoor | No PCB's | ANSI Standard C82.11-Cons 2002 | ANSI Standard C62.41-1991

## Understanding **Electromagnetic HID Ballasts**

Current offers High Intensity Discharge (HID) ballasts for mercury, probe start metal halide, pulse start metal halide and high pressure sodium lamps. Standard metal halide lamps or probe start metal halide over 150 watts, like fluorescent, are electric discharge lamps and require an open circuit voltage of nearly two times the operating voltage to the initiate the arc between the two electrodes in the arc tube. High pressure sodium, pulse start metal halide and probe start metal halide lamps 150 watts or less require an ignitor to initiate the high voltage to start the lamps. The ballasts provide the starting voltage with the igniter, where required and provides stability for the lamp. HID lamps have negative impedance characteristics and would draw current until destruction unless a ballast was in place to regulate the current.

HID lamps take several minutes to warm-up and reach full light output. If power is interrupted between the lamp and the ballast, the arc will extinguish and lamp will go out. The lamp must cool down and reduce the vapor pressure before it will re-start. Typical warm-up and restrike times are as follows:

### HID Ballast Types

#### *Core and Coil*

The most common HID ballasts are the core and coil and is used in 90% of the fixture applications. Core and coil ballasts consist of one, two or three copper (or aluminum) coils on a core of electrical-grade steel laminations. HID ballasts are classified by the kind of circuit they use: Reactor (R), High Reactance autotransformer (HX), Constant Wattage Autotransformer (CWA), Regulated lag (Reg Lag) or Electronic. HID ballast are also classified as high power factor (HPF) or normal power factor (NPF).

HID ballast 150 watts or less have High Reactance Autotransformer circuits and high power factor (HX-HPF). HID ballast greater that 150 watts have Constant Wattage Auto transformer circuits and are high power factor (HPF).

CWA ballast is the most common circuit for core and coil ballast. CWA circuits provide for stable light regulation. The CWA circuit consists of a high reactance autotransformer with a capacitor in series with the lamp resulting with high power factor ballast. In most CWA ballast circuits a 10% drop in line voltage will only reduce the light output and wattage by 5%. The CWA circuit ballast requires an igniter for QMH pulse start, ceramic metal halide and HPS lamps. Igniters are also required for QMH lamps 150 watts or less.



## 86675 – GEM100MLTLC3D-5

### Metal Halide

1 – 100W MH M90 or M140 Quad (120/208/240/277V)

- For 100W Metal Halide HID Lamps
- Magnetic ballast construction ideal for a wide variety of lighting applications
- Precision-wound coils, ensuring even heat dissipation and the highest electrical integrity
- Distributor replacement kit contains the appropriate core and coil with color coded leads, a properly rated capacitor and ignitor (if required) and all other components required for ballast replacement

| General Characteristics | |
|---|---|
| Ballast Type | Magnetic – Core and Coil |
| ANSI Lamp Codes | M92, M90, M140 |
| Voltage | 120/208/240/277 |
| Line Voltage Regulation(+/-) | 5% |
| Circuit Type | HX-HPF |
| Insulation Class | 180° C |
| Type of Capacitor | Dry Film |
| Capacitance | 12 Mfd GECAP-12/280V-D |
| Voltage (MIN) | 280 |
| Capacitor Temperature Rating | 100°C (212°F) |
| GE Igniter (Discontinued) | MH350-1A |
| Sound Rating | |
| Additional Info | |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 5.25 in (133 mm) |
| Width (W) | 1.25 in (32 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 4.6 in (117 mm) |
| Mount Width (X or F) | |
| Mount Slots (MS) | 0.25 in (6 mm) |
| A | 2.0 |
| B | 3.0 |
| Weight | 5.0 lbs |
| Exit Type | Side |
| Nominal Length | 2.7 in (69 mm) |
| Frame Size (H x L) | 2.813 in x 3.939 in |

**Specifications by lamp and line voltage**

| Lamp | Specifications by line voltage | 120 | 208 | 240 | 277 |
|---|---|---|---|---|---|
| M92 | System Wattage (W) | 119 | 119 | 119 | 119 |
| | Nominal Current | 1.10A | 0.60A | 0.50A | 0.50A |
| | Ballast Factor | 1 | 1 | 1 | 1 |
| | Ballast Efficiency Factor | | | | |
| | Max Input Current | 2.27A | 1.30A | 1.13A | 0.98A |
| | Starting Current | 1.26A | 0.69A | 0.60A | 0.53A |
| | Open Circuit Voltage | 274V | 274V | 274V | 274V |
| | Drop Out Voltage | 96V | 166V | 192V | 222V |
| | Power Factor (>=) % | 90 | 90 | 90 | 90 |
| | Min. Starting Temp (°F/°C) | -22/-30 | -22/-30 | -22/-30 | -22/-30 |
| | Fuse Rating | 5 | 4 | 3 | 3 |
| | UL Bench Top Rise | D | D | D | D |

| Lamp | Specifications by line voltage | 120 | 208 | 240 | 277 |
|---|---|---|---|---|---|
| M90, M140 100W Ceramic Metal Halide 100W Quartz Metal Halide | System Wattage (W) | 119 | 119 | 119 | 119 |
| | Nominal Current | 1.10A | 0.60A | 0.50A | 0.50A |
| | Ballast Factor | 1 | 1 | 1 | 1 |
| | Ballast Efficiency Factor | 0.84 | 0.84 | 0.84 | 0.84 |
| | Max Input Current | 2.27A | 1.30A | 1.13A | 0.98A |
| | Starting Current | 1.26A | 0.69A | 0.60A | 0.53A |
| | Open Circuit Voltage | 274V | 274V | 274V | 274V |
| | Drop Out Voltage | 96V | 166V | 192V | 222V |
| | Power Factor (>=) % | | 90 | 90 | 90 |
| | Min. Starting Temp (°F/°C) | -22/-30 | -22/-30 | -22/-30 | -22/-30 |
| | Fuse Rating | 5 | 4 | 3 | 3 |
| | UL Bench Top Rise | D | D | D | D |

Safety and Performance cUL Listed UL Listed

## 86718 – GEM150MLTLC3D-5

### Metal Halide

1 – 150W MH M102 or M142 Quad (120/208/240/277V)

- For 150W Metal Halide HID Lamps
- Magnetic ballast construction ideal for a wide variety of lighting applications
- Precision-wound coils, ensuring even heat dissipation and the highest electrical integrity
- Distributor replacement kit contains the appropriate core and coil with color coded leads, a properly rated capacitor and ignitor (if required) and all other components required for ballast replacement
- Quad ballast (120, 208, 240, 277)

| General Characteristics | |
|---|---|
| Ballast Type | Magnetic – Core and Coil |
| ANSI Lamp Codes | M142, M102 |
| Voltage | 120/208/240/277 |
| Line Voltage Regulation(+/-) | 5% |
| Circuit Type | HX-HPF |
| Insulation Class | 180° C |
| Type of Capacitor | Dry Film |
| Capacitance | 16 Mfd GECAP-16/280V-D |
| Voltage (MIN) | 300 |
| Capacitor Temperature Rating | 100°C (212°F) |
| GE Igniter (Discontinued) | MH350-1A |

| Dimensions | |
|---|---|
| Length (L) | 5.25 in (133 mm) |
| Width (W) | 1.25 in (32 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 4.6 in (117 mm) |
| Mount Width (X or F) | |
| Mount Slots (MS) | 0.25 in (6 mm) |
| A | 2.3 |
| B | 4.0 |
| Weight | 7.0 lbs |
| Exit Type | Side |
| Nominal Length | 2.7 in (69 mm) |
| Frame Size (H x L) | 2.813 in x 3.939 in |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 60 Hz |

**Specifications by lamp and line voltage**

| Lamp | Specifications by line voltage | 120 | 208 | 240 | 277 |
|---|---|---|---|---|---|
| M142, M102 150W Ceramic Metal Halide 150W Quartz Metal Halide | System Wattage (W) | 186 | 186 | 186 | 186 |
| | Nominal Current | 1.60A | 1.00A | 0.80A | 0.70A |
| | Ballast Factor | 1 | 1 | 1 | 1 |
| | Ballast Efficiency Factor | 0.81 | 0.81 | 0.81 | 0.81 |
| | Max Input Current | 3.37A | 1.95A | 1.68A | 1.39A |
| | Starting Current | 1.86A | 1.03A | 0.89A | 0.77A |
| | Open Circuit Voltage | 257V | 257V | 257V | 257V |
| | Drop Out Voltage | 96V | 166V | 192V | 222V |
| | Power Factor (>=) % | 90 | 90 | 90 | 90 |
| | Min. Starting Temp (°F/°C) | -22/-30 | -22/-30 | -22/-30 | -22/-30 |
| | Fuse Rating | 10 | 5 | 5 | 4 |
| | UL Bench Top Rise | A | B | A | A |

Safety and Performance cUL Listed UL Listed

## 63078 - GEM175ML5AA3-5

### Metal Halide

1 – 175W MH M57 or M109 5-Tap (120/208/240/277/480V)

- For 175W Metal Halide HID Lamps
- Magnetic ballast construction ideal for a wide variety of lighting applications
- Precision-wound coils, ensuring even heat dissipation and the highest electrical integrity
- 5-tap ballast (120, 208, 240, 277, or 480 volt) featuring a 480-volt tap

| General Characteristics | |
|---|---|
| Ballast Type | Magnetic – Core and Coil |
| ANSI Lamp Codes | M57, H38, M109 |
| Voltage | 120/208/240/277/480 |
| Line Voltage Regulation(+/-) | 10% |
| Circuit Type | CWA |
| Insulation Class | 180° C |
| Type of Capacitor | Oil filled |
| Capacitance | 10 Mfd |
| Voltage (MIN) | 400 |
| Capacitor Temperature Rating | 100°C (212°F) |

| Dimensions | |
|---|---|
| Length (L) | 5.3 in (133 mm) |
| Width (W) | 1.3 in (33 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 4.6 in (117 mm) |
| Mount Width (X or F) | |
| Mount Slots (MS) | 0.3 in (8 mm) |
| A | 3.0 |
| B | 4.0 |
| Weight | 8.0 lbs |
| Exit Type | Side |
| Nominal Length | 3.2 in (83 mm) |
| Frame Size (H x L) | 2.813 in x 3.939 in |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 60 Hz |

**Specifications by lamp and line voltage**

| Lamp | Specifications by line voltage | 120 | 208 | 240 | 277 | 480 |
|---|---|---|---|---|---|---|
| M57, M109 | System Wattage (W) | 202 | 202 | 202 | 202 | 202 |
| | Nominal Current | 1.70A | 1.00A | 0.90A | 0.80A | 0.40A |
| | Ballast Factor | 1 | 1 | 1 | 1 | 1 |
| | Ballast Efficiency Factor | 0.87 | 0.87 | 0.87 | 0.87 | 0.87 |
| | Max Input Current | 1.70A | 1.00A | 0.90A | 0.80A | 0.40A |
| | Starting Current | 0.60A | 0.37A | 0.32A | 0.28A | 0.21A |
| | Open Circuit Voltage | 307V | 307V | 307V | 307V | 307V |
| | Drop Out Voltage | 96V | 166V | 192V | 222V | 384V |
| | Power Factor (>=) % | 90 | 90 | 90 | 90 | 90 |
| | Min. Starting Temp (°F/°C) | -22/-30 | -22/-30 | -22/-30 | -22/-30 | -22/-30 |
| | Fuse Rating | 5 | 3 | 3 | 2 | 1.5 |
| | UL Bench Top Rise | D | C | C | C | C |

Safety and Performance cUL Listed UL Listed

## 87211 – GEM250ML5AC3-5

### Metal Halide

1 – 250W MH M58 5-Tap (120/208/240/277/480V)

- For 250W Metal Halide HID Lamps
- Magnetic ballast construction ideal for a wide variety of lighting applications
- Precision-wound coils, ensuring even heat dissipation and the highest electrical integrity
- Distributor replacement kit contains the appropriate core and coil with color coded leads, a properly rated capacitor and ignitor (if required) and all other components required for ballast replacement
- 5-tap ballast (120, 208, 240, 277, or 480 volt) featuring a 480-volt tap

| General Characteristics | |
|---|---|
| Ballast Type | Magnetic – Core and Coil |
| ANSI Lamp Codes | M58 |
| Voltage | 120/208/240/277/480 |
| Line Voltage Regulation(+/-) | 10% |
| Circuit Type | CWA |
| Insulation Class | 180° C |
| Type of Capacitor | Oil Filled |
| Capacitance | 15 Mfd GECAP-15/400V-O |
| Voltage (MIN) | 400 |
| Capacitor Temperature Rating | 100°C (212°F) |
| GE Igniter (Discontinued) | |
| Sound Rating | |
| Additional Info | |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 5.25 in (133 mm) |
| Width (W) | 1.25 in (32 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 4.6 in (117 mm) |
| Mount Width (X or F) | |
| Mount Slots (MS) | 0.25 in (6 mm) |
| A | 3.0 |
| B | 4.3 |
| Weight | 9.0 lbs |
| Exit Type | Side |
| Nominal Length | 3.2 in (83 mm) |
| Frame Size (H x L) | 2.813 in x 3.939 in |
| **Lead Lengths** | |
| Orange | |
| Violet & Black | |
| Violet/White | |
| Black/Yellow | |

**Specifications by lamp and line voltage**

| Lamp | Specifications by line voltage | 120 | 208 | 240 | 277 | 480 |
|---|---|---|---|---|---|---|
| M58 250W Quartz Metal Halide | System Wattage (W) | 280 | 280 | 280 | 280 | 280 |
| | Nominal Current | 2.50A | 1.40A | 1.25A | 1.10A | 0.65A |
| | Ballast Factor | 1 | 1 | 1 | 1 | 1 |
| | Ballast Efficiency Factor | 0.89 | 0.89 | 0.89 | 0.89 | 0.89 |
| | Max Input Current | 2.60A | 1.60A | 1.30A | 1.20A | 0.70A |
| | Starting Current | 1.50A | 1.00A | 0.80A | 0.70A | 0.50A |
| | Open Circuit Voltage | 290V | 290V | 290V | 290V | 290V |
| | Drop Out Voltage | 96V | 166V | 192V | 222V | 384V |
| | Power Factor (>=) % | 90 | 90 | 90 | 90 | 90 |
| | Min. Starting Temp (°F/°C) | -22/-30 | -22/-30 | -22/-30 | -22/-30 | -22/-30 |
| | Fuse Rating | 8 | 5 | 4 | 3 | 2 |
| | UL Bench Top Rise | B | B | B | C | C |

Safety and Performance cUL Listed UL Listed

## 72300 – GEM400ML5AA4-5/2

### Metal Halide

1 – 400W M59 or H33 5-Tap (120/208/240/277/480V) A1 C&C

- For 400W Metal Halide HID Lamps
- Magnetic ballast construction ideal for a wide variety of lighting applications
- Precision-wound coils, ensuring even heat dissipation and the highest electrical integrity
- Distributor replacement kit contains the appropriate core and coil with color coded leads, a properly rated capacitor and ignitor (if required) and all other components required for ballast replacement
- 5-tap ballast (120, 208, 240, 277, or 480 volt) featuring a 480-volt tap

| General Characteristics | |
|---|---|
| Ballast Type | Magnetic – Core and Coil |
| ANSI Lamp Codes | M59 |
| Voltage | 120/208/240/277/480 |
| Line Voltage Regulation(+/-) | 10% |
| Circuit Type | CWA |
| Insulation Class | Class H, 180°C or Class N, 200°C |
| Type of Capacitor | Oil Filled |
| Capacitance | 24 Mfd GECAP-24/400V-O |
| Voltage (MIN) | 450 |
| Capacitor Temperature Rating | 105°C (221°F) |
| GE Igniter (Discontinued) | |
| Sound Rating | |
| Additional Info | |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 5.25 in (133 mm) |
| Width (W) | 1.25 in (32 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 4.6 in (117 mm) |
| Mount Width (X or F) | |
| Mount Slots (MS) | 0.25 in (6 mm) |
| A | 2.17 |
| B | 3.90 |
| Weight | 10.8 lbs |
| Exit Type | Side |
| Nominal Length | 3.7 in (95 mm) |
| Frame Size (H x L) | 4.25 in x 4.75 in |
| **Lead Lengths** | |
| Orange | |
| Violet & Black | |
| Violet/White | |
| Black/Yellow | |

**Specifications by lamp and line voltage**

| Lamp | Specifications by line voltage | 120 | 208 | 240 | 277 | 480 |
|---|---|---|---|---|---|---|
| M59 400W Quartz Metal Halide 360W Quartz Metal Halide | System Wattage (W) | 461 | 461 | 461 | 461 | 461 |
| | Nominal Current | 4.0A | 2.3A | 2.0A | 1.75A | 1.00A |
| | Ballast Factor | 1 | 1 | 1 | 1 | 1 |
| | Ballast Efficiency Factor | 0.86 | 0.86 | 0.86 | 0.86 | 0.86 |
| | Max Input Current | 4.0A | 2.3A | 2.0A | 1.75A | 1.00A |
| | Starting Current | 3.90A | 3.90A | 3.90A | 3.90A | 3.90A |
| | Open Circuit Voltage | 300V | 300V | 300V | 300V | 300V |
| | Drop Out Voltage | 580V | 580V | 580V | 580V | 580V |
| | Power Factor (>=) % | 90 | 90 | 90 | 90 | 90 |
| | Min. Starting Temp (°F/°C) | -22/-30 | -22/-30 | -22/-30 | -22/-30 | -22/-30 |
| | Fuse Rating | 8 | 5 | 4 | 3 | 2 |
| | UL Bench Top Rise | D or A | D or A | D or A | D or A | D or A |



Safety and Performance cUL Listed UL Listed

# 87213 – GEM1000ML5AA5-5/2

## Metal Halide

1 – 1000W MH M47 5-Tap (120/208/240/277/480V)

- For 1000W Metal Halide HID Lamps
- Magnetic ballast construction ideal for a wide variety of lighting applications
- Precision-wound coils, ensuring even heat dissipation and the highest electrical integrity
- Distributor replacement kit contains the appropriate core and coil with color coded leads, a properly rated capacitor and ignitor (if required) and all other components required for ballast replacement
- 5-tap ballast (120, 208, 240, 277, or 480 volt) featuring a 480-volt tap

| General Characteristics | |
|---|---|
| Ballast Type | Magnetic – Core and Coil |
| ANSI Lamp Codes | M47 |
| Voltage | 120/208/240/277/480 |
| Line Voltage Regulation(+/-) | 10% |
| Circuit Type | CWA |
| Insulation Class | Class H, 180°C or Class N, 200°C |
| Type of Capacitor | Oil Filled |
| Capacitance | 24 Mfd GECAP-24/480V-O |
| Voltage (MIN) | 480 |
| Capacitor Temperature Rating | 105°C (221°F) |
| GE Igniter (Discontinued) | |
| Sound Rating | |
| Additional Info | |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 7.75 in (197 mm) |
| Width (W) | 2.75 in (70 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 6.1 in (155 mm) |
| Mount Width (X or F) | |
| Mount Slots (MS) | 0.25 in (6 mm) |
| A | 3.0 |
| B | 5.0 |
| Weight | 21.0 lbs |
| Exit Type | Side |
| Nominal Length | 3.7 in (95 mm) |
| Frame Size (H x L) | 4.25 in x 6.00 in |
| **Lead Lengths** | |
| Orange | |
| Violet & Black | |
| Violet/White | |
| Black/Yellow | |

**Specifications by lamp and line voltage**

| Lamp | Specifications by line voltage | 120 | 208 | 240 | 277 | 480 |
|---|---|---|---|---|---|---|
| M47 1000W Quartz Metal Halide | System Wattage (W) | 1,050 | 1,050 | 1,050 | 1,050 | 1,050 |
| | Nominal Current | 9.00A | 5.20A | 4.50A | 3.90A | 2.25A |
| | Ballast Factor | 1 | 1 | 1 | 1 | 1 |
| | Ballast Efficiency Factor | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 |
| | Max Input Current | 9.00A | 5.20A | 4.50A | 3.90A | 2.25A |
| | Starting Current | 5.60A | 5.60A | 5.60A | 5.60A | 5.60A |
| | Open Circuit Voltage | 415V | 415V | 415V | 415V | 415V |
| | Drop Out Voltage | 96V | 166V | 192V | 222V | 384V |
| | Power Factor (>=) % | 90 | 90 | 90 | 90 | 90 |
| | Min. Starting Temp (°F/°C) | -22/-30 | -22/-30 | -22/-30 | -22/-30 | -22/-30 |
| | Fuse Rating | 18 | 10 | 9 | 7 | 5 |
| | UL Bench Top Rise | D or A | D or A | D or A | D or A | D or A |

Safety and Performance cUL Listed UL Listed

## 86693 – GEM150048TAC5M5-5

### Metal Halide

1 – 1500W MH M48 480

- For 1500W Metal Halide HID Lamps
- Magnetic ballast construction ideal for a wide variety of lighting applications
- Precision-wound coils, ensuring even heat dissipation and the highest electrical integrity
- Distributor replacement kit contains the appropriate core and coil with color coded leads, a properly rated capacitor and ignitor (if required) and all other components required for ballast replacement

| General Characteristics | |
|---|---|
| Ballast Type | Magnetic – Core and Coil |
| ANSI Lamp Codes | M48 |
| Voltage | 480 |
| Line Voltage Regulation(+/-) | 10% |
| Circuit Type | CWA |
| Insulation Class | 180°C |
| Type of Capacitor | Oil Filled |
| Capacitance | 32 Mfd GECAP-32/525V-O |
| Voltage (MIN) | 525 |
| Capacitor Temperature Rating | 100°C (212°F) |
| GE Igniter (Discontinued) | |
| Sound Rating | |
| Additional Info | |

| Dimensions | |
|---|---|
| Length (L) | 6.0 in (152 mm) |
| Width (W) | 5.8 in (147 mm) |
| Height (H) | 4.3 in (109 mm) |
| Weight | 29.8 lbs |
| Exit Type | Side |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 60 Hz |

**Specifications by lamp and line voltage**

| Lamp | Specifications by line voltage | 480 |
|---|---|---|
| M48 1500W Quartz Metal Halide | System Wattage (W) | 1,581 |
| | Nominal Current | 3.10A |
| | Ballast Factor | 1 |
| | Ballast Efficiency Factor | 0.95 |
| | Max Input Current | 3.10A |
| | Starting Current | 3.18A |
| | Open Circuit Voltage | 449V |
| | Drop Out Voltage | 384V |
| | Power Factor (>=) % | 90 |
| | Min. Starting Temp (°F/°C) | -22/-30 |
| | Fuse Rating | 10 |
| | UL Bench Top Rise | G |

Safety and Performance cUL Listed UL Listed

# 86698 – GEM1500MLTAC5-5

## Metal Halide

1 – 1500W MH M48 Quad (120/208/240/277V)

- For 1500W Metal Halide HID Lamps
- Magnetic ballast construction ideal for a wide variety of lighting applications
- Precision-wound coils, ensuring even heat dissipation and the highest electrical integrity
- Distributor replacement kit contains the appropriate core and coil with color coded leads, a properly rated capacitor and ignitor (if required) and all other components required for ballast replacement
- Quad ballast (120, 208, 240, 277)

| General Characteristics | |
|---|---|
| Ballast Type | Magnetic – Core and Coil |
| ANSI Lamp Codes | M48 |
| Voltage | 240/277 |
| Line Voltage Regulation(+/-) | 10% |
| Circuit Type | CWA |
| Insulation Class | 180°C |
| Type of Capacitor | Oil Filled |
| Capacitance | 32 Mfd GECAP-32/525V-O |
| Voltage (MIN) | 525 |
| Capacitor Temperature Rating | 100°C (212°F) |
| GE Igniter (Discontinued) | |
| Sound Rating | |
| Additional Info | |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 3.9 in (99 mm) |
| Width (W) | 1.0 in (25 mm) |
| Height (H) | 2.8 in (71 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 6.1 in (155 mm) |
| Mount Width (X or F) | |
| Mount Slots (MS) | 0.25 in (6 mm) |
| A | 4.0 |
| B | 6.0 |
| Weight | 30.0 lbs |
| Exit Type | Side |
| Nominal Length | 5.2 in (133 mm) |
| Frame Size (H x L) | 4.25 in x 6.00 in |

**Specifications by lamp and line voltage**

| Lamp | Specifications by line voltage | 120 | 208 | 240 | 277 |
|---|---|---|---|---|---|
| M48 1500W Quartz Metal Halide | System Wattage (W) | 1,602 | 1,602 | 1,602 | 1,602 |
| | Nominal Current | 13.70A | 7.70A | 6.80A | 6.00A |
| | Ballast Factor | 1 | 1 | 1 | 1 |
| | Ballast Efficiency Factor | 0.94 | 0.94 | 0.94 | 0.94 |
| | Max Input Current | 13.70A | 7.70A | 6.80A | 6.00A |
| | Starting Current | 12.95A | 7.46A | 6.52A | 5.75A |
| | Open Circuit Voltage | 440V | 440V | 440V | 440V |
| | Drop Out Voltage | 96V | 166V | 192V | 222V |
| | Power Factor (>=) % | 90 | 90 | | 90 |
| | Min. Starting Temp (°F/°C) | -22/-30 | -22/-30 | -22/-30 | -22/-30 |
| | Fuse Rating | 40 | 25 | 20 | 20 |
| | UL Bench Top Rise | A | A | A | A |

Safety and Performance cUL Listed UL Listed

## 67345 – GEP320MLTAA4-5/2

### Pulse Start

1 – 320W PS M132 or 154 Quad (120/208/240/277V)

- For 320W Pulse Start Metal Halide HID Lamps
- Magnetic ballast construction ideal for a wide variety of lighting applications
- Precision-wound coils, ensuring even heat dissipation and the highest electrical integrity
- Distributor replacement kit contains the appropriate core and coil with color coded leads, a properly rated capacitor and ignitor (if required) and all other components required for ballast replacement
- Quad ballast (120, 208, 240, 277)

| General Characteristics | |
|---|---|
| Ballast Type | Magnetic – Core and Coil |
| ANSI Lamp Codes | M154, M132 |
| Voltage | 120/208/240/277 |
| Line Voltage Regulation(+/-) | 10% |
| Circuit Type | CWA |
| Insulation Class | Class H, 180°C or Class N, 200°C |
| Type of Capacitor | Oil Filled |
| Capacitance | 21 Mfd GECAP-21/345V-O |
| Voltage (MIN) | 370 |
| Capacitor Temperature Rating | 105°C (221°F) |
| GE Igniter (Discontinued) | MH350-1A |
| Sound Rating | |
| Additional Info | |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 5.25 in (133 mm) |
| Width (W) | 1.25 in (32 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 4.6 in (117 mm) |
| Mount Slots (MS) Mount Width (X or F) | 0.25 in (6 mm) |
| A | 1.89 |
| B | 3.60 |
| Weight | 9.50 lbs |
| Exit Type | Side |
| Nominal Length | 3.7 in (95 mm) |
| Frame Size (H x L) | 4.25 in x 4.75 in |

**Specifications by lamp and line voltage**

| Lamp | Specifications by line voltage | 120 | 208 | 240 | 277 |
|---|---|---|---|---|---|
| M48 1500W Quartz Metal Halide | System Wattage (W) | 370 | 370 | 370 | 370 |
| | Nominal Current | 3.10A | 1.80A | 1.55A | 1.34A |
| | Ballast Factor | 1 | 1 | 1 | 1 |
| | Ballast Efficiency Factor | 0.86 | 0.86 | 0.86 | 0.86 |
| | Max Input Current | 3.10A | 1.80A | 1.55A | 1.34A |
| | Starting Current | 3.20A | 3.20A | 3.20A | 3.20A |
| | Open Circuit Voltage | 270V | 270V | 270V | 270V |
| | Drop Out Voltage | 540V | 540V | 540V | 540V |
| | Power Factor (>=) % | 90 | 90 | 90 | 90 |
| | Min. Starting Temp (°F/°C) | -20/-30 | -20/-30 | -20/-30 | -20/-30 |
| | Fuse Rating | 7 | 4 | 3 | 3 |
| | UL Bench Top Rise | A or B | A or C | A or C | A or C |

Safety and Performance cUL Listed UL Listed

## 67347 – GEP400MLTAA4-5/2

### Pulse Start

1 – 400W PS M135/M155 Quad (120/208/240/277V)

- For 400W Pulse Start Metal Halide HID Lamps
- Magnetic ballast construction ideal for a wide variety of lighting applications
- Precision-wound coils, ensuring even heat dissipation and the highest electrical integrity
- Distributor replacement kit contains the appropriate core and coil with color coded leads, a properly rated capacitor and ignitor (if required) and all other components required for ballast replacement
- Quad ballast (120, 208, 240, 277)

| General Characteristics | |
|---|---|
| Ballast Type | Magnetic – Core and Coil |
| ANSI Lamp Codes | M135/M155 |
| Voltage | 120/208/240/277 |
| Line Voltage Regulation(+/-) | 10% |
| Circuit Type | CWA |
| Insulation Class | Class H, 180°C or Class N, 200°C |
| Type of Capacitor | Oil Filled |
| Capacitance | 24 Mfd GECAP-24/400V-O |
| Voltage (MIN) | 450 |
| Capacitor Temperature Rating | 105°C (221°F) |
| GE Igniter (Discontinued) | MH350-1A |
| Sound Rating | |
| Additional Info | |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 5.25 in (133 mm) |
| Width (W) | 1.25 in (32 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 4.6 in (117 mm) |
| Mount Width (X or F) | |
| Mount Slots (MS) | 0.25 in (6 mm) |
| A | 2.17 |
| B | 3.90 |
| Weight | 10.80 lbs |
| Exit Type | Side |
| Nominal Length | 4.6 in (119 mm) |
| Frame Size (H x L) | 4.25 in x 4.75 in |

**Specifications by lamp and line voltage**

| Lamp | Specifications by line voltage | 120 | 208 | 240 | 277 |
|---|---|---|---|---|---|
| M135/M155 | System Wattage (W) | 457 | 457 | 457 | 457 |
| | Nominal Current | 4.00A | 2.30A | 2.00A | 1.75A |
| | Ballast Factor | 1 | 1 | 1 | 1 |
| | Ballast Efficiency Factor | 0.87 | 0.87 | 0.87 | 0.87 |
| | Max Input Current | 4.00A | 2.30A | 2.00A | 1.75A |
| | Starting Current | 3.80A | 3.80A | 3.80A | 3.80A |
| | Open Circuit Voltage | 300V | 300V | 300V | 300V |
| | Drop Out Voltage | 580V | 580V | 580V | 580V |
| | Power Factor (>=) % | 90 | 90 | 90 | 90 |
| | Min. Starting Temp (°F/°C) | -20/-30 | -20/-30 | -20/-30 | -20/-30 |
| | Fuse Rating | 8 | 5 | 4 | 3 |
| | UL Bench Top Rise | A or D | A or D | A or D | A or D |

Safety and Performance cUL Listed UL Listed

# 87214 – GES250ML5AA4-5

## High Pressure Sodium

1 – 250W HPS S50 5-Tap (120/208/240/277/480V)

- For 250W High Pressure Sodium HID Lamps
- Magnetic ballast construction ideal for a wide variety of lighting applications
- Precision-wound coils, ensuring even heat dissipation and the highest electrical integrity
- Distributor replacement kit contains the appropriate core and coil with color coded leads, a properly rated capacitor and ignitor (if required) and all other components required for ballast replacement
- 5-tap ballast (120, 208, 240, 277, or 480 volt) featuring a 480-volt tap

| General Characteristics | |
|---|---|
| Ballast Type | Magnetic – Core and Coil |
| ANSI Lamp Codes | S50 |
| Voltage | 120/208/240/277/480 |
| Line Voltage Regulation(+/-) | 10% |
| Circuit Type | CWA |
| Insulation Class | 180°C |
| Type of Capacitor | Oil Filled |
| Capacitance | 35 Mfd GECAP-35/240V-O |
| Voltage (MIN) | 240 |
| Capacitor Temperature Rating | 100°C (212°F) |
| GE Igniter (Discontinued) | HPS400-3A |
| Sound Rating | |
| Additional Info | |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 5.25 in (133 mm) |
| Width (W) | 1.25 in (32 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 4.6 in (117 mm) |
| Mount Width (X or F) | |
| Mount Slots (MS) | 0.25 in (6 mm) |
| A | 2.0 |
| B | 4.0 |
| Weight | 12.0 lbs |
| Exit Type | Side |
| Nominal Length | 3.7 in (95 mm) |
| Frame Size (H x L) | 4.25 in x 4.75 in |
| **Lead Lengths** | |
| Orange | |
| Violet & Black | |
| Violet/White | |
| Black/Yellow | |

**Specifications by lamp and line voltage**

| Lamp | Specifications by line voltage | 120 | 208 | 240 | 277 | 480 |
|---|---|---|---|---|---|---|
| S50 250W High Pressure Sodium | System Wattage (W) | 292 | 292 | 292 | 292 | 292 |
| | Nominal Current | 2.50A | 1.50A | 1.30A | 1.10A | 0.60A |
| | Ballast Factor | 1 | 1 | 1 | 1 | 1 |
| | Ballast Efficiency Factor | 0.86 | 0.86 | 0.86 | 0.86 | 0.86 |
| | Max Input Current | 2.50A | 1.50A | 1.30A | 1.10A | 0.60A |
| | Starting Current | 1.59A | 0.93A | 0.81A | 0.70A | 0.40A |
| | Open Circuit Voltage | 186V | 186V | 186V | 186V | 186V |
| | Drop Out Voltage | 96V | 166V | 192V | 222V | 384V |
| | Power Factor (>=) % | 90 | 90 | 90 | 90 | 90 |
| | Min. Starting Temp (°F/°C) | -22/-30 | -22/-30 | -22/-30 | -22/-30 | -22/-30 |
| | Fuse Rating | 8 | 5 | 4 | 4 | 4 |
| | UL Bench Top Rise | C | C | B | B | B |

Safety and Performance cUL Listed UL Listed

## 63066 – GES400ML5AA4-5 (replaces 87215)

### High Pressure Sodium

1 – 400W HPS S51 5-Tap (120/208/240/277/480V)

- For 400W High Pressure Sodium HID Lamps
- Magnetic ballast construction ideal for a wide variety of lighting applications
- Precision-wound coils, ensuring even heat dissipation and the highest electrical integrity
- Distributor replacement kit contains the appropriate core and coil with color coded leads, a properly rated capacitor and ignitor (if required) and all other components required for ballast replacement
- 5-tap ballast (120, 208, 240, 277, or 480 volt) featuring a 480-volt tap

| General Characteristics | |
|---|---|
| Ballast Type | Magnetic – Core and Coil |
| ANSI Lamp Codes | S51 |
| Voltage | 120/208/240/277/480 |
| Line Voltage Regulation(+/-) | 10% |
| Circuit Type | CWA |
| Insulation Class | 180°C |
| Type of Capacitor | Oil Filled |
| Capacitance | 55 Mfd GECAP-55/240V-O |
| Voltage (MIN) | 240 |
| Capacitor Temperature Rating | 100°C (212°F) |
| GE Igniter (Discontinued) | HPS400-3A 86641 |
| Sound Rating | |
| Additional Info | |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 5.25 in (133 mm) |
| Width (W) | 1.25 in (32 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 4.6 in (117 mm) |
| Mount Width (X or F) | |
| Mount Slots (MS) | 0.25 in (6 mm) |
| A | 2.0 |
| B | 4.0 |
| Weight | 15.0 lbs |
| Exit Type | Side |
| Nominal Length | 4.2 in (108 mm) |
| Frame Size (H x L) | 4.25 in x 4.75 in |
| **Lead Lengths** | |
| Orange | |
| Violet & Black | |
| Violet/White | |
| Black/Yellow | |

**Specifications by lamp and line voltage**

| Lamp | Specifications by line voltage | 120 | 208 | 240 | 277 | 480 |
|---|---|---|---|---|---|---|
| S51 400W High Pressure Sodium | System Wattage (W) | 472 | 472 | 472 | 472 | 472 |
| | Nominal Current | 4.00A | 2.20A | 2.00A | 1.70A | 1.00A |
| | Ballast Factor | 1 | 1 | 1 | 1 | 1 |
| | Ballast Efficiency Factor | 0.85 | 0.85 | 0.85 | 0.85 | 0.85 |
| | Max Input Current | 4.00A | 2.20A | 2.00A | 1.70A | 1.00A |
| | Starting Current | 2.87A | 1.66A | 1.44A | 1.25A | 0.72A |
| | Open Circuit Voltage | 191V | 191V | 191V | 191V | 191V |
| | Drop Out Voltage | 96V | 166V | 192V | 222V | 384V |
| | Power Factor (>=) % | 90 | 90 | 90 | 90 | 90 |
| | Min. Starting Temp (°F/°C) | -22/-30 | -22/-30 | -22/-30 | -22/-30 | -22/-30 |
| | Fuse Rating | 15 | 8 | 8 | 5 | 5 |
| | UL Bench Top Rise | C | C | C | C | C |

Safety and Performance cUL Listed UL Listed

## 87218 – GES1000ML5AA5-5

### High Pressure Sodium

1 – 1000W HPS S52 5-Tap (120/208/240/277/480V)

- For 1000W High Pressure Sodium HID Lamps
- Magnetic ballast construction ideal for a wide variety of lighting applications
- Precision-wound coils, ensuring even heat dissipation and the highest electrical integrity
- Distributor replacement kit contains the appropriate core and coil with color coded leads, a properly rated capacitor and ignitor (if required) and all other components required for ballast replacement
- 5-tap ballast (120, 208, 240, 277, or 480 volt) featuring a 480-volt tap

| General Characteristics | |
|---|---|
| Ballast Type | Magnetic – Core and Coil |
| ANSI Lamp Codes | S52 |
| Voltage | 120/208/240/277/480 |
| Line Voltage Regulation(+/-) | 10% |
| Circuit Type | CWA |
| Insulation Class | 180°C |
| Type of Capacitor | Oil Filled |
| Capacitance | 26 Mfd GECAP-26/525V-O |
| Voltage (MIN) | 525 |
| Capacitor Temperature Rating | 100°C (212°F) |
| GE Igniter (Discontinued) | HPS1000-4B |
| Sound Rating | |
| Additional Info | |

| Electrical Characteristics | |
|---|---|
| Supply Current Frequency | 60 Hz |

| Dimensions | |
|---|---|
| Length (L) | 7.75 in (197 mm) |
| Width (W) | 2.75 in (70 mm) |
| **Mounting Dimensions** | |
| Mount Length (M) | 6.1 in (155 mm) |
| Mount Width (X or F) | |
| Mount Slots (MS) | 0.25 in (6 mm) |
| A | 4.0 |
| B | 6.0 |
| Weight | 28.0 lbs |
| Exit Type | Side |
| Nominal Length | 4.7 in (121 mm) |
| Frame Size (H x L) | 4.25 in x 6.00 in |
| **Lead Lengths** | |
| Orange | |
| Violet & Black | |
| Violet/White | |
| Black/Yellow | |


**Specifications by lamp and line voltage**

| Lamp | Specifications by line voltage | 120 | 208 | 240 | 277 | 480 |
|---|---|---|---|---|---|---|
| S52 1000W High Pressure Sodium | System Wattage (W) | 1,102 | 1,102 | 1,102 | 1,102 | 1,102 |
| | Nominal Current | 9.50A | 5.50A | 4.70A | 4.10A | 2.40A |
| | Ballast Factor | 1 | 1 | 1 | 1 | 1 |
| | Ballast Efficiency Factor | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 |
| | Max Input Current | 9.50A | 5.50A | 4.70A | 4.10A | 2.40A |
| | Starting Current | 5.75A | 3.40A | 2.90A | 2.60A | 1.80A |
| | Open Circuit Voltage | 435V | 435V | 435V | 435V | 435V |
| | Drop Out Voltage | 96V | 166V | 192V | 222V | 384V |
| | Power Factor (>=) % | 90 | 90 | 90 | 90 | 90 |
| | Min. Starting Temp (°F/°C) | -22/-30 | -22/-30 | -22/-30 | -22/-30 | -22/-30 |
| | Fuse Rating | 20 | 15 | 10 | 10 | 8 |
| | UL Bench Top Rise | D | D | D | D | D |



Safety and Performance cUL Listed UL Listed

**Lamp Size/Diameter**
The diameter of a lamp, at its maximum dimension, is expressed in eighths of an inch. Examples: The diameter of an A19 lamp is 19-eighths of an inch, or 2-3/8", at its widest point. A T8 lamp has a diameter of 8-eighths, or one inch.




**Important Notice**
This catalog is a compilation of accumulated data. Additional information is constantly being uncovered through research and testing, which may modify the data given herein. This is particularly true of newer lamps and ballasts. Accordingly, SPECIFICATIONS ARE SUBJECT TO CHANGE WITHOUT NOTICE. For the latest lamp and ballast design data and information, contact your Current representative.

The data and suggested applications contained in this catalog, as well as any additional information our representative may be able to furnish, are for general information only and are not intended and should not be taken as representations or warranties as to the suitability of a lamp or ballast for any particular application or use in any particular equipment, nor are our representatives authorized to make any such warranties. Applications and conditions of use are many and varied, and beyond our control. We cannot possibly have the same degree of knowledge that the purchaser has with respect to the design of his equipment and the conditions of its use. Therefore, it is up to the purchaser to make its own determination as to the suitability of a lamp or ballast for his intended application or use and to assume the responsibility for that determination.

Current desires to supply the best possible products at all times. For this reason, Current reserves the right to make changes in its products and to introduce new products or discontinue existing ones without notice.

# **GLOSSARY** OF TERMS

**Ambient Temperature**
Ambient temperature which refers to the temperature inside the fixture in the air surrounding the fluorescent lamp or LED. Fluorescent lamp light output and LED life are affected by the ambient temperature.

**Amperes**
("Amps") A measure of electrical current. In incandescent lamps, the current is related to voltage and power as follows: Watts (power) = Volts x Amps (current).

**ANSI (American National Standards Institute)**
A consensus-based organization which coordinates voluntary standards for the physical, electrical and performance characteristics of lamps, ballasts, luminaires and other lighting and electrical equipment.

**ANSI Ballast Type**
A reference to the ANSI document describing the lamp which also lists the characteristics of the ballast required to operate the lamp. Technically, therefore, it is incorrect to refer to "Ballast Type" with the ANSI code but this misuse is common. The following naming system is used: H – mercury lamps; M – metal halide lamps; S – high pressure sodium lamps; L – low pressure sodium lamps.

**Ballast**
An auxiliary piece of equipment required to start and to properly control the flow of current to gas discharge light sources such as fluorescent and high intensity discharge (HID) lamps. Typically, magnetic ballasts (also called electromagnetic ballasts) contain copper windings on an iron core while electronic ballasts are smaller and more efficient and contain electronic components.

**Ballast Efficacy Factor (BEF)**
Defined as ballast factor x 100 divided by input watts. The value is used to evaluate various lighting systems based on light output and power input. The BEF can only be used to compare systems operating the same type and quantity of lamps.

**Ballast Factor (BF)**
This is the percentage of a lamp's rated lumen output that can be expected when operated on a specific, commercially available ballast. Note that the "rated output" is sometimes measured on a reference ballast unlike ones that actually operate the lamp in the field. For example, a ballast with a ballast factor of 0.93 will result in the lamp's emitting 93% of its rated lumen output. A ballast with a lower BF results in less light output and also generally consumes less power.

**Beam Angle**
The angular dimension of the cone of light from reflectorized lamps (such as R and PAR types) encompassing the central part of the beam out to the angle where the intensity is 50% of maximum. The beam angle (sometimes called "beam spread") is often part of the ordering code for reflectorized lamps. Example: The 50PAR30/HIR/NFL25 is a 50 watt PAR30 narrow flood lamp with a beam angle of 25 degrees, i.e. 12.5 degrees on either side of the center (see FIELD ANGLE).

**Bi-Pin**
Any base with two metal pins for electrical contact. This is the typical base for a fluorescent tube of 1 to 4 feet in length. It consists of 2 prong contacts that connect into the fixture. Medium bi-pins are used with type T-8 and T-12 tubular fluorescent lamps and miniature bi-pins are used for tubular T-5 fluorescent lamps.

**Candela (cd)**
The measure of luminous intensity of a source in a given direction. The term has been retained from the early days of lighting when a standard candle of a fixed size and composition was defined as producing one candela in every direction. A plot of intensity versus direction is called a candela distribution curve and is often provided for reflectorized lamps and for luminaires with a lamp operating in them.

**Candlepower**
An obsolete term for luminous intensity; current practice is to refer to this simply as candelas (see CANDELA).

**Center Beam Candlepower (CBCP)**
Refers to the luminous intensity at the center of the beam of a blown or pressed reflector lamp (such as a PAR lamp). Measured in candelas (see CANDELA).

**Color Rendering Index (CRI)**
A measure of the ability of a light source to render object colors faithfully in comparison with a designated standard light source. Incandescent objects and daylight are both considered "standard" sources. Note that "standard" is defined for convenience in reproducibility rather than being based on user preference.

**Color Temperature (Correlated Color Temperature – CCT)**
A number indicating the degree of "yellowness" or "blueness" of a white light source. Measured in Kelvins, CCT represents the temperature an incandescent object (like a filament) must reach to mimic the color of the lamp. Yellowish-white ("warm") sources, like incandescent lamps, have lower color temperatures in the 2700K–3000K range; white and bluish-white ("cool") sources, such as cool white (4100K) and natural daylight (6000K), have higher color temperatures. The higher the color temperature the whiter, or bluer, the light will be.

**Crest Factor (Lamp Current Crest Factor)**
Ratio of peak to RMS for any AC waveform. Crest factor can refer to voltage crest factor or current crest factor.

**Current Type (AC/DC)**
Whether the operational voltage is based on Alternating Current or Direct Current.

**Efficacy**
A measurement of how effective the light source is in converting electrical energy to lumens of visible light. Expressed in lumens-per-watt (LPW), this measure gives more weight to the yellow region of the spectrum and less weight to the blue and red regions where the eye is not as sensitive. The efficiency of a light source is simply the fraction of electrical energy converted to light, i.e. watts of visible light produced for each watt of electrical power with no concern about the wavelength where the energy is being radiated. For example, a 100-watt incandescent lamp converts 7% of the electrical energy into light; discharge lamps convert 25% to 40% into light.

**Efficiency**
The efficiency of a light source is simply the fraction of electrical energy converted to light, i.e. watts of visible light produced for each watt of electrical power with no concern about the wavelength where the energy is being radiated. For example, a 100-watt incandescent lamp converts 7% of the electrical energy into light; discharge lamps convert 25% to 40% into light. The efficiency of a luminaire or fixture is the

**Efficiency (Continued)**
percentage of the lamp lumens that actually comes out of the fixture (see LUMINAIRE EFFICIENCY).

**Electromagnetic Spectrum**
A continuum of electric and magnetic radiation that can be characterized by wavelength or frequency. Visible light encompasses a small part of the electromagnetic spectrum in the region from about 380 nanometers (violet) to 770 nanometers (red) by wavelength.

**Electromagnetic Interference (EMI)**
High-frequency electronic ballasts and other electronic devices can produce a small amount of radio waves that can interfere with radio and TV. Federally-mandated requirements must be met for EMI levels before an electronic device is considered FCC compliant (FCC is the Federal Communications Commission).

**Federal Communications Commission (FCC)**
The U. S. federal agency that regulates emissions in the radio frequency portion of the electromagnetic spectrum. Part 18 of the FCC rules specifies electromagnetic interference (EMI) from lighting devices at frequencies greater than 450 kilohertz (kHz). A consumer-rated Class B ballast is designed for use in the home near TV and radio receivers. It produces less electrical noise that could interfere with consumer products. A Class A-rated ballast is designed for use in commercial and industrial applications that are not in the vicinity of TV and radio receivers.

**Field Angle**
The angular dimension of the cone of light from reflectorized lamps (such as R and PAR types) encompassing the central part of the beam out to the angle where the intensity is 10% of maximum (see BEAM ANGLE).

**Footcandle (fc)**
A unit of illuminance or light falling onto a surface. It stands for the light level on a surface one foot from a standard candle. One footcandle is equal to one lumen per square foot (see LUX).

**Frequency**
Rate of alternation in an AC current. Expressed in cycles per second or Hertz (Hz).

**Glare**
Visual discomfort caused by excessive brightness is called discomfort glare. If task performance is affected it is called disability glare. Glare can be direct glare or indirect (reflected) glare.

**Harmonic**
An integral multiple of the fundamental frequency (60 Hz) that becomes a component of the current. Harmonic Distortion (see TOTAL HARMONIC DISTORTION or THD).

**Hertz (Hz)**
Unit used to measure frequency of alteration of current or voltage, in cycles per second.

**Ignitor**
An electronic device providing a high voltage pulse to initiate an electrical discharge. Typically, the ignitor is paired with or is a part of the ballast.

**Illuminance**
The "density" of light (lumens/area) incident on a surface; i.e. the light level on a surface. Illuminance is measured in footcandles or lux.

**Input Voltage**
Power supply voltage required for proper operation of fluorescent or HID ballast.

**Input Watts**
The total power input to the ballast that includes lamp watts and ballast losses. The total power input to the fixture is the input watts to the ballast or ballasts and is the value to be used when calculating cost of energy and air conditioning loads. More than 90% of the input watts is wattage or power delivered to the lamp load with typical ballast.

**Instant Start**
A type of ballast designed to start fluorescent lamps as soon as the power is applied. Most T8 fluorescent lamps are being operated on electronic instant-start ballasts. Slimline fluorescent lamps operate only on instant-start circuits.

**Kelvins** (see COLOR TEMPERATURE).

**L70, L85, etc.**
L70 (or L85, etc.): The elapsed operating time over which a population of LED light sources will maintain 70% (or 85%) of its initial light output. This 70% number represents the expected median light output (which is close to the average light output) of the tested LED light source population. The value is often stated using the form L70(10K)= 50,000 Hours; this means that the LED light source's median light output reaches 70% of the initial light output at 50,000 Hours based on 10,000 hours of test data using TM-21 projection methods. When the L70 value is stated as "Reported" it means that tests have gone to at least 1/6th of the reported time as required by IESNA's TM-21 methodology. On the other hand, manufacturers will sometimes state a "Calculated" value of L70 which means they are using mathematical curve fitting and projection methods of TM-21 to project beyond 6 times the available test hours.

**Lamp Watts**
Power dissipated in the lamp—some of which is converted to light, some to heat and some to ultraviolet.

**LED**
Light Emitting Diode used as the primary light source in a wide array of LED lighting products. Also referred to as SSL (Solid State Lighting).

**LED Tube Beam Angle**
The angle between the two opposite directions in which the average intensity is 50% of the center beam intensity as measured in the azimuthal plane perpendicular to and at the center of the linear replacement lamp axis.

**Life** (see RATED LAMP LIFE).

**Light Center Length (L.C.L.)**
The distance between the center of the filament, or arc tube and a reference plane—usually the bottom of the lamp base.

**Light Emitting Diode (LED)**
A solid that directly converts electrical impulses into light.

**LM79**
Test procedures specified by the Illuminating Engineering Society for measurements on LED products (complete assembled systems) of lumens, watts and color in actual operating environments.

**LM80**
Test procedures specified by the Illuminating Engineering Society for measuring lumen depreciation of LED sources, arrays and modules—not luminaires.

**Lumen**
A measure of luminous flux or quantity of light emitted by a source.

**Lumen Depreciation, Lumen Maintenance**
A measure of how well a lamp maintains its light output over time. It may be expressed numerically or as a graph of light output vs. time. The "mean lumens" of a lamp is the lumens at 40% of rated life (50% for HPS lamp).

**Lumens Per Watt (LPW)**
A ratio expressing the luminous efficacy of a light source.

**Luminance**
A photometric measure of "brightness" of a surface as seen by the observer, measured in candelas per square meter.

**Luminous Efficacy**
The light output (lumens) of a light source divided by the total power input (watts) to that source. It is expressed in lumens per watt (see LUMENS PER WATT).

**Lux (lx)**
A unit of illuminance or light falling onto a surface. Lux stands for the light level on a surface one meter from a standard candle. One lux is equal to one lumen per square meter. Ten lux approximately equals one footcandle (see FOOTCANDLE).

**Maximum Overall Length (M.O.L.)**
The end-to-end measurement of a lamp, expressed in inches or millimeters.

**Mean Lumens**
The average light output of a lamp over its rated life. Based on the shape of the lumen depreciation curve, for fluorescent and metal halide lamps, mean lumens are measured at 40% of rated lamp life. For mercury, high-pressure sodium and incandescent lamps, mean lumen ratings refer to lumens at 50% of rated lamp life (see LUMEN MAINTENANCE).

**Medium Base**
Usually refers to the screw base typically used in household incandescent lamps. There is also the medium bi-pin base commonly used in T12 and T8 fluorescent lamps.

**Mogul Base**
A screw base used on larger lamps, e.g. many HID lamps.

**PAR Lamp**
PAR is an acronym for parabolic aluminized reflector. A PAR lamp, which may utilize either an incandescent filament, a halogen filament tube or an HID arc tube, is a precision pressed-glass reflector lamp. PAR lamps rely on both the internal reflector and prisms in the lens for the control of the light beam. Today it is common to refer to LED replacement products for PAR lamps as "LED PAR Lamps" even though there may be no parabolic reflector in the package.

**Parallel Lamp Operation/Parallel Wiring**
Refers to ballasts that employ multiple output current paths from a single ballast to allow lamps to operate independent of one another, allowing other lamps operated by the ballast to remain lit should companion lamp(s) fail (see SERIES LAMP OPERATION).

**PCB (Polychlorinated Biphenyls)**
Chemical pollutant formerly used in ballast capacitors that were part of ballasts. It is now illegal to use PCBs and most such ballasts have been replaced over time.

**Photopic** (see SCOTOPIC/PHOTOPIC).

**Power Factor (PF)**
A measure of the phase difference between voltage and current drawn by an electrical device, such as a ballast or motor. Power factors can range from 0 to 1.0 with 1.0 being ideal. Power factor is sometimes expressed as a percent. Incandescent lamps have power factors close to 1.0 because they are simple "resistive" loads. The power factor of a fluorescent and HID lamp system is determined by the ballast used. "High" power factor usually means a rating of 0.9 or greater. Power companies may penalize users for using low-power-factor devices.

**Preheat Circuit**
A type of fluorescent lamp-ballast circuit used with the first commercial fluorescent lamp products. A push button or automatic switch is used to preheat the lamp cathodes. Starting the lamp can then be accomplished using simple "choke" or reactor ballasts. A preheat fluorescent lamp is one in which the filament must be heated by use of a starter before the arc is created. These lamps are typically operated with electromagnetic ballasts.

**Programmed Rapid Start**
Lamp starting method which preheats the lamp filaments while not allowing the lamp to ignite and then applies the open circuit voltage (OCV) to start the lamp. The user may experience a half- to one-second delay after turning on the lamps while the preheating takes place. This type of starting circuit keeps lamp end blackening to a minimum and improves lamp life performance, especially in applications where the lamps are frequently switched on and off.

**Pulse Start**
A lamp that requires an HID ballast with a high-voltage ignitor to start the lamp.

**Rapid Start**
Lamp starting method in which lamp filaments are heated while open circuit voltage (OCV) is applied to facilitate lamp ignition. A Rapid Start fluorescent lamp has two pins at each end connected to the filament. Some rapid start lamps may be instant-started without filament heat, for example, the F32T8 lamp.

**Rated Lamp Life**
For most lamp types, rated lamp life is the length of time of a statistically large sample between first use and the point when 50% of the lamps have died (see L70 for LED Lamps).

**Reflector Lamp (R)**
A light source with a built-in reflecting surface. Sometimes, the term is used to refer specifically to blown bulbs like the "R" and "ER" lamps; at other times, it includes all reflectorized lamps like PAR and MR.

**Series Lamp Operation**
Refers to ballasts that employ a single current path passing through all lamps operated by the ballast. If one lamp should fail, companion lamps operated by the same ballasts will also extinguish or dim.

**Specification Series (SP) Colors**
Energy-efficient, all-purpose tri-phosphor fluorescent lamp colors that provide good color rendering. The CRI for SP colors is 70 or above and varies by specific lamp type.

**Specification Series Deluxe (SPX) Colors**
Energy-efficient tri-phosphor fluorescent lamp colors that provide better color rendering than Specification Series (SP) colors. The CRI for SPX colors is 80 or higher and varies by specific lamp type.

**Spectral Power Distribution (SPD)**
A graph of the radiant power emitted by a light source as a function of wavelength. SPDs provide a visual profile or "fingerprint" of the color characteristics of the source throughout the visible part of the spectrum. Also called "spectral curve" or "spectrum."

**TCLP Test**
The Toxicity Characteristic Leaching Procedure (TCLP) test, specified in the Resource Conservation and Recovery Act (RCRA) of 1990, is used to characterize fluorescent lamp waste as hazardous or nonhazardous waste. The TCLP test measures the ability of the mercury and/or lead in a lamp to leach from a landfill into ground water.

**THD** (see TOTAL HARMONIC DISTORTION).

**TM21**
Technical Memorandum developed by the Illuminating Engineering Society to provide method for projecting lumen maintenance of an LED source, array or module as a function of temperature. This will allow LED Luminaire manufacturers to predict lumen depreciation in their fixtures, based on the operating temperature of the LED in that package. See also, "L70, L85, etc."

**Total Harmonic Distortion (THD)**
A measure of the distortion of the input current on alternating current (AC) power systems caused by higher order harmonics of the fundamental frequency (60Hz in North America). THD is expressed in percent and may refer to individual electrical loads (such as a ballast) or a total electrical circuit or system in a building. ANSI C82.77 recommends THD not exceed 32% for individual commercial electronic ballasts, although some electrical utilities may require lower THDs on some systems. Excessive THDs on electrical systems can cause efficiency losses as well as overheating and deterioration of system components.

**Voltage**
A measurement of the electromotive force in an electrical circuit or device expressed in volts. Voltage can be thought of as being analogous to the pressure in a waterline.

**Watt**
A unit of electrical power. Lamps are rated in watts to indicate the rate at which they consume energy.

# **COLOR** SAMPLES

The following pages are provided for comparing light sources. Recent studies have found that color preference is largely dictated by color fidelity and saturation, with reds being particularly important. Current's TriGain® technology provides superior color and performance.








## 99 Color Samples



## 99 Color Samples



**Notes:**

Current

ALBEO

DAINTREE WIRELESS CONTROLS

EVOLVE

FORUM

GE LAMPS

GTX

IMMERSION

LIGHTGRID

LIGHTSWEEP

LUMINATION

TETRA

**Current - GLI Brands**
6085 Parkland Blvd
Mayfield Heights, OH 44124

**LED.com/Lamps**

© 2026 Current Lighting Solutions, LLC. All rights reserved. GE and the GE monogram are trademarks of the General Electric Company and are used under license. Information and specifications subject to change without notice. All values are design or typical values when measured under laboratory conditions.

(Rev 05/19/2026)
**GEL207-GE-Lamps-Catalog_R40**